

Environmental Best Management Practices & Design Standards

2016



Prepared by:
City of Bellevue Parks & Community Services
Natural Resource & Resource Management Divisions
(425) 452-6855



Acknowledgements

Thank you to everyone who contributed to this document's development and creation. It could not have been done without the time, input and expertise of everyone involved.

Parks Natural Resource Division
Parks Resource Management Division
Parks Planning Division
Utilities Department
Developmental Services Department




Table of Contents

Acknowledgements i

Introduction iii

How to Use This Manual..... iv

Chapter 1: Construction Site Management 1

Chapter 2: Stormwater Pollution Prevention Plan for Park Operations 9

Chapter 3: Integrated Pest Management (IPM) 17

Chapter 4: Irrigation and Water Management 45

Chapter 5: Nursery Operations 53

Chapter 6: Planting Bed Management 57

Chapter 7: Turf Management..... 65

Chapter 8: Streetscape Management 73

Chapter 9: Trees & Natural Areas 93

Chapter 10: Trail System Management 113

Chapter 11: Agricultural Areas 121

Glossary 129

References 134

Appendices

1. Parks & Community Services Water Shortage Response Plan
2. Parks & Community Services Standard Detail Drawings

Introduction

This manual was written to provide clear direction on standard operational procedures and design features; to effectively communicate the operational practices of the Parks & Community Services Department (Parks) to the public; and to respond to regional, state and federal environmental issues. Proper care and maintenance, as well as the understanding of certain practices and systems, is essential in perpetuating the longevity and usefulness of our park resources.

The Parks & Community Services Department's mission is to contribute to a healthy community through an integrated system of exceptional parks, open space, recreational, cultural and human services. This mission is based on the Parks and Community Services Department's philosophy to:

- Protect and preserve environmentally sensitive natural areas;
- Provide connections for an integrated open space system;
- Enhance the City's visual character throughout the park system by perpetuating the "City in a Park" ideal;
- To acquire and develop park facilities to meet the present and future needs of the community; and
- To renovate or modify parks for optimum use of resources.

The goals of the Parks & Community Services Department are to ensure the safety of citizens, protect water quality, provide for recreation, preserve wildlife habitat, buffer land uses and improve landscape conditions. All park designers, planners, managers, crews and contractors are required to use water efficiently; implement the principles of IPM; reduce and reuse landscape waste materials; minimize negative impacts on aquatic environments and soil organisms; design and renovate landscape areas to suit the site conditions; and restore, create and protect environmentally rich areas such as wetlands and riparian corridors, and aquatic, wildlife, forest and meadow habitats.

The Parks & Community Services Department is the single largest land owner and manager in Bellevue, with over 3,000 acres of property. Of this, approximately 800 acres are in developed park sites, with various amenities such as: beaches, golf courses, sport-fields/courts, community centers, and City buildings. The remaining 2,200 acres are in natural areas comprised of forests, steep slopes, wetlands and meadows. Parks also manages 46 acres of farmland and 120 acres of street tree and arterial landscapes within the City's developed right-of-ways.

In order to continue to improve the standard of care and our maintenance practices, the Parks Department will review and revise this manual every 4 years. Any changes, modifications, or comments regarding these best management practices, should be directed to the Natural Resource & Resource Management Divisions.

Sincerely,



Patrick Foran, Director
Parks & Community Services Department

How to Use This Manual

This manual represents present day ideals and should be seen as a flexible document that can readily adapt to new environmental information and management technologies. The wording of this manual has been carefully selected. "Shall" and "will" have been selected to indicate those activities that are performed as management practices. The verb "should" prescribes practices the Department should be performing to adequately care for the resources base.

In an effort to better organize this information, this manual has been divided into 11 chapters that collectively represent the breadth of the Parks & Community Services Department's maintenance operational responsibilities. Each chapter has a consistent section format, as follows:

Section 1 – Purpose

Discusses the inventory of the resource being managed and describes the level of detail known about the resource. It explains the objectives for which that specific resource is managed and the role it serves in the community. This section also presents any of the environmental risks associated with the management of that resource and the effect it has on air and water quality.

Section 2 – Background

Provides background information about the resource, including: design elements considered during creation, renovation or enhancement of the resource; and relevant policies.

Section 3 – BMPs

Outlines the specific Best Management Practices (BMPs) associated with the resource. BMP can be defined as: a clear and consistent set of directions to Parks staff for the management and maintenance of resource areas and the individual assets contained within those areas. Resource areas within the City of Bellevue parklands include landscape, horticulture and urban forest categories. This section also includes safety and risk management procedures and equipment requirements, if applicable.

Section 4 – Training

Notes training needed or required.

CHAPTER 1 – Construction Site Management



1.1 Purpose

The purpose of this section is to identify the management practices that should be employed at construction sites to guarantee a successful project before, during and through a lifetime of site use and maintenance. The Bellevue Parks & Community Services Department manages construction sites to preserve existing vegetation and infrastructure for several reasons:

- To sustain both the function and value of vegetation assets.
- To enhance public safety by carefully maintaining the health of onsite vegetation and to reduce liability.
- To contain costs associated with site restoration.
- To reduce or avoid soil compaction and degradation.
- To avoid physical injury to existing trees.
- To avoid root injury to trees and other vegetation.
- To protect soils and hydraulic integrity of the entire site.
- To protect existing irrigation, utilities and underground drainage.
- To prevent sediment laden and/or polluted runoff from entering drainage systems and water bodies (streams, wetlands, lakes).

1 Construction Site Management

1.2 Background

Many problems encountered in landscape maintenance can be traced to poor management of original construction. If construction equipment improperly strikes or grades over vegetation, those plants often suffer or die. If a site's soil is overly compacted or contaminated, it will not allow the air and water movement essential for healthy root zones and plants. If hydrologic processes on site are disrupted, the site may forever have drainage problems. These and other construction related impacts can produce long-term maintenance problems that can be avoided by following the BMPs set forth in the remainder of this section.

1.3 Best Management Practices

Pre-Construction

The project manager shall consult with DSD and acquire all necessary permits for each specific construction project. The project manager will coordinate all required code enforcement inspections with DSD staff.

- National Pollutant Discharge Elimination System (NPDES) requirements for erosion control shall be established prior to construction. Specific requirements of NPDES are covered in Chapter 2 – Stormwater Pollution Protection Plan (SWPPP) for Park Operations.
- The project manager shall know and understand the development and building regulations concerning trees and vegetation in the area.
- The project manager will contact "Dial-Before-You-Dig" (1-800-424-5555 or 811) to locate any underground utilities onsite before construction begins.
- The project manager will be responsible for decisions related to vegetation on site before and during removal.
- The site shall be inventoried and surveyed if necessary. Site inventory includes determining size, species, and numbers of trees/plants on site; locating irrigation and drainage systems and problems, if any, of root intrusions into the drainage and other utility systems. Property corners shall also be identified, if necessary, prior to work.
- The project manager shall ensure that irrigation and drainage systems are operable and adequate.
- The project manager shall identify and protect natural water flows and drainage patterns and maintain vegetated buffers.

- An erosion control plan and turbidity monitoring plan for projects near streams and wetlands shall be developed as necessary.
- All trees and plants to be preserved and protected shall be identified on site plans.
- The project manager should consult the site manager(s) for site history and maintenance prior to finalization of site plans.

Construction Site Preparation

- Staging areas for equipment shall be established far enough from plant material so that existing plants and their roots are protected.
- Entry and exit routes shall be established and fenced off with chain link or construction fencing. When planning routes, avoid utility access corridors.
- 6' high chain-link fencing, or other adequate tree protection fencing, shall be installed around the tree protection zone (TPZ) and any other vegetation that will remain onsite. At the discretion of the project manager, the fencing shall be installed at least 1 foot out from the trunk for every inch diameter of the existing trees or farther.
- If tree protection cannot be installed at the predetermined TPZ because of site constraints, the fencing can be moved no closer than the critical root zone (CRZ) and an adequate root buffer shall be constructed in the affected area of the TPZ.
- Irrigation and drainage systems shall be protected from damage unless plans call for renovation of such systems.
- All trees and plants in the construction zone shall be pruned as necessary to remove deadwood and prevent damage from construction equipment.
- Trees/plants to be preserved shall be watered and fertilized before and after construction at the discretion of the project manager.

Construction

Trees vary in their ability to adapt to altered growing conditions. Mature trees have established stable biological systems in the pre-existing physical environment. Disruption of this environment by construction activities interrupts the tree's physiological processes causing depletion of energy reserves and a decline in vigor, often resulting in the tree's death. Typically, this reaction may develop from one to seven years after disruption. The tree protection BMPs are intended to eliminate undesirable consequences that result from uninformed or careless acts and preserve both trees and property values. The following BMPs, if followed, will reduce the negative impacts of park construction on trees:

- Tree protection fencing will be constructed at the outer limit of the TPZ. If the fencing must enter inside the TPZ, root buffer will be constructed. One

1 Construction Site Management

- warning sign will be displayed for every 15 feet of lineal fencing, facing toward the work area. No activity is allowed in the CRZ of the trees being protected.
- On occasion, trees will need to have branches pruned in order to facilitate access to a construction site or the construction of a new facility. Pruning will follow International Society of Arboriculture Pruning Guidelines.
 - Trenching and excavation activities are prohibited within the TPZ.
 - When utility installation must occur within the TPZ, tunneling shall be the preferred method to install such utilities. The tunnel shall be dug either by hand, air spade, hydraulic vacuum or mechanically boring the tunnel under the roots with a horizontal directional drill and hydraulic or pneumatic air excavation technology.
 - Construction shall be monitored regularly to ensure compliance with specifications. Work shall be stopped if construction site management BMP's are not being followed by the contractor.
 - Cement washout pits and chemical holding areas shall be located away from vegetation protection areas, streams and wetlands.
 - Contractor parking and material storage shall be limited to already impacted areas away from tree roots.
 - Site offices and equipment shall not encroach into vegetation protection areas.
 - Whenever possible, control and minimize grade changes within vegetation protection areas. Generally, no changes in grade should occur within the TPZ of any tree to remain on site. This area may be increased at the discretion of the project manager. If the grade must be raised around a desired tree, a dry well shall be constructed around the tree at the drip line or some point farther out.
 - Refueling and maintenance areas shall be kept away from trees, native soils, water bodies and drainage systems. Fuel spills will not be tolerated on construction sites. If pollutants leak or are discharged into a water-body, the City of Bellevue Clearing and Grading Inspector, as well as the Department of Ecology shall be contacted.
 - To the extent possible, construction equipment shall be kept away from all onsite vegetation, especially those within designated protection areas. TESC implementation, maintenance, and removal shall follow COB regulations.

Post-Construction

Maintaining preserved and establishing new vegetation is the primary focus following construction. This requires identifying problems and treatments that may

preserve these resources. If warranted, severely damaged vegetation should be removed and replaced by the contractor at their expense with new plantings.

The following practices should be employed to preserve vegetation:

- Weekly water management (most important item), at least 1" per week between May 1st – Sept. 30th, corresponding with drier weather.
- Insure contractor compliance with plant establishment warranty period.
- Fertilize with an appropriate product, as needed.
- Wait one growing season for pruning and minimal nitrogen applications. Maintain levels for 3 to 5 years.
- Maintain a depth of 2 to 3 inches of mulch around trees and shrubs, and new plantings.
- Watch closely for pests and changes in plant structure. Preventative treatments may be advisable.
- Maintenance staff shall closely monitor and inspect all new construction throughout the warranty period to ensure plant establishment.
- Special emphasis will be placed on weed control during the plant establishment period (3 to 5 years).
- For enhancement projects completed within Sensitive/Critical Areas or Sensitive/Critical Area Buffers, the project manager shall coordinate all monitoring protocol as established and enforced by DSD. Specific information concerning Sensitive/Critical Area management is covered in chapter 9 – Forests and Natural Areas.

Mitigating Tree Infrastructure Conflicts

Conflicts may occur when tree roots grow adjacent to paving, foundations, sidewalks or curbs (hardscape). Improper or careless extraction of these elements can cause severe injury to the roots and instability or even death of the trees. The following alternatives must first be considered before root pruning within the TPZ of a tree.

1. Removal of Pavement or Sidewalk

Removal of existing pavement over tree roots shall include the following precautions:

- Break hardscape into manageable pieces with a jackhammer or pick and hand load the pieces onto a loader. The loader must remain outside the TPZ on undisturbed pavement or off exposed roots. Do not remove base rock that has been exploited by established absorbing roots.
- Apply untreated wood chips over the exposed area within one hour, then wet the chips and base rock and keep moist until overlay surface is applied.

1 Construction Site Management

2. Replacement of pavement or sidewalk

An alternative to the severance of roots greater than 2- inches in diameter should be considered before cutting roots. If an alternative is not feasible, remove the sidewalk, as stated above, cut roots with a sharp, clean saw, as approved by the project manager or arborist and replace sidewalk using #3 dowels at the expansion joint if within 10-feet of a street tree. Use wire mesh reinforcement if within 10-feet of the trunk of a tree. Any work in the right-of-way requires a ROW usage permit from the Transportation Department.

3. Alternative methods to prevent root cutting

- Grinding a raised sidewalk edge.
- Ramping the walking surface over the roots or lifted slab with pliable paving. Routing the sidewalk around the tree roots.
- Install boardwalk, flexible paving or rubberized sections.

4. Alternatives to conventional pavement and sidewalk materials

Substitute permeable materials for typical asphalt or concrete overlay, sub-base or footings to consider are:

- Permeable paving materials (such as ECO-Stone or RIMA pavers).
- Interlocking pavers, flexible paving, wooden walkways and brick or flagstone walkways on sand foundations.

5. Tree and Infrastructure Conflicts

Avoid tree and infrastructure conflicts and associated costs by the following planting practices:

- Plant deep rooting trees that are proven to be non-invasive.
- Over soil that shrinks and swells, install a sidewalk with higher strength that has wire mesh and/or expansion slip joint dowel reinforcement.
- Fracture soil with an air spade and backfill with sand prior to planting to promote deep rooting and improved drainage.
- Install root barrier only along the hardscape area of the tree and allow roots to use open lawn or planter strip areas.
- Dedicate at least 10-linear feet of planting space for the growth of each tree.
- Provide a dedicated irrigation system or zone for the tree, so the trees do not have to compete and are not dependent on the turf and shrub irrigation.
- Avoid planting trees over underground drainage systems where root intrusion will impede function of the system.

6. Alternative Base Course Materials

When designing hardscape areas near trees, the project architect or engineer should consider the use of recommended base course material such as an engineered structural soil mix. An approved structural soil mix will allow a long term cost effective tree and infrastructure compatibility that is particularly suited for the following types of development projects:

- Repair or replacement of sidewalk greater than 40-feet in length.
- Planting areas that are designed over structures or parking garages.
- Confined parking lot medians and islands or other specialized conditions as warranted.

7. Tree Removal

In some cases, tree removal may be the preferred option if the site does not provide adequate space to account for future growth of the tree.

1.4 Training

Provide training to all construction personnel to make sure they understand all construction site BMPs.

- The project manager and the designated site manager(s) shall receive the most recent training and education dealing with construction site management. This training includes the most recent advances for protecting trees and erosion control on construction sites.
- Urban Foresters and site managers should receive training in appraising and evaluating tree and plant damage according to International Society for Arboriculture standards.

1 Construction Site Management

(This page intentionally left blank for note taking)



CHAPTER 2 – Stormwater Pollution Prevention Plan (SWPPP) for Park Operations



2.1 Purpose

Bordered by Lake Washington & Lake Sammamish, the City of Bellevue has more than 60 miles of streams, 800 acres of wetlands and 3 small lakes (Larson, Phantom, and Bellevue) that provide rich habitat for fish and wildlife as well as a multitude of benefits that enhance the quality of life for Bellevue residents. Protecting these environmentally sensitive assets from the discharge of harmful pollutants is an important goal of the Parks & Community Services Department.

Stormwater accumulates a variety of pollutants as it runs over roofs, lawns, sidewalks, streets, compacted soils and parking lots before entering streams or groundwater. Pollutants commonly found in urban stormwater include heavy metals, pesticides and fertilizers, oil and grease, bacteria and sediment. Stormwater runoff contributes to water quality problems that can endanger human health and wildlife.

Bellevue Parks & Community Services operates three maintenance facilities (Resource Management, Bellefields and Golf Course) that have areas where bulk materials are stored and equipment is washed. Bulk materials are also intermittently stored on a temporary basis at park sites when performing maintenance operations such as turf topdressing, infield replenishment and landscape renovation. If not properly managed, pollutants can be discharged from these facilities or sites into the

2 SWPPP for Park Operations

City's stormwater system. The purpose of this section is to identify methods and procedures to reduce or eliminate the contamination of stormwater runoff or discharges of pollutants from Bellevue Parks operations. The objectives of a Stormwater Pollution Prevention Plan (SWPPP) are as follows:

- Implement and maintain best management practices that identify, reduce, eliminate and/or prevent the discharge of stormwater pollutants from Parks maintenance facilities.
- Eliminate unpermitted discharges and other illicit discharges to the City's stormwater drainage systems.

2.2 Background

The Washington State Department of Ecology requires that the City meet the requirements of the NPDES and State Waste Discharge General Permit and Phase II Municipal Stormwater Permit. Condition of this permit requires that the City implement and maintain a SWPPP for all heavy equipment maintenance or storage yards, and all material storage facilities owned or operated by the City. The permit also requires the City to include periodic visual observation of discharges from the facility to evaluate the effectiveness of the BMPs. The Resource Management, Bellefields and Golf Course maintenance facilities are included in the SWPPP since activities at these three sites can be categorized as heavy equipment maintenance or storage yards or bulk material storage facilities.

2.3 Best Management Practices

Good Housekeeping

"Good housekeeping" is an ongoing approach to improving and maintaining a clean and orderly work environment. Recommendations for good housekeeping are as follows:

- Promptly contain and clean up solid and liquid pollutant leaks and spills including oils, solvents, fuels and dust to prevent contact with any soil, vegetation or paved area exposed to stormwater.
- Sweep paved material handling and storage areas regularly as needed to collect and dispose of dust and debris that could contaminate stormwater. Do not hose down pollutants from any area to the ground, storm drain, conveyance ditch or receiving water unless necessary for dust control

- purposes to meet air quality regulations and unless the pollutants are conveyed to a treatment system approved by the City.
- Clean accumulations of oils, debris, sludge, etc. from all BMP systems regularly, including catch basins, sedimentation basins, oil/water separators, boomed areas and conveyance systems to prevent the contamination of stormwater.
 - Promptly repair or replace all substantially cracked or otherwise damaged paved secondary containment, high-intensity parking and any other drainage areas, which are subjected to pollutant material leaks or spills.
 - Promptly repair or replace all leaking connections, pipes, hoses, valves, etc. which can contaminate stormwater.
 - Use solid absorbents and rags for cleanup of liquid spills and leaks where practical.
 - Dispose all green wastes in appropriate storage bins for regular recycling and disposal. All non-green waste and construction debris should be separated and disposed of separately. Contaminated green waste generated from street and parking lot sweeping should be handled separately and transferred to an appropriate vendor who can accept contaminated waste.

Perform Routine Maintenance

Over time, sediment and pollutants can accumulate in stormwater collection, conveyance and treatment systems, such as basins, ditches, storm drains and oil/water separators. These pollutants can include sediment and other substances such as oils, debris and sludge. When a storm event occurs, the pollutants can become mobilized and transported into receiving waters. Regular maintenance of the stormwater drainage system decreases the amount of pollutants available to contaminate stormwater. Routine maintenance elements and recommendations are described as follows:

1. Catch Basins. Catch basins at the Resource Management, Bellefields and Golf Course facilities shall be inspected annually and maintained according to maintenance standards consistent with the most recent edition of the Stormwater Management Manual for Western Washington. Additional inspections may be warranted following major storm events (i.e. greater than 1 inch of precipitation in a 24 hour period).
2. Parking Lot Sweeping. Sweeping should occur monthly to reduce the amount of potential sediment entering storm catch basins and conveyance systems. This practice will help reduce the costs associated with commercial cleaning and repairs identified through the NPDES Utility inspection program.

2 SWPPP for Park Operations

3. Stormwater Treatment Facilities. The Resource Management & Golf Course facilities have equipment wash stations that treat stormwater through oil/water separators before discharging into the City's storm conveyance system. These treatment facilities shall be inspected annually and maintained using standards consistent with the most recent edition of the Stormwater Management Manual for Western Washington. The separators shall be vector cleaned throughout the year as necessary.
4. Drainage Systems/Ponds. Inspection and maintenance of drainage conveyance systems and retention ponds should occur annually. Cleaning of inflow and outflow drains (i.e. removing built up vegetation) should be performed annually. These practices will extend the service life of the system and reduce long term maintenance costs.

Spill Prevention & Response

Spills can contribute a variety of pollutants to the stormwater drainage system and nearby waterways, but this result is often preventable if appropriate practices for chemical and waste handling and spill response are implemented.

1. Spill Prevention. To reduce the potential for spills, the following practices shall be implemented:
 - Clearly label all containers that contain potential pollutants.
 - Store and transport liquid materials in appropriate containers with tight fitting lids.
 - Place drip pans underneath containers, fittings, valves and any other area where materials are likely to spill or leak.
 - Use tarpaulins, ground cloths or drip pans in areas where materials are mixed, carried and applied to capture any spilled materials.
2. Spill Plan. The Resource Management, Bellefields and Golf course facilities shall implement site specific spill plans to address small spills and leaks. These plans shall be updated annually and posted at appropriate points in the building, such as loading areas, product storage areas and waste storage areas. The spill plan shall include the following information:
 - Facility description including the address and telephone number, the nature of the facility and the general types of chemicals used.
 - Names, addresses and telephone numbers of designated spill response employees who are responsible for implementing the spill cleanup.
 - Site drainage plan showing locations of storage areas for chemicals, storm drains and other relevant drainage or materials information.
 - Description of the emergency cleanup and disposal procedures.

- Names and telephone numbers of agencies to contact in the event of a spill.
3. Spill Cleanup Kits. Spill cleanup kits shall be stored near areas with a high potential for spills so that they are easily accessible. The spill kit contents must be appropriate to the types and quantities of materials stored or otherwise used at the facility and refilled when materials are used. Spill kits may include the following items:
- Absorbent pads
 - Sorbent booms
 - Absorbent granular material (e.g. kitty litter)
 - Personal protective equipment (e.g. latex gloves, safety goggles)
 - Thick plastic garbage bags
 - Drain cover
4. Spill Cleanup & Disposal. To minimize release of pollutants into the storm drainage system, the following procedures shall be implemented when there is a spill:
- Immediately report spills that involve potentially flammable or hazardous substances to the Bellevue Fire Department. Notify the Utilities 24-hour Emergency Response Line (425-452-7840) that an illicit discharge has occurred.
 - Immediately evaluate whether the illicit discharge can be safely contained or prevented from entering the drainage system and/or receiving waters.
 - Determine the responsible party, if possible.
 - Characterize the nature of the pollutant so that the appropriate personal protective equipment (PPE) can be utilized.
 - If you know what the substance is, follow the recommended procedures for containment/cleanup for that substance. If necessary, refer to the material safety data sheet (MSDS) for the substance.
 - If the substance is unknown, the following steps shall be taken:
 - If it is safe to do so, attempt to contain the spill. Use physical barriers, such as sand bags, or an absorbent, such as a pad or clay litter.
 - Do not use water or any other substances on the spill unless it is safe to do so.
 - Do not wash or push the substance toward the drain, indoors or out, until it has been identified and a safe cleanup method has been determined.

2 SWPPP for Park Operations

- Immediately notify your supervisor of the spill and what steps have been taken to contain it or identify the substance.
- If necessary, place warning signs or barriers around the area to keep people away.
- Do not use a vacuum to clean up flammable substances.

Inspections

The Resource Management, Bellefields and Golf Course maintenance facilities shall be regularly inspected by the designated SWPPP Manager where heavy equipment and material storage areas are exposed to stormwater. During these inspections, staff shall assess how the stormwater BMPs are operating. Routine visual inspections shall occur at least quarterly during the wet season (October – March) and at least once during the dry season. Some types of equipment, processes and BMPs will require more frequent checks than others. Visual inspections of wash stations should occur monthly with a written log maintained each year of the person who made the inspection, the date of the inspection, and what action was taken as a result of the inspection. Removal and clearing debris from the separators should occur immediately after each inspection as required.

Reporting & Recordkeeping

Records shall be kept of all inspections, observations and compliance documentation for each of the Resource Management, Bellefields and Golf Course facilities. The results of each visual inspection shall be summarized in an inspection report or checklist and be entered into the City's Maximo database. The visual inspection report shall include the following:

- Scope of the inspection and date.
- Major observations relating to the implementation of the SWPPP.
- Summary of the actions which will be taken to meet NPDES Municipal Stormwater permit requirements.
- Tracking procedures to ensure that an inspection report is prepared and appropriate corrective actions taken.

2.4 Training

All staff members shall be trained annually on safe techniques for handling materials, spill control procedures and operations and maintenance of BMPs to prevent illicit discharge of pollutants into the City's stormwater system. All pollution prevention team members shall be trained annually in the operation, maintenance and inspections of BMPs. This training will be documented for compliance with NPDES Municipal Stormwater permit requirements.



2 SWPPP for Park Operations

(This page intentionally left blank for note taking)



CHAPTER 3 – Integrated Pest Management (IPM)



3.1 Purpose

The City's parks and natural areas are a reflection of the values of the community. The Parks Department strives to ensure that public landscapes remain attractive and meet the expectations of thousands of users, and preserve natural ecosystems for future generations. These green open spaces offer Bellevue residents the opportunity to enjoy a natural environment within their community. Trees, shrubs, flower beds, ponds, rivers and lakes make up these open spaces, and require maintenance and protection from damage by both humans as well as biological pests.

Integrated Pest Management (IPM) is a sustainable approach to managing pests by combining biological, cultural, physical and chemical methods in a way that will minimize the effects on the environment, minimize domestic and health risks, while considering budgetary restrictions. The Parks Department adopted an IPM program in 1997, which has been integrated into this document, which outlines how both passive and active modes of maintenance are vital to the preservation of any environment. The objectives of the Parks Department's IPM program are as follows:

- To protect the health, safety, and welfare of the community.
- To provide efficient cost effective maintenance of the City's park resources. This includes non-chemical controls whenever possible.

3 Integrated Pest Management (IPM)

- To design new and renovate existing landscape areas that suit site conditions with sustainable maintenance practices, thus providing a comprehensive stewardship of parks and natural resources.
- To restore, create and protect environmentally valuable areas such as wetlands and riparian areas, aquatic and terrestrial wildlife habitat, forests and meadow areas.

3.2 Background

Policies and Regulations

By legal definition, a pesticide is any substance for which a manufacturer or distributor claims pesticidal value. Today there are more than 30,000 pesticide products registered to destroy, prevent, attract, or in some manner, control pests.

The Insecticide Act of 1910 was the first legislative action taken in an effort to regulate the use of pesticides. Since then there has been the Federal Insecticide, Fungicide and Rodenticide Act of 1947 (FIRFA) and more recently, the Federal Environmental Pesticide Control Act of 1972. The major provisions of this act are:

- All pesticides must be registered with the U.S. Environmental Protection Agency (EPA). Qualified states may also register pesticides under special conditions.
- All pesticides will be classified for either general or restricted use.
- Only certified applicators, or those under their supervision, may apply restricted use pesticides. States have the authority to certify applicators.
- Use of pesticide inconsistent with labeling instructions is prohibited.
- Violators may be fined or imprisoned or both.

In order to comply with this act as well as other regulations, the City of Bellevue has established its own Hazard Communication Program, which integrates into the Park's IPM program as well, to ensure that all employees remain informed and receive the proper training when dealing with hazardous chemicals and their application. The components of this will be discussed later in this chapter.

Other important regulations pertain to working within protected areas, such as wetlands and riparian corridors, steep slopes and native growth protection areas. Certain activities are restricted in these areas and may require special permits granted by the City of Bellevue and other regulatory agencies. Further description of these areas and their restrictions will be described later in this chapter.

Pesticide Use Decision Process

The following agencies and individuals are involved in the determination of when to use pesticides in Bellevue Parks:

- The Washington State Department of Agriculture (WSDA) sets the overall policy for pesticide use in the state of Washington. The approved chemical list can be seen on their website at www.agr.wa.gov.
- The Washington Department of Ecology (DOE) requires a special permit for all aquatic herbicide applications. This permit allows herbicide control for all listed noxious weeds within an aquatic environment and monitors impact levels on non-target plants.
- The Park Resource Managers, Golf Course Superintendents, Program Supervisors, Contract Administrators and Crew Leaders are responsible for upholding and applying City and Park's pesticide policies and procedures within their areas of control. They are also responsible for ensuring that any personal protective equipment (PPE) is available and properly fitted for use by applicable staff for any chemical application.
- The Site Managers and Crew Leaders determine the most appropriate control measure for actual landscape pest situations, including selecting the most appropriate pesticide products, if necessary. In golf maintenance, this responsibility rests with the Golf Course Superintendent or their immediate assistant. They are also responsible for the safe storage and handling of pesticides, spill responses and related training.
- The Risk Manager is responsible for coordinating the mandatory annual recertification training for all licensed pesticide applicators, officially called "Pesticide Operators." This position also serves as the primary contact for providing information regarding the Department's IPM program to the general public and outside agencies.

Pest Management Guidelines

The following pest management guidelines generally apply to all City of Bellevue Parks and Community Services landscapes:

- Park landscapes will be designed to minimize pest management. Where resources are available and existing design themes will not be compromised, modifying landscapes will be considered to reduce pest management.
- All reasonable, cost effective non-chemical pest control options will be considered first before resorting to the use of pesticides.

3 Integrated Pest Management (IPM)

- Parks will practice IPM in all pest management situations, understanding that some situations will require the use of a pesticide product.
- Certain levels of pest problems or populations will be accepted within established thresholds. Those thresholds will vary with the pest and the landscape setting.
- Parks will not perform prophylactic or calendar-based pesticide applications.
- Only pesticides approved for that particular use will be used for the prescribed applications. When pesticides are applied, the smallest effective area will be treated, and the application will be timed to minimize public contact and the effects on the environment.
- Whenever possible, pesticide applications will be carefully timed to control the pest and reduce the need for retreatment.
- In accordance with the Washington State Licensing Guidelines, all staff and contractors who are engaged in the use, application and storage of pesticides shall have a current Washington State Pesticide License. Contractors must notify appropriate Department representatives prior to the application of any pesticide for approval to use such pesticides.
- Parks pesticide applicators shall strictly observe all pesticide products label requirements. All chemicals used on Parks property will have an MSDS on file, and will be available to all staff, contractors and the public upon request.
- Pesticides shall not be used to control plants with edible fruit during the fruiting season unless the plant being controlled is not of sufficient size to produce fruit. Fruiting plants such as blackberries may be first cut to the ground, allowed to re-sprout and then chemically controlled before the plant can produce fruit. Plants controlled in this manner will never be allowed to produce fruit in the future.
- All sites where pesticides have been applied shall be posted, as required by the Washington State Department of Agriculture (WSDA). As required by the WSDA, all applications of pesticides will be recorded. All application records Department wide will be filed in one central location at the Resource Management office and made readily available to the public upon request.
- When pesticides are used in confined environments such as greenhouses, the facility shall be clearly posted "Closed to Entry" until the re-entry time period has elapsed.
- Parks will continue its aggressive training program for all staff who apply pesticides, and will continue to emphasize learning new pest control techniques as they are available.

- Parks will continue to field test alternative controls to pesticide use and will implement successful control options as budget allows.
- To promote public understanding and support of the benefits of the IPM program, educational assistance and information will be made available to the public regarding the use of pesticides.
- The City shall comply with all Federal, State and Local regulations pertaining to the application, handling, storage and disposal of pesticides.

Components of an IPM Program

IPM involves a structured decision-making process that embodies the philosophy and the components of the IPM system. Through the following applications, as well as the proceeding guidelines, a well-managed IPM program can be implemented.

1. Identification of pest populations: Identify the nature, location, scale and the intensity of the problem.
2. Determine plant injury levels: Define the tolerance levels for aesthetic and economic injuries. Prescribe the point at which actions must be taken to avoid exceeding the tolerance level.
3. Design and implement the pest management treatment: Research all possible options and design strategies. Non-target organisms must be considered at this time. Use of pesticides is limited to situations where other cultural and biological options are not likely to be successful within the context of available resources. The pesticide chosen shall be the least toxic of those available with as minimal impact possible, as defined by that chemical's use.
4. Evaluate results. Conduct follow-up inspections to support evaluation:
 - Did the pest population decline to acceptable levels?
 - Was there a negative impact on non-target organisms?
 - Do the host plants appear to be able to thrive following a successful treatment?
5. Adjust and extend program as indicated: Decide whether further treatment will be necessary, either on a temporary or permanent basis. If it will be on a permanent basis, plan potential site modifications to eradicate the problem or prevent future recurrences.
6. Create documentation of all research, monitoring, and application data: A comprehensive system of forms for monitoring data and documenting treatment is a key component of a successful IPM program.
7. Share pest management information with decision-makers and maintenance staff: Professional staff must know the degree to which landscape pest management programs impact existing staff, maintenance budgets and park

3 Integrated Pest Management (IPM)

assets. Only through such understanding and ongoing communication can the best long-term strategies be developed for managing pest populations.

IPM Control Alternatives Selection Hierarchy

The following selection rationales are used as a guide for determining whether pesticides shall be used in place of other control methods:

- Proper planning and management decisions begin the IPM process.
- Cultural methods of vegetation and pest control are preferred and will be employed first.
- If unsuccessful, mechanical means of vegetation and pest control will be employed next where practical and feasible.
- Biological means of vegetation and pest control will be employed next where they are practical and feasible.
- Pesticides will only be used when no other feasible method exists that will control the pest within the realities of the location, site conditions, budget and other relevant considerations. At the same time, it is recognized that pesticide use is a legitimate element of an IPM program.

3.3 Best Management Practices

Storage and Use Guidelines

Every employee has a personal responsibility to themselves, other staff and the public to follow safe work practices when storing or using pesticides. The following management practices are required:

- Always read and understand the label of the chemical that you will be using.
- Store and handle all chemicals or fertilizers in a manner that minimizes worker exposure and potential for contamination of surface and ground water.
- Always have the correct Material Safety Data Sheet (MSDS) on hand for all chemicals or fertilizers at your site (required by law).
- Always check the MSDS for the type of protection needed and the recommended re-entry time before the chemical is applied.
- When possible, purchase the smallest amount of any pesticide and avoid stockpiling of chemicals.
- Store fertilizer in a separate weatherproof area.

- All spray equipment shall be maintained in proper working order and stored in an OSHA approved site.
- All protective gear (masks, filters, rain gear) will be stored separately from any possible contamination.
- Store and mix all chemicals in a WSDA approved storage and mixing area. Label storage area with an NFPA coded sign to protect Fire Department or Hazmat personnel in case of emergency.
- Any pesticides in inventory that are no longer needed for use will be disposed of through hazardous materials disposal practices. The Washington State Department of Agriculture (WSDA) provides free disposal of unwanted pesticides at various locations throughout the calendar year.
- All chemical containers will be clearly labeled.
- A pesticide inventory will be maintained by the Resource Management Division.

Pesticide Application Equipment

Pesticide application for all listed areas will be carried out by hand with directed, low-volume, single-wand sprayers, wiping, daubing and painting equipment, injection systems, or drop spreaders. Typically, applications are done with backpack sprayers, but may also include sprayers with larger fill tanks providing the same kind of hand application method is used. These methods of delivery result in low volume applications at low nozzle pressures. This practice minimizes the formation of fine mists that can result in pesticide drift. These practices also help ensure that the pesticide applied will reach only its intended target. In large open turf areas, boom type sprayers may also be employed. Boom sprayers are efficient and expedient tools used to destroy weed species after they have exceeded the acceptable threshold level. Broadcast applications shall be avoided unless absolutely necessary.

Personal Protective Equipment (PPE)

Table 3.1 shows the personal protective equipment required by City, State and Federal regulations for pesticide use.

Chemical Application near Watercourses & Aquatic Habitats

Generally, the use of chemical products within 50 feet of a watercourse shall be prohibited in favor of an alternative control method. If a pesticide or herbicide must be applied within the 50-foot buffer, only products registered for use near water bodies shall be used, and great care will be taken to ensure that the product does not migrate into the watercourse either through drift or by overland flow. All applications will be made under the guidelines of the NPDES Aquatic Noxious Weed Management General Permit as issued by the Washington State Department of

3 Integrated Pest Management (IPM)

Ecology (DOE). Weather conditions must be monitored carefully to avoid applying a chemical near a watercourse immediately before heavy rains. Soil conditions and site topography must also be carefully studied to determine the appropriate timing of a chemical application and/or whether a chemical should even be applied at the site.

Chemical Application in Watercourses

Generally, the use of chemical products within aquatic environments shall be prohibited in favor of alternative control methods. In limited situations, the City may apply herbicides directly to watercourses to control wide spread noxious aquatic vegetation, such as Eurasian Water Milfoil, within public marinas, boat launches and swimming beaches. In such applications, only products registered for use in aquatic environments and approved by the DOE will be used. Chemical applications will be contained to the area of infestation and applied under guidelines set forth within the NPDES Aquatic Plant & Algae Management General Permit issued by the DOE. Aquatic pesticide applications will generally be contracted out to specialized aquatic weed management agencies and supervised by City Representatives.



Table 3.1 Personal Protective Equipment (PPE) Guide for Using Pesticides

Form of Pesticide	LABEL SIGNAL WORD		
	CAUTION	WARNING	DANGER
Dry	<ul style="list-style-type: none"> • long-legged pants • long-sleeved shirt • shoes & socks 	<ul style="list-style-type: none"> • long-legged pants • long-sleeved shirt • shoes & socks • wide-brimmed hat • gloves 	<ul style="list-style-type: none"> • long-legged pants • long-sleeved shirt • shoes & socks • hat • gloves • cartridge or canister respirator if dusts in air or if label precautionary statement says "Poisonous or fatal if inhaled"
Liquid	<ul style="list-style-type: none"> • long-legged pants • long-sleeved shirt • shoes & socks • wide-brimmed hat • gloves 	<ul style="list-style-type: none"> • long-legged pants • long-sleeved shirt • shoes & socks • wide-brimmed hat • rubber gloves • goggles if required by label precautionary statement • cartridge or canister respirator if label precautionary statement says "Do not breathe vapors or spray mist" or "Poisonous if inhaled" 	<ul style="list-style-type: none"> • long-legged pants • long-sleeved shirt • rubber boots • wide-brimmed hat • rubber gloves or face shield • canister respirator if label precautionary statement says "Do not breathe vapors or spray mists," or "Poisonous if inhaled"
Liquid when mixing	<ul style="list-style-type: none"> • long-legged pants • long-sleeved shirt • shoes and socks • wide-brimmed hat • gloves • rubber apron 	<ul style="list-style-type: none"> • long-legged pants • long-sleeved shirt • shoes & socks • wide-brimmed hat • rubber gloves • goggles or face shield • rubber apron • Respirator if label precautionary statement says: "Do not breathe vapors or spray mist" or "Poisonous (or fatal or harmful) if inhaled" 	<ul style="list-style-type: none"> • long-legged pants • long-sleeved shirt • rubber boots • wide-brimmed hat • rubber gloves • goggles • rubber apron • canister respirator
Liquid (prolonged exposure to spray, or application in enclosed area)	<ul style="list-style-type: none"> • long-legged pants • long-sleeved shirt • boots • rubber gloves • waterproof wide-brimmed hat 	<ul style="list-style-type: none"> • water-repellent long-legged pants & long-sleeved shirt • rubber boots • rubber gloves • rubber apron • waterproof wide-brimmed hat • face shield • cartridge or canister respirator 	<ul style="list-style-type: none"> • waterproof suit • rubber boots • rubber gloves • waterproof hood or wide brimmed hat • face shield • canister respirator

3 Integrated Pest Management (IPM)

IPM Best Management Practices

Parks maintains a wide variety of landscape types, each with unique pest control issues and control measures. For these reasons, the pest control measures specific to each landscape are dealt with separately in this section. If chemical applications are required, only chemicals approved for a specific location will be used in that location. Parks only uses City approved chemicals on park properties.

Control of Special Pests

Blackberries

An aggressive, invasive plant, blackberry will overtake a disturbed site at an alarming rate. Mechanical control is not very effective by itself, but combined with chemical control measures and replanting of the site, effective control can be maintained. Chemical applications shall be kept to the area of infestation. Treatment efforts should include re-vegetating the site with desirable plant species.

Scotch Broom

An unruly plant, it thrives on disturbed sites. It is difficult to control and spreads rapidly. The seeds and flowers are toxic, making it a high priority for eradication. Manual control can have some effect, but it must be done at the proper time of year. Chemical control can also be effective, but requires follow up management techniques until full eradication occurs. Chemical applications shall be kept to the area of infestation.

English Ivy

A very aggressive, invasive, introduced plant, Ivy is difficult to control or eradicate. Manual or mechanical control is somewhat effective, but highly time consuming. A combination of mechanical and chemical control is more effective and spread can be kept to a minimum with continuous control measures. Chemical applications shall be kept to the area of infestation.

Horsetail

One of the most tenacious weeds in Northwest gardens is horsetail. It is almost impossible to control manually or mechanically. Horsetail can be controlled with herbicides. As with other chemical controls, chemical application shall be contained to the area of infestation. Horsetail is an indication of high water content in soil, so any use of herbicides should be well thought out and carefully timed.

Eurasian Water Milfoil

Because it is widely distributed and difficult to control, milfoil is considered to be one of the most problematic invasive aquatic plants in Washington State. Milfoil can drastically alter a water body's ecology and significantly interfere with recreational activities such as swimming and boating. Because of its wide distribution, eradication is not practical. Therefore, a "management" approach has been adopted to control the spread of milfoil within public marinas, boat launches and swimming beaches. A combination of manual and chemical control shall be used to achieve the most effective results.

Garlic Mustard

Garlic mustard is an invasive non-native biennial herb that spreads by seed. It is difficult to control once it has reached a site. It out competes native vegetation and it can establish in a relatively stable forest understory. Plant stands can produce more than 62,000 seeds per square meter to quickly out compete local flora, changing the structure of plant communities on the forest floor. This noxious weed has been discovered within Coal Creek Park, Eastgate Park and Forest Park Open Space and is aggressively managed by Bellevue Parks staff in cooperation with King County primarily with herbicide applications.

Poison Hemlock

This noxious weed is acutely toxic to people and animals. It is most commonly found along roadsides, in open fields and in natural areas. Unrelated to the native evergreen hemlock tree, poison-hemlock can be deadly. As such, this weed is aggressively managed, typically with use of herbicides, when discovered in Bellevue Parks.

Tansy Ragwort

This invasive, toxic biennial is most often found in pastures and along roads and trails. Although animals tend to avoid it, they may eat enough of it to become ill and even die. In spite of efforts to control it, tansy ragwort is widespread in the Pacific Northwest and can be found within Bellevue Parks and Open Space. This weed is best controlled by using a combination of manual control and herbicide application.

New Zealand Mud Snails

This invasive species has been discovered in Kelsey Creek (Kelsey Creek Park) and Valley Creek (Highland Park). The City had developed protocol to prevent the further spread of this invasive species. Decontamination of equipment, personal gear and increasing public awareness is the most effective method of controlling the spread of the New Zealand mud snail.

3 Integrated Pest Management (IPM)

Rats

Rats are only somewhat of a pest problem in Bellevue parks. Bellevue does have some natural predators of rats which helps alleviate many of the problems that could occur. They do pose a human health risk and will be controlled in given situations. The common method of control is baiting with an approved rat bait/trap. Extreme caution must be taken to place rat bait in locations where people or domestic animals cannot access it.

Mice

Mice are becoming an increasing human health problem from Hanta virus. Mice control is not currently a major pest control issue in park facilities, but increased control measures may be required in the future based on the history of the virus.

Moles

Moles can cause significant damage and disfigurement to turf areas in developed parks, athletic fields and golf courses. Moles can also destroy flower beds and damage underground utilities. Since mole trapping is outlawed in Washington State, approved mole baits have become the most common control method utilized by Bellevue Parks. Extreme caution must be taken to place mole baits in locations where people or domestic animals cannot access them.

Yellow Jackets, Hornets, and Wasps

These insects often require control in parks. Control is typically through use of an approved insecticide. Only individual nests are treated and only if the nest poses an imminent risk to humans using park facilities.

Vector-borne Disease

Here in the Pacific Northwest, vector-borne diseases have increasingly become an issue. The most significant is mosquito-borne diseases, such as the West Nile Virus (WNV). Complete control of mosquito infestations is near impossible, but cultural control can have some effect, such as removing any standing-stagnant water from any sites. Larvicides may also be used to control mosquito infestations if it's determined that public health concerns warrant their use. As part of the city-wide WNV response plan, surveillance (dipping) for pond facilities will be included during the mosquito season when human cases are reported in the Puget Sound region.

IPM for Greenhouse Operations

Greenhouses are a production operation dealing with large numbers of plants, of similar species, in a closed, non-public environment. Because of these factors, the

tolerance threshold for many pest problems is much less in the greenhouse environment than it is in general park landscapes, requiring the use of a broader palette of pesticide products.

Pest Tolerance Thresholds

Weeds are not tolerated in the City greenhouse.

- Insects or disease pests that threaten the health of plant collections or production crops are not tolerated in the greenhouse.
- Display spaces shall be kept free of weeds.

Pest Management Strategies

Weed Control

- Greenhouse operating areas and containers and conservatory through hand/manual weeding.
- Weeds shall be controlled in exterior spaces, building perimeters, shade houses, cold frames and related areas either by hand or mechanically with push type mowers and string trimmers or suppressed with landscape fabrics.
- Exterior areas shall receive pesticide treatments for weed control, if they impact interior production.

Insect Control

- Insect pests shall be routinely monitored by visual inspection or the use of "sticky traps."
- Cultural practices including regular irrigating and fertilizing shall be used.
- Insects should be removed by hand or washing them off the affected parts of the plants.
- Biological controls, such as beneficial insects and other organisms that attack pest insects, should be used to keep pest populations under control. Periodic release of beneficial insects helps to suppress and reduce the need for chemical control.
- Spot treatments of the least toxic, yet effective, insecticide shall be directed at specific plant parts for specific pest control.

Disease Control

- Good sanitation techniques shall be provided, including regular removal of plant debris and keeping tools and work areas clean.
- Plants shall be properly spaced to provide for good air circulation.
- Disease resistant plants shall be selected.

3 Integrated Pest Management (IPM)

- Diseased plants shall be kept away from healthy crops.
- The least toxic, but effective, pesticide product shall be applied to control specific disease pathogens on specific plants or crops.

IPM for Nursery Operations

The nursery, located on SE 16th Street, is a facility for the growing of plants for use on developed and undeveloped park property. It occupies roughly five acres of property and has been in continuous operation for more than 40 years. The plants provided by the nursery operation include natives as well as ornamentals, groundcovers, vines, perennials, shrubs and trees. The plants are grown to support various needs throughout the park system ranging from small in-house planting projects to large Capital Improvement Projects. In recent years, the production of native plants has been increased substantially to meet increasing demand, primarily for forest restoration projects. Control of pests in the nursery environment is very important since many plants may be affected at one time.

Pest Tolerance Thresholds

Pests that threaten the health of the nursery crops will not be tolerated and will be controlled.

Pest Management Strategies

Surface and Groundwater Protection

- General site runoff is controlled through biofiltration.
- Select the least toxic and most non-leaching chemical products only when necessary.
- Precisely follow all label instructions.

Weed Control

- Most weed control at the nursery is accomplished through hand weeding, mulching and use of landscape fabrics.
- When other controls have failed, herbicide is used for spot control of weeds.

Insect Control

- Habitat for natural insect pest predators will be encouraged as an environmentally sound means to reduce populations of insect pests.

Disease Control

- Select disease-resistant plant varieties.

- Monitor plant crops for disease outbreaks.
- Practice good cultural practices including watering, fertilizing, pruning and maintaining good air circulation.
- Reduce the potential for transfer of disease through good sanitation techniques. These practices include keeping growing areas, tools and containers clean and removing plant litter and debris in a timely manner.

IPM for Planting Beds

Planting beds are defined as non-turf planted areas that include woody plant material such as shrubs, trees and ground covers. The category also includes floral color displays containing herbaceous plants such as perennials, annuals and bulbs. The most serious pest management issue in planting beds is weed control. If not controlled, weeds not only make a plant look unkempt, but more importantly, can out-compete desirable landscape plants resulting in a loss of assets. The table on the following page shows pest tolerance thresholds and IPM principles that shall be employed in selecting maintenance methods for planting beds.



3 Integrated Pest Management (IPM)

Pest Tolerance Thresholds for Planting Beds

Area	Weeds	Insects	Disease
General Landscape Beds	<ul style="list-style-type: none"> • Some weeds acceptable • Goal is for bed areas to be free of weeds for both asset protection and appearance • Weeds will not be allowed to out-compete desirable landscape plants 	<ul style="list-style-type: none"> • Generally tolerated unless particularly valuable plants are actually threatened 	<ul style="list-style-type: none"> • Occasionally tolerated • Manual and cultural controls preferred • Chemical controls used to save specimens
Highly-visible/ Public facility landscapes/ Bellevue Botanical Gardens	<ul style="list-style-type: none"> • Generally not acceptable 	<ul style="list-style-type: none"> • Generally tolerated unless they threaten particularly valuable plants • Manual removal of obvious pests is encouraged 	<ul style="list-style-type: none"> • Occasionally tolerated • Manual and cultural controls preferred • Chemical controls used when other means fail
Floral beds	<ul style="list-style-type: none"> • Generally not acceptable 	<ul style="list-style-type: none"> • Generally tolerated 	<ul style="list-style-type: none"> • Disease problems tolerated • Plants may be replaced when appearance is impacted
Newly-established landscapes	<ul style="list-style-type: none"> • Weed control is very important to ensure complete establishment of desired plants 	<ul style="list-style-type: none"> • Generally tolerated • Presence of pests may result in host plant being removed and replaced 	<ul style="list-style-type: none"> • Minor disease problems may be tolerated • Presence of disease problems may result in host plant removal and replacement

Pest Management Strategies

Weed Control

- Weeds are controlled by hand pulling, or by mechanical methods in larger planting beds.
- Planting beds will be mulched after planting to suppress new weed growth.
- Spot treatment with herbicides shall be used as necessary.

Disease Control

- Diseased plants shall be hand pulled from planting beds and discarded appropriately.
- Disease resistant plants shall be planted in all planting beds, whenever possible.

IPM for Trees

Trees are an integral part of most landscapes, whether formal or natural, and are considered an asset. They provide shade, clean the air of pollutants, modify both micro and macro climates and provide visual relief to the urban environment. Because trees are often very large and tall, accessing and managing insects and disease can be quite difficult and costly.

Pest Tolerance Thresholds

In general, insect and disease pests in trees, including trees located in streetscapes, are tolerated.

- Insect or disease pests in selected, high-value specimen trees may be subject to control measures.

Pest Management Strategies

Physical Damage to Trees

- Physical damage to trees can be a major factor in overall loss of trees. This damage most often occurs in one of two ways. One is when trees are repeatedly struck by mowing equipment. A second form of injury is by string trimmers, which can damage bark leading ultimately to tree loss. Many trees are also lost to lack of appropriate care during construction projects within existing parks.
- Removing turf from around the tree base to create tree mulch rings 3 to 4 feet in diameter can substantially reduce damage caused by mowers and trimmers. With tree mulching, a mower or trimmer never has to come close enough to the tree to cause damage. The tree mulch ring will need to be kept free of grass and weeds.
- Following the BMPs in Chapter 1, Construction Site Management, substantially reduces or eliminates damage from construction activities.
- All pruning for tree health reasons and for hazard reduction will be done in conformance with the International Society of Arboriculture standards.

Insect Control

Parks does not actively control insect pests in trees. This is particularly true of large trees where the control of the pest might require the use of large aerial spray equipment, which carries with it a high probability of the insecticide applied leaving the area due to wind drift. For example, Parks does not spray aphids despite the "honeydew" problem associated with them. When insect pests are controlled in trees, the following measures are used:

3 Integrated Pest Management (IPM)

- Trees that are highly susceptible to specific insect pests (such as blue spruce and spruce aphids) may be removed from the landscape and replaced with resistant species.
- When possible, the portion of the tree affected by the insect (such as tent caterpillars) can be physically removed, eliminating the pest.
- An insecticide may be applied to control a specific insect pest in very select situations. These situations include pests on specimen quality trees at special gardens or in high visibility locations where the presence of the pest threatens the life of the tree. In these situations, general foliar applications will not be made unless the potential for product drift can be controlled.
- Injection technology when practical may allow for systemic control of certain insect pests with minimal or no impact to human or environmental health.

Disease Control

Dutch Elm Disease and Anthracnose on London Plane Trees are the only tree diseases Parks actively controls with pesticides. Most other diseases are tolerated in trees, unless they lead to a tree becoming a hazard to the surrounding environment. As with insecticides, it is unlikely that Parks will subscribe to general foliar applications of fungicides or similar pesticide products to control disease pests in trees. The following are control measures that can be performed:

- Trees that are susceptible to particular disease pathogens may be removed from the landscape and replaced with resistant varieties.
- When possible, parts of trees affected by disease should be pruned out and properly disposed to stop the spread of disease within the tree and to adjacent trees.
- An appropriate fungicide may be applied to control a specific disease pathogen in very selected situations. These cases include specimen quality trees in special gardens or in high-visibility park locations where the presence of the disease threatens the life of the tree. In these situations, general foliar applications will not be made unless the potential for product drift can be controlled.
- Injection technology when practical may allow for systemic control of certain disease in tree pests with minimal or no impact to human or environmental health.

IPM for Turf

The City of Bellevue Park system maintains a wide variety of turf types. These include park lawn areas (both formal and informal), athletic fields, golf courses, meadow areas and other turf types. Each of these turf types has different pest management challenges, and practices may vary accordingly.

Pest Tolerance Thresholds

Some level of weed, insect and disease pests are tolerated in general park lawn areas.

- Weed, insect and disease pests are typically tolerated in general park lawn areas.
- Turf pests in highly maintained turf such as athletic fields, bathing beaches and other high-visibility/high-use areas are generally controlled through good turf cultural practices.
- Pesticides can be applied to park turf areas only when thresholds for weeds, especially in high profile areas, become unacceptable.
- Because of the unique conditions present on golf courses, a variety of pest control measures are used, including mechanical, cultural and chemical.

Pest Management Strategies

Weed Control

Weeds in turf are tolerated, to some level, with the exception of golf course turf and a few high-visibility park turf areas. When control is necessary, the primary method is through the following cultural practices:

- Careful monitoring of watering practices
- Fertilization
- Aeration
- Top-dressing
- Over-seeding

By performing this preventive maintenance, park turf is healthier and better able to compete with various broadleaf weeds. Chemical weed control may be used for controlling particularly difficult weeds in high-visibility turf areas.

- In these rare situations, the least toxic, least residual pesticide will be used.
- Pesticide use should be avoided near waterways.
- In general, broadcast applications will be avoided.
- The timing of such applications will be made to avoid contact with the public to the greatest extent possible.

3 Integrated Pest Management (IPM)

- Posting of the site that has been treated will be done as legally required to meet or exceed legal requirements.
- Maintenance of City golf courses includes treatment of broadleaf weeds through cultural practices and spot application of carefully selected herbicides.

Insect Control

The only real insect pest of significance for turf in the Bellevue area is the European Crane Fly. While it can be quite damaging to turf areas, the crane fly is not controlled by prophylactic means in City of Bellevue parks.

- Chemical control is used in limited circumstances for highly visible and valuable turf areas such as golf courses, athletic fields and formal park areas (i.e. Robinswood House).
- Any chemical applications will consist of spot treatments directed specifically at the turf areas containing the pest.
- The preferred initial choice for application in high-use areas will be the least toxic product available.

Wood Brush Control

Woody brush control in meadows may require the use of chemical controls if mechanical control measures are not adequate.

Disease Control for General Park Turf

Disease in general park turf is typically tolerated and not actively controlled.

- In high-use/high-visibility park turf areas, disease will be controlled to a considerable degree by performing sound cultural practices.
- Pesticides may be used as a last resort to control disease in park turf areas.

Disease Control for Golf Course Turf

Because turf disease can be a significant problem on golf courses, it must be controlled to preserve the function of this asset. Golf course turf, particularly greens and tees, must perform under extreme conditions of maintenance and use. These conditions make golf course turf more susceptible to disease than general park turf.

- Golf turf disease is controlled through good cultural practice to the greatest extent possible.
- Certain diseases are controlled through the application of an appropriate fungicide.
- When used, fungicides are applied to the diseased turf only, such as a green.

- The least toxic and still effective products are used.
- The fungicide used will be rotated yearly to reduce the chance of the turf disease developing a resistance to the chemical control.

Grass Trimming Abatement

The control of grass growing along fence lines and around trees, bollards, posts and other landscape features is a regular maintenance activity that helps preserve the asset by allowing large riding lawn mowers to steer clear of objects. This is especially important around trees where impact from mower damage can easily lead to tree loss. At the same time, keeping this grass controlled allows for parks to appear clean and well kept. This grooming affects how the public uses our facilities. Well-maintained parks are subject to less vandalism and related misuse. The following are BMPs for grass trimming abatement:

- Line trimmers or push mowers: The grass is trimmed using gas-powered line trimmers or push-type lawn mowers. This labor-intensive practice is costly and produces noise and air pollution.
- Herbicide: Applications are performed annually or semi-annually, to provide pre-emergent control of weed and grass seed not yet germinated in tree mulch rings, planting beds and similar areas.
- Concrete mow strips: As resources are available, it is sometimes possible to provide a "mow strip" of concrete or a similar low maintenance product around some landscape features to eliminate the need for grass trimming. This control option is costly and doesn't work in all situations.

IPM for Natural and Sensitive Areas

Natural areas are City-owned property with critical environmental resources. These sensitive habitats shelter native ecosystems and wildlife habitat and include nearly all classifications in the City's *Sensitive Areas Manual*, including steep slopes and slide prone areas. For the purposes of this BMP manual, these resource assets are divided into three major groups:

- Wetlands, riparian corridors, shorelines and aquatic habitats
- Forests
- Meadows

3 Integrated Pest Management (IPM)

Pest Tolerance Thresholds

- Invasive plants are generally not tolerated. Invasive plants will be controlled in conjunction with natural resource enhancement efforts in these environments as resources permit and where control can be practically achieved.
- Noxious weeds will not be tolerated and will be controlled when found in conformance with State of Washington mandate. For more information on noxious weeds, visit the following web-site:
<http://www.kingcounty.gov/environment/animalsAndPlants/noxious-weeds.aspx>
- Only insect pests that pose a risk to the public (such as hornets) or to the resource (such as gypsy moth) will be controlled.
- Plant diseases will generally be tolerated unless: a specific control can be employed that will be effective in ensuring the health of particularly valuable assets; or if they pose a threat to other plant populations outside of the natural area; or if they pose an unacceptable risk to the public.
- Herbicide Use: The use of herbicides in any natural environment must be carefully considered. Herbicides will be used for weed control in natural areas only when other control measures have been tried and failed, and only if control can be achieved through the use of an herbicide, and is imperative to the health of the site. For wetland or aquatic environments, only herbicides approved for aquatic use will be used. When needed, herbicide use practices are as follows:
 - Cut and stem treatment (daubing or painting) is the preferred choice for natural area management.
 - Certain invasive plants are difficult to treat and control in their mature form. If possible, remove existing growth manually or mechanically. Wait for new growth to become established, then treat with the appropriate and approved herbicide.

Pest Management Strategies

Weed Control

An overriding principle of IPM is the maintenance of healthy plant communities. That means weed control of the following types:

- Timed mowing. Carefully timed mowing before seed set can effectively reduce weed seed sources. Frequent mowing can eliminate blackberry and other woody species.
- Mulching. Mulching around the base of plantings is widely accepted as a horticultural practice for soil fertility and weed control. In most instances, composted wood chips or onsite recycle leaf litter are

adequate materials. Avoid wood chips from diseased trees. Mulch should be between 2 to 3 inches deep for best results.

- Weed monitoring during mulching. Care must be given to not incorporate new weed problems when importing mulch materials.

Woody Brush Control:

The control of woody brush, like blackberry, is very important in certain park locations. Often these plants are found in transition areas between developed park areas and natural areas. If not controlled, woody brush can easily overtake forest-edge environments, eliminating vital habitat opportunities. Control measures for woody brush include the following:

- Manual or mechanical removal using hand tools or gas-powered equipment. Special tools are now available for removing woody brush. In many areas, this can provide effective control.
- Chemical control can be employed when other measures are not mechanically or economically feasible. Spot applications are preferred, whenever possible, to large area applications.

Insect Control:

Insects like the European and Asian Gypsy moth and the Asian Long Horned Beetle can potentially devastate Bellevue's urban forest. Parks will cooperate with State and Federal agencies in their monitoring and control programs to prevent the introduction of these pests.

Disease Control – Root Rots:

Even native forests can have serious disease problems. Root rots are the most serious problem, leading often to the death of significant trees. Several strategies help control root rot in forests:

- Inoculate with mycorrhizae
- Remove infected wood
- Plant resistant varieties
- Treat resulting stumps with borax on Western Hemlock
- Do not change site conditions on mature trees

Stump Re-Sprouting Control:

Often there is a need to remove small trees and prevent re-sprouting of a stump. Methods for controlling the re-sprouting of stumps include the following:

- If the location of the stump(s) will allow access by equipment, then they can be mechanically removed providing the location is not within an environmentally critical area.

3 Integrated Pest Management (IPM)

- Small stumps may be removed manually providing they are not on steep slopes or in other environmentally critical areas.
- The re-sprouting of stumps can also be controlled by painting newly cut stump surfaces with an herbicide. Care will be taken to limit the application of the selected herbicide to the stump surface only.

Invasive Plant Control:

Invasive plants have taken over many of the City's forested areas and have radically and negatively impacted pre-existing ecosystems. Attaining long-term control of invasive plants is essential to the recovery and preservation of Bellevue's natural ecosystems. Invasive plant control shall follow the guidelines established by *King County Noxious Weed Boards*. Except in the case of Class A weeds, the goal is suppression of weed populations to below threshold (damage causing) levels. Eradication of certain ecological weeds (blackberry or ivy) in all of the City's natural areas is neither feasible nor cost-effective. However, controlling the spread of the problem and eradicating it in certain priority locations is the goal. Control methods include:

- Use *extent of removal* and *type of habitat* to determine the pest control method.
- Large areas that are totally infested can be mowed. Areas that are interspersed with invasive pests require more selective procedures such as manual removal.
- Heavy equipment or manual removal can be used on firm soils. On either steep or saturated soil, use techniques that will minimize site or slope disturbance.
- Where mechanical or manual removal is neither possible nor practical but control is essential, careful and selective use of an approved herbicide is permitted.
- Re-establishing a new native planting regime as quickly as possible following the removal of invasive plants is critical to successful forest restoration. These new plantings will require care for several years to guarantee establishment.
- Preserve established native plants when possible rather than re-establishing new plants after the clearing of invasives.
- Public education and outreach concerning plant identification and management techniques will also aid the City in controlling noxious weeds.

Nuisance Wildlife Control:

Mountain beavers, moles, coyotes, beavers, opossums, raccoons, waterfowl and other species can be destructive to natural areas when their activities are

excessive. Overall, Parks does not encourage the interference with wildlife and prefers to leave them to their natural behaviors. If control of wildlife is deemed necessary, Parks will work with the most appropriate County (Animal Control) or State (Department of Wildlife) agency to formulate a control solution.

IPM for Trails

Pest Tolerance Thresholds

Invasive plants that invade the trail area are generally not tolerated. Invasive plants will be controlled in conjunction with ecosystem restoration efforts on any park trail as resources permit.

- Noxious weeds will not be tolerated and will be controlled when found in conformance with State of Washington mandate.
- Weeds are generally found on trails and many will be tolerated. Weeds that begin to form a hindrance of trail function will be eradicated.
- Only insect pests that pose a risk to the public (i.e. hornets) will be controlled.

Pest Management Strategies

Weed Control:

Weeds on trails are generally tolerated, until they begin to interfere with trail function. When control is necessary, the primary method is increasing mulch on, or re-surfacing, the trail surface. Chemical weed control is often not necessary on trail surfaces, but will be used only as a last resort for controlling particularly difficult weeds.

- In these rare situations the least toxic, least residual herbicide will be used for spot treatments.
- General broadcast treatments will be avoided.
- Timing of such applications will be made to avoid contact with the public to the extent possible.
- Posting of the site that has been treated will be done as legally required.

Insect Control:

Overall, insects on trails are tolerated. Only insects that can cause a health risk are controlled. Wasps and hornets are some of the few insects that will be eradicated immediately when encountered. When this is necessary, chemical control with an approved insecticide is the preferred method, and only the individual nests will be treated.

3 Integrated Pest Management (IPM)

IPM within Agricultural Areas

Pest Tolerance Thresholds

Invasive plants that invade agricultural areas are generally not tolerated. Invasive plants will be controlled as resources permit.

- Noxious weeds will not be tolerated and will be controlled when found in conformance with State of Washington mandate.
- Weeds are generally found in agricultural areas and many will be tolerated. Weeds that begin to interfere with crop production will be eradicated.
- Only insect pests that pose a risk to the public (i.e. hornets) will be controlled.

Pest Management Strategies

Weed Control

Generally, weeds are tolerated in agricultural areas. When control is necessary, mechanical practices are the primary methods.

- Mowing
- Hand pulling
- Herbicides are used only in extreme cases

Insect Control

Insects are not a high concern on agricultural farms. In the past, there has been little need to utilize insecticides, except in the case of hornet nests. The selective use of surfactants has proven to be effective for controlling minor insect breakouts.

Disease Control

Most agricultural areas owned by Parks are on wetlands. Disease issues related to that kind of environment make control more difficult. At the present time, only fungicides approved for a wetland environment have been used to counter diseases such as "mummy berry", which is a serious disease on blueberry farms. The following control measures may be performed in order to prevent spread of diseases:

- Drainage of crop rows to reduce root rot.
- Spot application of an approved fungicide. In these situations, general foliar application will not be made unless the potential for product drift can be controlled.
- Clean cultivation or tilling of the soil around crop plants to bury mummified berries to 1 inch will help prevent the disease from spreading in the following year.

Fertilizer Use

Parks does not use fertilizers on any agricultural lands.

Nuisance Wildlife

There is some need for control of nuisance wildlife on Parks owned agricultural lands. Most of the farms grow fruits, which are highly appealing to many wildlife populations. Most grazing by wildlife is tolerated, with the exception of Starlings. They pose a major detriment to the farm as they can consume large amounts of foods and are very abundant. The Starling population has risen to such a level that extreme measures of control have been considered. Presently, Parks uses bird calling machines placed throughout the farm areas as a deterrent to Starlings and other birds.

3.4 Training

Because IPM is an ecologically sophisticated process that requires professional expertise in vegetation and pest management, it demands trained field personnel that are knowledgeable about:

1. Ecological interactions and relationships among vegetation and pests;
2. Potential tools and materials that can be used to effectively manage vegetation and pests by manipulating environmental conditions; and
3. Correct timing for implementing specific management practices relative to vegetation and pest biology.

Educational and career opportunities in IPM will enhance crew professionalism, their knowledge of current vegetation and pest management practices, and their stewardship of managed landscapes. Each landscape type will have an individualized training program developed and accessible to all applicable staff.

3 Integrated Pest Management (IPM)

(This page intentionally left blank for note taking)



CHAPTER 4 –

Irrigation and Water Management



4.1 Purpose

Water resources are an important part of the Parks & Community Services Department's landscape assets. Turf, shrubs and trees all require water to live, but not all require the same amounts. Wise water use must consider both the preservation of landscape assets and the impact on the broader watershed. An efficient irrigation program makes the best use of the resource by not wasting water vital to other natural resources, such as fish, while at the same time preserving landscape assets.

The design and programming of irrigation systems is complex. It requires understanding the principles of hydro-zoning and knowledge of basic hydraulics, site conditions such as soils, slopes and plants, and knowledge of the irrigation system tools themselves. As competition for available water becomes more acute, the department will continue to be equally dedicated to carefully managing this resource.

4 Irrigation and Water Management

4.2 Background

Best management practices for irrigation system operations combine activities for maximizing a range of technologies for water control and common field practices.

Irrigated Park Areas

Because our mission is to preserve all landscape assets, most developed landscape areas are irrigated, including the following:

- Athletic fields
- Community and neighborhood parks
- Golf greens, tees, and fairways
- Most turf areas
- Most shrub and annual plant beds
- Newly installed landscapes
- Most areas in high-use or high-visibility parks
- Special gardens
- City building facilities

Non-Irrigated Park Areas

The following City assets are not irrigated:

- Meadow areas
- Natural areas
- Low visibility and low use turf areas

Design

Irrigation design is the foundation of sound water management. The design process involves determining which sites to irrigate, what portions of each site should be irrigated and choosing the appropriate automated system. (Note: all new irrigation systems are designed and installed in compliance with City of Bellevue's water budget requirements.)

Choosing an Automatic Irrigation Control Option

The City of Bellevue utilizes a variety of controllers for timing the application of irrigation water. These automatic controllers serve three primary purposes:

1. Operate remotely rather than manually, saving labor hours and water.
2. Accurately time irrigation to specific needs of soils, slopes and plants.
3. Reduce impacts to park use and water loss to evaporation by operating at night.

Types of Irrigation Controllers used in Bellevue Parks

Four types of irrigation controllers are used in Bellevue Parks:

Electric Controllers

These controllers use electrical circuitry. Advantages of these controllers include relatively low cost, significant programming flexibility and ease of repair. The only disadvantage of these controllers is that they operate as stand-alone units, thereby lacking the savings potential of central computer control. Electric is the preferred controller for parks that will not be connected to central control.

Battery-Operated Controllers

Battery-operated controllers are either mechanical or solid state controllers that operate off of battery power. They are typically used at locations where automatic irrigation is desirable but access to electric power is not feasible. The City uses very few of these devices currently as constant monitoring is required to make the systems reliable. Batteries are subject to failure and moisture problems, requiring regular replacement.

Solar Powered Controllers

Solar powered controllers utilize solar energy to provide power for the controller. This technology is relatively new and requires the use of on-site solar panels which are susceptible to vandalism and misuse. The Parks Department has yet to find reliable solar powered equipment, yet will still continue to experiment with this technology as newer and improved equipment is made available.

Computer ET Based (Maxicom)

Maxicom is the brand name for the centralized computer-controlled ET based irrigation system that the City uses at those parks where communication linkages are possible. The use of a centralized ET based computer system provides the following advantages as it pertains to irrigation water management:

- Allows remote irrigation systems to be programmed without a physical site visit.
- Monitors water use within individual systems and can detect and flag problems and pinpoint them for repair.
- Since the system is linked to a weather station, it can be automatically programmed to withhold water on rainy days.
- Remote systems can be automatically programmed not to water when soil moisture levels indicate water is not needed. These built in sensors can determine where water is being used and where there may be problems.

4 Irrigation and Water Management

- Uses flow control monitoring devices that provide valuable data on water usage at each specific park site.

Maxicom is the preferred computerized control system for the majority of the City's park sites. This system requires daily monitoring by a trained technician who can make appropriate changes based on water use data and weather conditions. Since this system is relatively complicated to operate, only sufficiently trained staff should program and operate Maxicom controllers. The use of a computer ET based system for medium to large parks and athletic fields is very important and should continue to be a high priority.

Installing Irrigation Systems

All new irrigation systems and renovations shall be designed and installed according to departmental standard specifications, and shall comply with the City of Bellevue's water efficiency and irrigation regulations and codes. In order to have water service (meter) provided, a water budget must be prepared and approved by the Utilities Department. To the extent possible, standard material and products will be used to increase ease of maintenance and reduce inventory confusion and incompatibility problems.

Programming Automatic Irrigation Controllers

Programming automatic irrigation controllers relies more on understanding a site and its plant materials than the mechanics of the system itself. Controllers should be checked bi-weekly to ensure proper operation to maximize watering efficiency. The primary goal of using automatic irrigation controllers is to maintain a consistent soil moisture environment that maximizes plant health and vigor, while closely monitoring water use so as to not needlessly expend resources.

Water Auditing and Conservation

As budget allows, the Parks Department may perform occasional water audits on existing systems to determine if water usage exceeds, meets or fails to meet the needs of plant species, soil types and weather conditions. In such cases, usage adjustments are made if a water audit shows that efficiencies can be gained with little or no impact to the plant resources.

During drought seasons, the City of Bellevue follows a water shortage management plan which is based on the voluntary curtailment of water usage by Bellevue residents, as well as a 50% reduction in normal irrigation usages on City property.

For a detailed description of the City of Bellevue Parks and Community Services Department's Water Shortage Response Plan, see appendix. The Parks Department, in cooperation with the Utilities Department, also adheres to the City-wide Water Shortage Contingency Plan, adopted in 1994. Water restrictions are kept in effect until reservoirs are returned to a safe level, and water quality testing has proven the water safe to drink.

4.3 Best Management Practices

Water use needs of the turf, shrubs and trees shall be researched prior to irrigation.

- Apply no more water each week than required to sustain healthy plants. For turf areas, a general rule of thumb is no more than 1 inch of irrigation water per week, including rainwater.
- Turf should be watered 1 – 3 times per week, and for longer periods, to promote deep rooting. Deep rooting leads to healthier, more drought-tolerant grass.
- Soil also plays an important role in irrigation. Soil conditions should be considered, particularly in turf areas with heavy use. Heavier, clay-type soils cannot be watered as long during each watering cycle as can sandy soils.
- Turf and planted areas should be aerated and cultivated to relieve soil compaction and increase water uptake.
- Wherever possible, watering should be avoided during the hottest part of the day. Watering at night is preferred to reduce evaporation of water as well as possible vandalism to equipment and irrigation heads.
- Staff shall not allow manually operated systems to apply water longer than needed. The system shall not be turned on in the morning and turned off at the end of the day for convenience.
- Special attention shall be paid to verify that manually operated sprinklers are actually watering the landscape and not streets or other non-landscape areas.
- A water budget should be determined for each site.
- Depending on the availability of resources, a complete system audit should be completed on a 5-year cycle.
- Application of irrigation water shall be carefully monitored to determine when controller settings can be reduced to save water and to reduce runoff.
- A resource management system for irrigation operations should be developed. This system would provide a database from which

4 Irrigation and Water Management

programming records can be retrieved for annual system reprogramming to avoid starting from scratch.

Other considerations for Irrigation:

- Consider plant species and age when programming the irrigation controller or when applying water manually.
- Site topography plays an important role in irrigation timing. Given their potential for runoff, sloped sites may require multiple applications of irrigation water in shorter timing cycles than required for flat sites.
- Become familiar with site specific soil moisture holding capacity and soil infiltration rate.
- Know what the water requirements of the plants are in each zone. Prevent overwatering.
- Attributes per station such as: slope, exposure level, soil type, and plant requirements.

Irrigation System Maintenance

The following are preventive maintenance procedures for irrigation system operations:

- Visually check the system to make sure it is operating properly.
- Perform regular preventive maintenance on heads, valves and controllers.
- Repair the system promptly to reduce water loss.
- Make sure heads are set at the proper grade and properly aligned.
- Make sure valves are operating properly.
- Use the system winterization and de-winterization processes as opportunities to make complete system visual checks.
- Keep grass and shrubs trimmed away from heads to allow proper functioning.
- Clean heads as needed to ensure optimum performance.

Upgrades and Replacements

- The existing inventory of the condition of all City irrigation systems shall be maintained and updated.
- A replacement program (major maintenance program) is needed to ensure timely upgrading or replacement of old systems. The existing irrigation system major maintenance replacement program shall be maintained to provide priority-based direction for replacement funding.

4.4 Training

Staff training is required in several areas:

Basic Water Conservation

All park maintenance and operations staff should receive training on basic water conservation as part of an overall training program in environmental management. City staff, vendors or state agencies can provide this training. Staff should follow the Parks & Community Services Department drought policy during periods of extreme regional water shortages (see appendix).

Electric Controllers

Programmers for the system are required to become familiar with the unique qualities of each controller. This training should be scheduled when controllers are installed or when unfamiliar with equipment. Training should include all field staff.

Maxicom

Operation of the Maxicom system requires training and certification. This training is provided by outside vendors.

4 Irrigation and Water Management

(This page intentionally left blank for note taking)



CHAPTER 5 – Nursery Operations



5.1 Purpose

The Bellevue nursery provides a cost-effective way for the City to meet landscape construction and plant replacement needs throughout its park system. Strict operational practices are followed to produce high quality and healthy plants in City of Bellevue nurseries. This chapter identifies and defines these best management practices for nursery operations.

5.2 Background

The City of Bellevue operates a 5 acre nursery located at 15302 SE 16th Street. This facility holds ornamentals, groundcovers, vines, perennials, shrubs and trees that are procured from local nurseries and plant growers. These plants are stored at this facility to support various needs throughout the park system ranging from small in-house planting projects to large capital improvement projects.

An increasing number of these plants are Pacific Northwest native species that are grown for use in landscape restoration projects to ensure variety of plants needed in the sizes required. The following are features of the City Nursery:

5 Nursery Operations

- Office and storage building
- Growing frames
- Holding and healing-in area
- Container yards
- Poly and shade houses
- Propagation areas: cold frames, seed beds, poly-house.

Basic Operating Plan

- Most of the nursery operation is containerized. Plants are grown and stored in containers to various sizes for eventual planting in parks. A containerized operation is both cleaner and less labor intensive than field growing, particularly when moving plants out of the nursery.
- Plants are field grown to meet specific needs such as large specimen trees.

Plant Selection

- The City of Bellevue's nursery program is not designed to store or carry a large number of plants in its inventory. Surplus plants are not cost effective given the care required to maintain a large inventory.
- The types and quantities of plants selected for procurement and storage are generally determined through requests from City of Bellevue staff or to meet particular requirements of various capital projects.
- There are some plants that are grown as test subjects for possible introduction into park landscapes.

5.3 Best Management Practices

The following are standard practices for preparing and maintaining plants grown and/or stored in City of Bellevue nursery operations.

Site Preparation

- All plant growing and storage areas shall have adequate drainage to ensure plants are not sitting in water or saturated soil.
- Field growing soil and imported potting soil shall be tested as needed to determine the need for amendments/nutrients and for the presence of unwanted pathogens.
- The container soil mix shall be compost (20%), peat (15%), pumice (25%) and fine decomposed bark (40%) with 1 lb. calcium nitrate added per cubic yard.
- Soil for field growing shall be a sandy loam with not more than 30% organic material in the form of equal parts of compost and bark (Note:

bark in this case is fir or hemlock free of wood waste products. Cedar bark or chipping debris shall not be used).

Site Maintenance

- Noxious weeds shall be controlled or removed from the site during preparation.
- Roads and pathways shall be maintained on an annual basis to ensure accessibility.
- Any exposed soils or bark piles shall be covered with plastic.
- The general public or contractors shall not have access to the nursery grounds unless a pre-approved department staff person is also present.

Cultural Care

The following are preventive maintenance techniques the City of Bellevue uses to ensure the quality of its nursery plants.

- All plants should be spaced to allow for optimal growth, especially in field growing areas.
- Containerized plants shall be re-potted as needed to prevent encircling roots and to allow them to grow into their desired natural form without girdling.
- All plants shall be watered as needed. The primary method of irrigation is the existing overhead system. This system works well for field growing areas but is modified as needed for watering containerized plants.
- City water used for plant irrigation purposes shall be used efficiently:
 - Plants will be grouped by size and water needs.
 - Watering will be done on an as-needed basis.
 - The most efficient system for watering individual planted areas will be used.
 - Avoid watering nursery areas that are not currently holding plants.
- The nursery shall support recycling:
 - Clean compost will be used whenever possible.
 - Growing containers will be reused or recycled.
 - Plant debris will be sent to a "clean-green" yard waste facility.
 - Used soil from containers will be reused onsite whenever possible.
- Plants shall be fertilized as needed using slow-release types of fertilizers.
- Plant holding areas shall be used for plants that are in transition. While in holding, plants shall be mulched, staked as needed, watered and provided with shade protection if required.

5 Nursery Operations

- Winter protection shall be provided for plants as needed through the use of existing greenhouses or "frost blankets." Smaller, more tender plants shall have priority for winter protection.

5.4 Training

The City of Bellevue will develop a basic training program for staff assigned to work in the nursery. This training will also be made available to other City of Bellevue staff to broaden their horticultural skill base.



CHAPTER 6 – Planting Bed Management



6.1 Purpose

Landscape planting beds are often the focal point of a park, streetscape or City building. They provide color, texture, space definition, fragrance, wildlife habitat and other benefits enjoyed by park users. In the Pacific Northwest, climatic conditions favor growing a wide variety of ornamental landscape plants and a rich palette of Northwest native plants. These environmental conditions have allowed planners, designers and maintenance staff to create a landscape plant collection of real beauty. Careful management of these assets is required to continue the heritage and maintain the value of this substantial plant collection. The best management practices described in this chapter are applicable to parks, city buildings and streetscapes that have planting areas as a design function.

6.2 Background

Level of visibility and site use dictate maintenance standards for planting beds. Even within the same park, maintenance techniques can differ for formal plantings and high-traffic areas as opposed to remote areas that may remain informal and natural. For that reason, planting bed BMP's are tailored to the specific requirements of plant material and site goals. At a formal site, the desired result may be to promote prolonged bloom in floral displays.

6 Planting Bed Management

Planting beds can be divided into four categories according to level of visibility and usage:

1. Floral Beds are very visible and have a high standard of maintenance which includes weekly grooming, weeding and regular site visits.
2. General Landscape Bed Areas have moderate visibility and standards of maintenance which include monthly weeding and seasonal pruning.
3. High-Visibility/Public Facility Landscapes have the highest visibility and the highest standard of maintenance.
4. Newly Established Landscapes will have a very high standard of maintenance through the plant establishment period (1-5 years).

Existing Site/Environmental Conditions

Site microclimate considerations are taken into account when planning a new planting or renovating an existing one. The following factors must be weighed:

Current Landscape Condition

The condition of current plant material is a good indicator of existing cultural conditions. Compaction, low nutrients and types of pest populations determine renovation and plant selection options. This is particularly true of soil-borne pathogens such as Phytophthora root rot. Selecting resistant plant materials is a must. It is also recommended to select plants that do not require fertilizers or highly specialized care.

Soil Type and Condition

Soil may require amendment to improve drainage or water-holding capacity. Heavy clay or very sandy soils may be improved if desired, but appropriate plant selection is vital to the success of the planting.

Drainage

Irrigation and drainage conditions must be assessed and any improvements included in the design process. Run-off should be eliminated as much as possible. If a site is a steep slope, COB standards must be met. (see *COB Critical Areas Ordinances*)

Cultural Conditions

Cultural conditions such as exposure to sunlight and reflected light, heat, wind and rainfall apply to plant selection and irrigation installation.

Safety

Safety issues include falling branches, plant growth that blocks pathways, visibility through shrub beds, sightlines at park entrances and rerouting pedestrian traffic to sidewalks.

Flowers

In floral displays, the maintenance budget for the display must be taken into consideration when selecting plant material. Some annuals and perennials require more grooming than time constraints allow and should only be used where they will receive adequate care.

Species Diversity

Species diversity offers a longer season of interest. Monocultures can be more susceptible to total failure in case of insect or disease problems.

6.3 Best Management Practices

Site Preparation

Preparing the site is important to the long-term success of a landscape. Making the necessary cultural improvements before planting saves time and money. The following are BMPs for site preparation:

Existing Weeds

To prepare a site for landscaping or renovation, existing weeds and undesirable plant materials should be removed as thoroughly as possible. Weed populations (especially difficult-to-control weeds such as horsetail, morning glory and quack grass) affect planting plans. In a primary bed location, they should be eradicated before installation of new landscapes. If mechanical eradication is not practical, an appropriate chemical control will be used.

Overgrown Plants

Plant material that is too large, or has an expected mature size that is too large for the space, should be replaced with appropriately sized species.

Diseased Plants

Disease and insect-resistant material should be selected and used where the culture will promote healthy growth. In an existing planting bed to be renovated, diseased plants shall be removed and replaced with healthy specimens or treated by appropriate means.

Soil

Soil amendments as required should be added to and incorporated into an entire planting area. Avoid tilling saturated soils, which can damage tilth.

Water

Irrigation and drainage systems should be installed as needed.

6 Planting Bed Management

Landscape Features

Install retaining walls, pathways and hardscape features prior to plant installation to avoid subsequent damage.

Rocks and Debris

Excessive rocks and debris must be removed. Rake area to establish finish grade.

Fertilizers

A soil test indicates fertility levels in the soil. Fertilizer, if required, should be applied to the site and incorporated into the soil. Amendments that include un-composted woody material may require nitrogen.

Annuals

Annual flowerbeds must be spaded or tilled at planting time. Amendments such as compost, sand or Perlite can be added to adjust drainage. In containers, the addition of hydrating gel can enable the use of plant material that might not otherwise be appropriate to water requirements.

Planting

The following guidelines for proper installation of plant material ensure good establishment and healthy growth.

Fertilizer

If fertilizer is to be used, it is best to wait until plants are established before adding chemical fertilizers to the soil in order to promote long root growth.

Depth

Plants must be placed at proper depth, taking into consideration room needed for mulching.

Spacing

Proper spacing with consideration of mature size and spread of plants ensures good establishment. Good air circulation and availability of sunlight, water and nutrients will promote growth and avoid development of disease. Ground covers and floral plantings should be close enough to provide adequate coverage to compete with weeds, and provide effective display, without being too crowded at maturity.

Water

Water new plantings to settle soil and reduce transplant shock. Ensure adequate moisture levels during the growing season.

Mulch

Mulch at planting time for maximum efficiency. Rake soil smooth to prevent puddling and then apply mulch. Avoid smothering small plants. A fine mulch is preferred as it becomes the next season's planting soil.

Edging

The main purpose of edging is to maintain a neat, manicured edge to the planting bed area. Proper edging also controls weeds along the edge of the planting bed.

- Informal Plantings can be maintained mechanically or chemically to control turf and weed encroachment onto mulched areas.
- Formal Plantings can be maintained by hand tools, mechanical means or chemically.

Irrigation

Site conditions such as soil type and slope, exposure and moisture requirements of plants dictate both frequency and duration of application.

- Weather conditions, such as temperature and rainfall, require monitoring and response. Generally, most plants require at least 1 inch of water per week. Drought tolerant plants, once established, may need less. Floral plantings, particularly in containers, require considerably more.
- Infrequent deep watering is preferable. Avoid creating runoff.
- Shrubs, groundcovers and flowers planted in the root zones of large trees need more water to balance the competition from the tree roots.
- Consider pedestrian access, park usage and available personnel when establishing irrigation schedules.
- Avoid disease damage by keeping water off of leaves.
- Be sure to begin watering early enough in the spring to prevent plant stress and hydrophobic soil conditions. Continue irrigating until consistent fall rains begin.
- Visually test and monitor the system weekly.

Mulching

Mulching serves to conserve moisture, retain soil, suppress weed growth, moderate soil temperature, reduce compaction and supply nutrients for plants and soil microbes. Mulch is also aesthetically pleasing making it desirable for high visibility locations.

- Materials include bark products, compost, wood chips and other commercial organic products.
- Depth of application varies according to type of plant material, but averages 2 to 3 inches. Keep mulch materials away from contact with trunk or crown of plants to avoid stem rot.
- Recess edge of beds to avoid drift of mulch materials onto turf or pavement, where necessary.

6 Planting Bed Management

- Flowerbeds should be mulched with a fine material such as compost, taking care not to smother plant crowns. Generally, mulch in an annual planting is 1 inch deep although a deeper layer of mulch, if possible, will provide better weed suppression.
- Un-composted woodchips can potentially deplete soil nitrogen as they decompose. The use of woodchips may require application of a nitrogen-rich fertilizer.
- The use of fallen leaves as mulch may be appropriate in some areas. Avoid using diseased or insect-infested material. It is important to avoid smothering the roots of the desirable plants with too thick of a layer. A 2-inch layer is considered best. Compost from plants that are known to be diseased shall not be used for mulching purposes.

Fertilizing

Fertilizing, the use of organic or inorganic compounds, shall be tailored to specific requirements for plantings:

- Nutrients: Nutrient requirements differ according to plant type and the desired performance of a plant. Turf grass and showy ornamental plants require more nitrogen than plants grown specifically for flower and seed production. Plants grown for flower and seeds require more phosphorus (P) and potassium (K). Too much nitrogen can cause excess growth, which will be more susceptible to insect and disease damage.
- Application Timing: Timing application to the biological cycle of the plant is important in maintaining optimum growth. Plants just becoming established may require more P and K in the blend to encourage root development. Also, plants benefit most from fertilizer application at the onset of their new growth in the spring. Applications too close to fall may delay dormancy and promote soft growth, which can suffer winter damage.
- Micronutrients: Micronutrients are also important for plant health. It is best to test the soil to determine existing levels of these nutrients because an imbalance can harm plants.
- Soil pH: The pH of the soil will determine whether to use an acid or base formulation of fertilizer, as well as the need for lime applications. Always test for pH before applying any fertilizer or lime.
- Formula: Select a formulation that is best for the soil type and time of year. Cold weather slows the activity of soil microbes that make nutrients available to the plants. Plants require nitrogen, phosphorous, potassium and other nutrients to optimize growth.

- **Floral Plantings:** Floral plantings can be fertilized at planting time with slow-release fertilizer. Flowers can also be supplemented during growing season with foliar feedings of liquid fertilizer.
- **Compost:** Compost can be applied as a nutrient source. It must be fully decomposed so that nutrients are made available to plants. Most compost has no more than 3% nitrogen, which is slowly released. Its main benefit is that it encourages beneficial soil microbial growth.

Pruning

Pruning shall be performed according to current ISA standards and for the following reasons:

- Encouraging and directing new growth and flowering.
- Removing spent blooms and foliage.
- Removing insect, disease and weather damage.
- Maintaining size and shape.
- Maintaining visibility.
- Improving safety.
- Creating pedestrian and mower access.

Plant Selection

Use appropriate plant materials that grow to the correct size for the space. Plant selection reduces the need for excessive pruning.

Natural Form

A natural form is desirable in most park settings. This is also more healthy for the plant.

Hedge Pruning

Hedge pruning requires careful timing for optimum results:

- First cut should be made as new growth begins to harden off.
- Last hedging should be made no later than mid-August.
- Hedges should be wider at bottom than top.
- Hedge pruning is labor-intensive and is best applied to plants with smaller leaves as they tolerate heavy pruning better.
- Because the intensity of maintenance required, formally-pruned hedges are not desirable in many park locations.
- When major pruning is required of prominent plantings and hedges, neighbors/park users may need to be notified in advance of the work to be done.

6 Planting Bed Management

Timing

The best timing of pruning for most plant material is following flowering. Workload balancing, however, often dictates dormant season pruning.

Growth Habit

Growth habit of specific plant material will determine optimum pruning method.

6.4 Training

Training in IPM alternatives for planting bed maintenance will be provided to field staff. Staff will receive ongoing training in:

- Basic horticulture care
- Growth standards, plant ID
- Soils
- Chemical application



CHAPTER 7 – Turf Management



7.1 Purpose

Turf provides a forgiving and resilient surface for many recreational activities and is the traditional "green carpet" that visitors associate with parks. Because turf varies substantially in use, so do turf management practices. Appropriate management ensures high quality turf where it is needed, such as on athletic fields and golf courses, and that the designed use of a site is met. The best management practices described in this chapter for turf management would also be applicable for city streetscapes with turf as a component of the landscape.

7.2 Background

The park system offers visitors a wide variety of turf, including lawns (both formal and informal), athletic fields, golf courses and meadows. Each type of turf requires a separate best management practice. The intensity of management ranges from very highly maintained golf course turf to meadow areas that may get mowed only once a year as a fire prevention measure.

Construction Issues

- Turf areas should be constructed with a minimum slope of 2% to promote surface drainage and a maximum of 15% to allow riding mowers to safely access the areas.

7 Turf Management

- Whenever possible, the existing soil should be amended with sand and a minimum of 6" of topsoil to provide a drier surface area. Dry areas allow easier and earlier (in the mowing season) maintenance.
- Trees, signposts, benches and other park amenities should be carefully placed in turf areas to reduce the need for hand trimming. If possible, these amenities should have the turf immediately surrounding them removed (such as for a tree ring) to protect the amenity and to facilitate more efficient turf care.
- Whenever possible, seeding should occur during the spring or fall months to insure maximum germination.
- Design a natural buffer area (no pesticide or fertilizer use) between turf and water bodies or drainage systems. If possible, this buffer should be 50 feet.

Plant Selection

Selection of grass species is based on site conditions, expected usage and maintenance standards. Sites with optimum growing conditions and high maintenance standards are seeded with blends of several species of perennial rye grass. Sites with poor drainage, partial shade and limited fertilizer applications require blends of perennial rye grass and red fescues.

7.3 Best Management Practices

The following BMPs apply to all City of Bellevue turf plantings. Some variations may apply to golf course turf.

Mowing

Frequency

The importance of regular mowing for promoting healthy turf cannot be over emphasized. Growth should be monitored and frequency increased to avoid removing more than 1/3 of the leaf blade. The following is the basic standard for mowing frequency:

Season	Frequency
March - October	Weekly
February & November	Monthly or as needed
December	As needed

Cutting Height

Mowing height should be 2 to 2.5 inches to promote healthier turf. Lower cutting height often results in scalping spots where the ground is uneven.

Mulch Mowing

Grass clippings should rarely be removed from mowed turf areas. The plant nutrients and organic material they contain play an important role in developing a healthy, productive environment for root growth.

- Mowing patterns should be alternated to avoid ruts and compaction from the wheels.
- Avoid driving on frozen turf.
- Avoid driving on wet ground where ruts will remain. Walk the site during wet conditions to do a visual inspection.
- Mowing equipment must be maintained regularly, especially sharpening and adjusting of cutting edges.
- Ensure that grass clippings do not have the potential to be washed into stream or drainage systems, which can degrade water quality.

Trimming

- Trimming shall be performed by walk behind mowers and line trimmers in areas that cannot be accessed by riding mowers.
- Trimming should be coordinated to coincide with other mowing activities on the site.

Edging

- Edging shall be performed a minimum of 2 to 4 times per year, depending on the maintenance standard for the site. Turf edging is done to give a finished look to lawn areas that border paved surfaces or planting areas.
- At high visibility locations, edging shall be performed at a higher level of frequency.
- Edging should be performed with metal-bladed equipment whenever possible to prevent damaging turf edges.

Irrigation

- Automatic irrigation effectiveness shall be monitored on a weekly basis or more for sand based fields.
- Approximately 1 inch of water, including rainwater, shall be applied per week. During spring rainy seasons, irrigation techniques should be modified to fit the weather, as well as in the summer drought months. Theoretically, the irrigation cycle should be extended to the point just

7 Turf Management

before drought stress occurs. This period varies with soil conditions, weather, site usage and maintenance practices.

- Irrigation should be scheduled to promote deep root growth.

Fertilization

- In general, fertilizer blends containing phosphorus (P) are prohibited. The only exception may be when establishing newly seeded turf.
- Fertilizer shall be a slow release compound of Nitrogen (N), Iron (Fe) and Potassium (K). The ratio is dependent upon the time of year.
- Fertilized turf shall be pH soil tested as necessary to insure it is at the level most optimal for nutrient absorption.
- Each application should not exceed 1 lbs. of N per 1000 square feet.
- Applications during heavy rainfall shall be avoided to prevent runoff.
- Applications in very hot weather shall be avoided.
- Irrigation should be operational before growing season applications.
- Sprinkler heads should be marked to avoid damaging them during tractor applications.
- Excess fertilizer shall be removed from hard surfaces immediately.
- Micronutrients and lime should be added, as soil tests indicate.
- Site-specific fertilizer restrictions must be observed. Site-specific cautions include not using any fertilizer on turf areas adjacent to streams and wetlands and prohibiting applications within 25 feet of lakes and waterways.

Aeration

- Aeration shall be done 2 to 3 times per year, or as needed, using .75-inch hollow or solid tines.
 - Best periods: March/April, late June, and late August.
 - Technique: Make at least 2 passes at 90-degree angles.
- Areas with drainage problems should be deep-tine aerated 1-2 times per year using 1-inch-by-6-inch hollow or solid tines.

Top Dressing

General-use top dressing mix shall be used, and should be primarily sand with minimum organic matter.

- Frequency: most effective when done lightly and frequently.
- Each application should be about ¼ inch.

Over-seeding

Heavily impacted areas should be over-seeded at least once per year. The best practice is to over-seed in fall and slice seed in spring at a rate of 5 lbs. per 1000 ft². The following site characteristics, usage and maintenance practices shall guide seed selection:

- Ideal sites with full sun, good drainage and reasonable fertility are suited for perennial ryegrass blends.
- Lawns that are in partial shade or poorly drained should be seeded with mixes of perennial rye and fescues.
- Remove leaves and debris off of turf prior to over-seeding.
- Keep leaves and debris off turf of as much as possible after over-seeding to promote successful germination of grass seed.

Site Standards

Site standards for turf vary by landscape classification. Landscape classifications include prominent, general and non-irrigated lawn areas, steep slopes, meadows, soil or sand based athletic fields, synthetic athletic fields and bathing beaches.

Prominent Irrigated Lawn Areas

These are high-visibility or high-use landscapes. Some examples are community center lawns, popular picnic or sunbathing areas, lawns adjacent to busy arterials, beach parks, City buildings, community parks and the Bellevue Botanical Garden or smaller neighborhood parks where the lawn is the most significant amenity. Maintenance of these areas should be comparable to an athletic field with additional emphasis on trimming and edging.

- Soil shall be pH tested to determine fertilization requirements. Based on pH test results, 3 to 4 applications per year of fertilizer mix shall be applied.
- Soil aeration should occur 2 to 3 times per year with conventional 0.75-inch hollow tines.
- Over-seed the entire lawn at least once per year at 5 lbs. per 1000 ft². Monthly applications should occur in high-use areas.

General Irrigated Lawn Areas

These are lawn areas in parks of various types where irrigation is available.

- Apply N-K ratio fertilizer at 1 to 2 lbs. N per year, per 1000 ft², in 1 to 2 applications. Preferable fall N-K ratio is 15-0-31 with 6% iron and preferred spring N-K ratio is 22-0-22 with 6% iron.

7 Turf Management

- Soil aeration should occur 1 to 2 times per year with conventional 0.75-inch hollow tines.
- Over-seed as needed. Over-seeding is best done in April/May and October.

Non-Irrigated Lawn Areas:

These are lawn areas in parks of various types where irrigation is not available.

- N-K fertilizer should be applied once in October.
- Over-seed as needed. Over-seeding is best done in October.

Steep Slopes

Mowing and maintaining turf on steep slopes can be hazardous. Whenever possible, low growing shrubs or ground covers should be planted on steep slopes. This will greatly reduce maintenance needs and increase erosion control. If turf is ever required on a steep slope, the following management practices should be followed:

- Grass growth should be controlled mechanically with line trimmers.
- Turf growth regulators should be sprayed to extend trimming cycle.
- Consider leaving un-mown or mowing only 1 or 2 times per year.
- Consider replacement of existing turf with low growing shrubs or groundcovers.

Meadows

Meadows are unique environments that function primarily as wildlife habitat.

- Mowing should be infrequent with the goal being brush suppression and fire control. Analyze site for potential fire threat and fire control strategies.
- Successful establishment of native species requires that they have the opportunity to set and release seed before mowing.
- Site access routes should consider maintenance, interpretive value and habitat preservation.
- Species selection should be matched with existing available groundwater.
- Location of meadow should attempt to link other wildlife areas into larger contiguous habitat areas.
- Scheduling and timing should minimize impacts to wildlife nesting and habitation.
- One mowing every 2 to 3 years may be sufficient for woody brush control. Firebreak areas may require more frequent mowing to maintain. Mowing heights should be 3 to 5 inches.

Soil-Based Athletic Fields

These athletic fields are generally composed of native soil formed on-site with minimal amendment. These facilities are characterized by scheduled play. Drop-in

fields are maintained as general irrigated lawn unless there is exceptionally high usage.

- Soil shall be pH tested every 2-4 years. Add lime as needed to ensure optimum nutrient intake.
- N-K fertilizer shall be applied at a ratio at 2 to 6 lbs. of N per year in 3 to 4 applications.
- Soil aeration should occur 4 times per year with conventional 0.75-inch hollow tines. Field should be aerated with deep tines every 1 to 2 years.
- Over-seed the entire field at least once per year at 5 lbs. per 1000 ft², or about 375 lbs. per soccer field. Monthly applications should occur in heavy wear areas, such as the goalmouth, during the playing season.

Sand-Based Athletic Fields

These fields are entirely composed of imported sand and are known for their outstanding drainage capability.

- Irrigation shall occur more frequently than on soil fields.
- Apply N-K ratio fertilizer at 3 to 6 lbs. of N per year in 6 to 8 applications, depending on turf type and time of year.
- Soil aeration should occur 2 to 3 times per year with conventional 0.75-inch hollow tines. Deep-tine aerating (6"+) every 2 to 3 years should also be done.
- Over-seed the entire field or ballfield at least once per year at 5 lbs. per 1000 ft², or about 375 lbs. per soccer field. Monthly applications should occur in heavy wear areas, such as goalmouths, during playing season.

Bathing Beaches

- Apply 2 to 6 lbs. of N fertilizer per year in 2 to 3 applications of a slow-release product.
- Special care should be taken to not fertilize in advance of heavy rains or before expected heavy park use periods.
- Soil aeration should occur 2 to 3 times per year with conventional 0.75-inch hollow tines.
- Over-seed the entire lawn at least once per year at 5 lbs. per 1000 ft². Monthly applications should occur in heavy wear areas.

Synthetic Turf Athletic Fields

Maintaining a synthetic turf field is essential for optimum appearance, safety, performance and field longevity. Maintenance of a synthetic field typically consists of cleaning, stain removal, minor seam repair, grooming, infill material redistribution, and management of infill compaction. A regular maintenance schedule should include:

7 Turf Management

- Debris removal: Daily
- Aggressive surface cleaning: Biannually
- Grooming: Monthly
- Infill replenishment/redistribution: Weekly for high traffic areas on synthetic baseball infields, monthly for all other sports.
- De-compaction: Monthly

The synthetic turf manufacturer/installer should provide detailed written maintenance instructions, suggested warranty guidelines and training of maintenance personnel.

7.4 Training

- All park maintenance field staff should have training in basic turf management.
- The City mower operators have specific training regarding mowing heights and patterns.



CHAPTER 8 – Streetscape Management



8.1 Purpose

Attractive roadside landscaping improves livability within our community, and helps to make Bellevue a “City in a Park”. These “streetscapes” activate the street environment by engaging pedestrians and improving the roadway experience for everyone, and providing connectivity for the Parks system. Nearly 40 years of scientific research documents the positive impact that green infrastructure has on local economics, mental and physical health, public safety, water quality, and worker productivity.¹ Developing and maintaining safe, attractive, and sustainable streetscapes serves important public needs, manages assets wisely, and enhances the character of adjacent uses.

8.2 Background

Landscaping within public rights-of-way and easements must satisfy many rules and standards, as well as practical and aesthetic objectives. Above ground features must meet accessibility, visibility, safety and urban design standards. The area below streets and sidewalks must accommodate numerous utilities such as water, sewer,

¹ For more information visit *Green Cities: Good Health* at <http://depts.washington.edu/hhwb/>.

8 Streetscape Management

electric, storm drainage, irrigation and telecommunications facilities. Landscaping, street trees, benches, bus stops and other amenities share limited public and private streetscape spaces. For these landscapes to be successful, they must be well designed and constructed. Once installed, adequate funding and skilled maintenance is necessary to maintain and increase value for the public.

The Best Management Practices described in this chapter are intended to help streetscapes reach their potential, support city livability policies, and contribute to Bellevue’s image as a “City in a Park.”

Policy Overview

The practices described in this chapter implement policies set out in a variety of planning initiatives and city codes, including but not limited to the City of Bellevue Comprehensive Plan (Table 8.1), the Bellevue City Code (BCC), and the Land Use Code (LUC).

Table 8.1

Streetscape management is driven by several policies set out in the City of Bellevue 2015 Comprehensive Plan.

<p>Environmental Element: Policies 12, 13, 24, 45, 46, 49, 71, 97</p> <ul style="list-style-type: none"> • Establishes a 40% citywide tree canopy goal • Promotes preservation of significant trees and canopy loss mitigation • Supports low impact development techniques • Directs the city to pursue integrated site planning early in project development
<p>Land Use Element: Policies 2, 13, 32, 33</p> <ul style="list-style-type: none"> • Directs city to preserve existing tree canopy • Acquire and enhance landscaped areas to improve livability and neighborhood character
<p>Parks, Recreation & Open Space Element: Policies 31, 33</p> <ul style="list-style-type: none"> • Directs city to manage street tree resources for long-term vitality • Calls for conserving resources through efficient maintenance and operational procedures
<p>Transportation Element: Policies 51, 111, 139, 144</p> <ul style="list-style-type: none"> • Provides sufficient space in the ROW for trees and landscaping • Recognizes the health benefits of walking and bicycling • Protects and enhances the natural and built environment
<p>Urban Design & the Arts Element: Policies 2, 4, 12, 37, 38, 42, 44, 47, 54-57, 64-71, 74-76</p> <ul style="list-style-type: none"> • Promotes the quality and safety of urban environments through the preservation and enhancement of trees, species selection, low-impact development standards and site design • Directs use of landscaping to minimize impacts to neighborhoods • Promotes water conservation through irrigation system design • Directs city to provide adequate rooting space for trees in order to limit damage to sidewalk and street infrastructure

Streetscape Maintenance Requirements

Responsibility for maintaining landscaping within the right-of-way and easements belongs to the abutting property owner, unless accepted by the City. The following considerations are important for property owners to understand (see BCC 14.06.110):

- Trees and landscaping along street frontages may be required to be retained and maintained even if these amenities are on private property. *BCC 14.60.110 and 14.60.120; LUC 20.20.520 and 20.25.060*
- All work in the right-of-way is subject to Right-of-Way Use Permits and/or Clearing and Grading Permits. To learn more about the permitting needs for your project, call Service First at 425-452-6800.
- Property owners are responsible for ensuring that landscaping fronting their property does not obstruct driver or pedestrian sight distance as described in the Transportation Department Design Manual. *BCC 14.60.240*
- Property owners are responsible for maintaining all landscape materials in the right-of-way to industry standards (see section 8.3, "General Standards"). *BCC 14.06.100 and BCC 14.60.120*
- Illegal clearing, cutting, damaging, topping, pruning that is not in accordance with industry standards, or removing of street trees is a civil violation and subject to monetary penalties. *BCCs 1.18.045, 3.43.335, and 14.60.040*

Management Categories

Vegetation in Bellevue's right-of-way is classified into one of three management and maintenance categories:

1. **Formal Arterial Landscaping** — Landscape improvements in urban centers and along arterial streets in the right-of-way are often called "streetscapes". This vegetation requires the greatest level of maintenance and has the highest level of interaction with the community. Growing conditions are often impacted by urban stresses and vegetation likely to suffer from mechanical damage, biotic and abiotic disorders, and vandalism. These landscapes may be installed as part of a City capital investment project or through private development. The Parks & Community Services Department accepts management responsibility for most of these sites.
2. **Informal Roadside Vegetation** — Vegetation growing in the right-of-way that is naturally occurring and does not follow a predetermined planting plan. The plant mix generally consists of native species, but non-native and invasive plants are common. Vegetation that encroaches on the roadway is normally managed by the Transportation Department using articulated mowers or hand tools. Adjacent property owners are expected to provide

8 Streetscape Management

regular maintenance to address any aesthetic concerns within the community.

3. **Residential Landscapes** — Residential landscapes contribute significantly to the City’s urban forest and are the greatest component of city-wide tree canopy cover. Landscaping along residential streets includes front yards, planting strips and medians installed by developers or homeowners in residential subdivisions, and landscapes maintained by homeowner’s associations near the entrances of neighborhoods. The adjacent property owner or HOA is expected to maintain all vegetation within these areas.

8.3 Best Management Practices

The City of Bellevue maintains approximately 150 formal landscape sites within the right-of-way or easements, covering 190 acres City-wide. This land includes a wide variety of cover types and landscape features, including concrete walkways, gravel paths, landscaped medians, turf, groundcover, shrubs and over 10,000 trees.

General Standards

Landscaping within the right-of-way shall be maintained in accordance with the following industry standards:

ANSI Z133	Safety Requirements for Arboricultural Operations
ANSI A300	Industry Standards for Tree Care Practices
ANSI Z60.1	American Standard for Nursery Stock

Planting Bed Management

Basic streetscape site maintenance involves caring for shrubs, trees, turf and other landscape elements in planting beds. Most planting beds in a streetscape setting take the form of planting strips and medians in the right-of-way. A majority of the right-of-way landscapes managed by the Parks Department are maintained by private contractors, under the direction of a Contract Administrator. Contracts are awarded through a competitive process that balances a firms’ ability to successfully complete required tasks, protect the safety of pedestrians and motorists, and cost.

This chapter addresses planting bed management issues specific to right-of-way landscaping. See Chapter 6 – Planting Bed Management for more information on standards and BMPs employed throughout the Parks system.

Workload Plans

Contracts for streetscape landscape maintenance are structured by workload plans that specify work included, task frequencies and time standards per visit.

The majority of sites are visited on a weekly basis, and frequencies and time standards are based on the most efficient way to provide service. Spacing frequencies farther apart requires that additional time be allotted to the time standard for equivalent results. Reducing frequency or time standards per task leads to degradation of the site. Once degraded, capital costs to return the assets to existing standards are far more costly than any short-term savings from reductions.

Work typically includes:

- Vegetation mowing, edging, trimming, pruning and weeding
- Removing leaves and debris from hard and soft surfaces
- Operation and maintenance of above and below ground irrigation systems
- Litter pickup and garbage removal
- Cleaning garbage containers and replacing liners

Activity	Unit of Measure	Inventory Quantity	Time Standard	Time Std Per Visit	Frequency Per Month												Annual Freq	Annual Hours	
					J	F	M	A	M	J	J	A	S	O	N	D			
Turf																			
Mowing	SQ FT	10000	200	Min	50.0			4	5	4	4	5	4	5	4	1	36	30.00	
Trimming	LIN. FT	2500	20	Min	125.0			4	5	4	4	5	4	5	4	1	36	75.00	
Edging	LIN. FT	160	85	Min	1.9			2	3	2	2	3	2	2	2		18	0.56	
Fertilize Fine Mow	SQ FT	10000	190	Min	52.6			1				1				1	3	2.63	
Herbicide (Turf)	SQ FT	10000	160	Min	62.5					1							1	1.04	
Rough Mow	SQ FT	5000	300	Min	16.7			2	2	2	2	2	2	2	2		16	4.44	
Fertilize Rough Mow	SQ FT	5000	190	Min	26.3			1								1	2	0.88	
Shrub Beds																			
Bed Weeding & Hoeing	SQ FT	10000	175	Min	57.1	1	1	3	5	4	4	5	4	5	2	1	1	36	34.3
Bio Filter/Filterra beds	SQ FT	0	25	Min	0.0	1	1	3	5	4	4	5	4	5	2	1	1	36	0.0
Trim G. C.	LIN. FT	2500	50	Min	50.0				1		1		1		1		4	3.3	
Prune Shrubs	SQ FT	10000	100	Min	100.0			1		1		1			1		4	6.7	
Herbicide (Shrub Beds)	SQ FT	10000	160	Min	62.5				1								1	1.0	
Street Trees																			
Tree Grates	Each	0	10	Min	0				1								1	0.0	
Tree Pruning	Each	10	30	Min	300.0										1		1	5.0	
Tree Fert/Mulching	Each	10	5	Min	50.0			1						1			2	1.7	
Hard Surface																			
H. S. Sweep	SQ FT	5480	800	Min	6.9	2	2	4	5	4	4	5	4	5	4		39	4.5	
H. S. Weeds	SQ FT	5480	800	Min	6.9			1						1			2	0.23	
Leaf/Litter/Debris																			
Leaf Removal (Total Site Ft²)	SQ FT	30480	400	Min	76.2										1	4	4	9	11.4
Litter (Total Site Ft²)	SQ FT	30480	1200	Min	25.4	5	4	4	5	4	4	5	4	5	4	4	4	44	18.6
Garbage Collection	Each	0	3	Min	0.0	5	4	4	5	4	4	5	4	5	4	4	4	52	0.0
Encroachment	LIN. FT	160	100	Min	1.6			1		1		1			1		4	0.1	
Windfall Debris	Included																		
Lane Closure/TCS services	Each	0	480	Min	0.0			1		1		1			1		4	0.0	
Green Machine																			
Green Machine	SQ FT	5480	100	Min	54.8	1		1		1		1		1		1	6	5.5	
Pervious Surface Moss Control	SQ FT	5480	50	Min	109.6									1			1	1.8	
Irrigation Labor																			
Start-up/Winterize	Per Zone	4	20	Min	80.0				1						1		2	2.7	
Irrigation Repair	Per Zone	4	30	Min	120.0			1	1	1	1	1	1	1			7	14.0	
Irrigation Fees																			
Water Billngs (Conventional Zones)	Per Zone	3	40	GPM	120.0				100	140	180	200	170	140	100		1030	\$ 1,316.97	
Water Billngs (Drip Zones)	Per Zone	1	10	GPM	10.0				300	420	540	600	510	420	300		3090	\$ 329.24	
Irrigation Meter Fees	Each	1.00	74.8	\$	\$ 74.83	1		1	1	1	1	1	1	1	1	1	6	\$ 448.98	
Controller Power Meter Base Rate	Each	1.00	10.7	\$	\$ 10.72	1		1	1	1	1	1	1	1	1	1	6	\$ 64.32	
Drainage Fees	Acre	0.00		\$	\$ -	1		1	1	1	1	1	1	1	1	1	6	\$ -	
Hand Watering (non irrigated areas)	SQ FT	0	0.05	\$	\$ 0.0					2	4	4	4	2			16	\$ -	
Hand Watering (Gator Bags)	Each	0	20	\$	\$ 0.0					2	4	4	4	2			16	\$ -	

Figure 1. Example Workload Plan

8 Streetscape Management

Inspections

Contracted landscape work is typically inspected by City staff on a weekly basis in order to ensure contract compliance. Inspections are also used to identify safety hazards, graffiti, damage to plants and damage to irrigation due to vandalism or traffic accidents.

Traffic Control

Streetscape maintenance tasks that impact traffic or pedestrian flow require specialized supervision and additional permitting. For these sites, traffic control plans are either included in contract documents or developed and permitted as needed. A Certified Traffic Control Supervisor may be required to be on site for work that impacts traffic on arterial roads.

Planting Bed Renovation

Even with regular maintenance, streetscape planting beds have a life cycle of 15-25 years. Bed renovation is prioritized based on age, condition, visibility, available funding and the opportunity to pursue revitalization projects in partnership with other departments. Renovation may include amending and improving the soil, revitalizing broken irrigation systems and installing new plant material.

Landscape Pruning

Pruning trees and shrubs is essential to supporting their growth potential, avoiding hazards and minimizing infrastructure conflicts. All pruning is conducted according to current ANSI Z133 standards and is timed appropriately for each species to maximize plant health and aesthetics.

Shrub and Ornamental Grass Pruning

Pruning needs are minimized by selecting species that will not grow too large for planting locations. Shrubs in the right-of-way should not be maintained in a hedge – the natural form should be preserved whenever possible. The mature height of landscape plants shall not exceed 24" when sight distance standards apply. Mature plant spread should not exceed the space available within the planting strip and care is taken at the time of installation to ensure plants will not encroach on the sidewalk.

Landscape plants are pruned in order to ensure the following standards are met:

- Pedestrian or bicycle travel is not impeded
- Sight distance standards are maintained
- Timing is appropriate to encourage flowering/aesthetic benefits
- Frequency occurs at the optimal time to minimize pruning needs

Street Tree Cycle Pruning Program

The purpose of the Street Tree Cycle Pruning Program is to support tree health, encourage appropriate form and structure, minimize potential safety hazards, and to maintain pedestrian and vehicle clearance on adjacent streets and right-of-ways.

Established street trees are pruned on a regular cycle by qualified contractors. The actual cycle varies depending on funding - typically every 6 to 10 years as needed.

Cycle pruning contracts typically address the following issues:

- Health, structure and form:
 - Remove multiple leaders, crossing branches, suckers, etc
 - Remove dead or broken branches and diseased tissue
 - Shorten limbs that are imbalanced or have included bark
- Sidewalk and roadway clearance requirements:
 - 7' clearance over sidewalks
 - 14' clearance over streets
 - branches do not obstruct pedestrian or bicycle travel
 - Sight distance standards are maintained
- Ensure growth is directed away from common streetscape conflicts:
 - Traffic signage
 - Street lights
 - Power lines
 - Buildings and awnings

Young Tree Pruning

The first few years after planting is the most important period to correct common structural flaws in trees that can lead to serious problems and high maintenance costs as trees age (multiple leaders, crossing branches, conflicts with adjacent buildings, etc.). Pruning young trees requires a high level of skill and is performed by trained staff. All new trees planted in Bellevue's managed streetscapes are proactively pruned during the first 5 years after planting.

- During the first two years, only prune when clean cuts are needed to correct ripped or damaged branches.
- Gradually remove lower limbs annually to provide clearance to roads and sidewalks, and train branches away from signals, signs and buildings.
- Once appropriate clearance above streets and sidewalks is established, trees are assigned to a long-term pruning schedule (see "Street Tree Cycle Pruning Program").

8 Streetscape Management

Watering

Ongoing application of water is crucial to maintaining the City's investment in landscape plants. Due to the harsh conditions in arterial landscape spaces created by poor quality soil and limited rooting space, reflective heat and increased wind speeds caused by traffic, supplemental water is typically required to maintain healthy plants, even with drought tolerant species. At a minimum, landscaping should be watered weekly through the first three years after installation.

Irrigation

Approximately 2,250 irrigation zones and 90,000 sprinkler heads deliver water to the majority of Bellevue's streetscapes. Maintaining and improving irrigation systems is essential to keeping resource costs low and adapting management to species needs, seasonal weather and climatic variation. See Chapter 4 – Irrigation and Water Management for more information on equipment standards and BMPs.

Installation of irrigation may be required as a part of street frontage improvements (BCC 14.60.110B). Irrigation installations in the right-of-way shall meet all of the following requirements:

- Low volume efficient spray systems are required within the right-of-way. Drip irrigation systems should be limited to narrow beds under 3' wide.
- A separate meter and controller dedicated to right-of-way irrigation shall be installed at a location determined in consultation with Parks staff.
- City staff must have 24-hour access to the meter and controller.
- Right-of-way irrigation shall use a smart controller that can incorporate ET (evapotranspiration) information or sensors to initiate, adjust, or suspend irrigation to meet plant water needs and maximize efficiency.
- 6" diameter sleeves shall be installed under all sidewalks and driveways.
- Schedule 40 irrigation pipe is required. Class 100 and 200 irrigation pipe is prohibited in the right-of-way.
- Installation and repair must be performed by experienced or certified irrigation professionals.
- All work on new or existing irrigation systems supplying water to landscaping in the right-of-way must be inspected and tested by City staff before it is covered by soil.

Hand Watering

In certain cases, automatic irrigation may be either unavailable or insufficient for keeping establishing plants healthy through the dry season. In these cases, plants are hand-watered using a watering tank or other water sources available.

Street Trees of Bellevue

The Street Tree and Arterial Landscape workgroup within the Parks & Community Services Department maintains over 10,000 trees in formal arterial landscape areas, comprised of over 120 different taxa. Parks staff provide assistance to other departments within the City to evaluate existing trees in the right-of-way or select tree species for new plantings.

Tree Selection Criteria

Appropriate selection of trees is important for many reasons. Tree selection adds to neighborhood character, minimizes conflicts with other infrastructure, ensures adequate clearance over sidewalks and streets, reduces impacts from pests and disease, and helps to soften the transition between urban spaces and Bellevue's natural forest setting.

Trees should be selected on the basis of functional uses, growth characteristics, site adaptation, the amount of care it will require and aesthetic goals. It is important to plant the right tree in the right place. The following criteria is considered during species selection:

- Tolerance of site conditions: soil quality or drainage, pollution intensity, sun/shade, water availability, wind or temperature fluctuations, etc.
- Site conflicts: overhead power lines, adjacent parking or sidewalk, sight distance conflicts, quantity of available soil, etc.
- The quality and quantity of available nursery stock
- Plant features such as leaf color, mature size, flowers, thorns, etc.
- Disease resistance or pest issues

Designated Street Trees

Specific tree species are designated by code in some parts of Bellevue. In Downtown, new street trees must be installed according to Plate B (LUC 20.25A.060). Small, medium, and large categories of trees are identified in order to coordinate the selected species with spacing and soil requirements (see "Materials Standards"). In BelRed, street trees are regulated under LUC 20.25D.110 and the BelRed Streetscape Design Guidelines. The goal of designated street trees is to define neighborhoods and create cohesive corridors. Existing trees may not conform to code, however. In these cases, tree retention should be prioritized over conformity wherever possible.

Most of Bellevue's street trees are not regulated by Code. The Parks Department Street Tree & Arterial Landscape program manages a comprehensive list of existing trees and makes recommendations based on performance and availability for development on a case-by-case basis.

8 Streetscape Management

Trees Not Recommended for Any Site

Due to susceptibility to pests or disease, the following trees are not recommended for planting anywhere in this region and often require removal and replacement.

Botanical Name	Common Name	Issue
Betula species	Birch species	Bronze birch borer
Fraxinus species	Ash species	Emerald ash borer
Populus nigra	Lombardy poplars	Vulnerable to fungal leaf spot

Invasive Trees Recommended to Avoid

Invasive species may propagate to areas outside of their intended locations and should be avoided if possible.

Botanical Name	Common Name	Issue
Acer platanoides	Norway maple	Self-seeds into natural areas, over-represented in Bellevue's urban forest inventory
Ailanthus altissima	Tree of Heaven	Class C Noxious weed
Crataegus monogyna	English hawthorne	Class C Noxious weed
Ilex aquifolium	English holly	King County weed of concern
Prunus laurocerasus	English/Cherry laurel	King County weed of concern
Robinia pseudocacia	Black locust	King County weed of concern
Sorbus aucuparia	European mtn. ash	King County weed of concern

Trees Not Recommended for Streetscapes

Sites directly adjacent to the roadway are typically more stressful and have some site limitations that should be considered during species selection. The following trees are not recommended for streetscapes or sites adjacent to homes or infrastructure.

Botanical Name	Common Name	Issue
Acer macrophyllum	Bigleaf maple	Decay/other issues increase hazard potential
Acer saccharinum	Silver Maple	Structurally weak branches
Alnus rubra	Red alder	Decay/other issues increase hazard potential
Amelanchier species	Serviceberry	Vulnerable to rust diseases
Cupressus leylandii	Leyland Cypress	Canker diseases west of the Rockies; grows vigorously to block sidewalks and cause sight distance problems
Pinus nigra	Austrian pine	Vulnerable to Dothistroma needle blight
Pinus ponderosa	Ponderosa pine	Vulnerable to Dothistroma needle blight
Populus tremuloides	Quaking aspen	Decay/other issues increase hazard potential
Populus trichocarpa	Black cottonwood	Weak branch attachments increase hazard potential; rapid trunk growth poses issues for infrastructure
Prunus laurocerasus	English/Cherry laurel	Grows vigorously to block sidewalks and causes sight distance problems
Prunus tree species	Flowering Cherry	Susceptible to fungal diseases
Salix species	Willow species	Decay/other issues increase hazard potential

Street Tree Replacement Program

The Street Tree Replacement Program helps to maintain tree canopy throughout the City. Tree replacement reduces hazards from dead, damaged and dying trees, and supports attractive and inviting pedestrian environments. Staff performs the following tasks for trees that the Parks Department manages:

- Maintain an inventory of trees managed by the Parks Department, including dead, dying and missing trees
- Survey all trees in the inventory annually to identify hazards
- Remove and replace dead or hazardous trees as needed
- Replace trees in vacant planting locations
- Collect compensation for trees killed or damaged by vandalism or vehicle impacts per BCC 1.18.045

Tree Removal

Like any living plant, trees have a life cycle and inevitably decline as they age. All trees are subject to diseases, physical damage, insect infestation and drought conditions. Targeted removal restricts the spread of disease and reduces the possibility of human injury or property damage. When a tree that the Parks Department manages is damaged or visibly declining, City staff or a professional arborist will evaluate the tree to determine if removal is warranted or necessary.

Occasionally, healthy trees may need to be removed. Trees may be removed if approved construction activities will damage them to the extent that their health would be compromised, if it is blocking roadway sight lines, if overhead utilities cause excessive topping to be necessary, or if other issues arise that present a risk to public or private property.


Bellevue has tree canopy goals of 40% coverage City-wide – but we have been steadily losing canopy for the last few decades. Part of the toolkit for reversing the trend and reaching these goals includes collecting the base value of trees in the right-of-way that are determined to need removal for reasons other than health of the tree (per BCC 1.18.045 and BCC 14.60.120). Unless otherwise exempted by code, the City must be compensated for this loss of green infrastructure. The payment is put into a fund dedicated to planting trees in more appropriate locations. This fee is not meant to be a penalty, but rather an incentive to work proactively with the City to keep the trees in mind. It is always our preference to save trees rather than collect a fee. Tree value is determined using the industry standard ISA Trunk Formula Method, which takes into account tree species, size, health, site conditions, existing conflicts and replacement cost.

8 Streetscape Management

Tree Planting Procedure


Because installing trees is an investment in a long-term asset, care should be taken to ensure that it is planted properly. An improperly planted tree will develop root issues that may cause the tree to die prematurely.

1. Remove any container, burlap or wire from the root ball; tease or scour surface of root ball by rubbing with hands or clipping with pruners. If a wire basket or burlap is present, remove the top 2/3 using bolt cutters and a sharp knife. Leave the remaining wire and burlap when planting.
2. Locate the root collar by removing the substrate from the top of the root ball. Confirm that roots do not circle the trunk, make contact with bark or make abrupt turns toward center of root ball. Some root problems may be corrected on-site under the supervision of a project arborist. Per WSDOT Standard specifications 9-14.6(2), all plant material must meet the latest edition of the American National Standard for Nursery Stock (ASNS), ANSI Z60.1.



3. Excavate a circular planting hole with sloping sides and rough surfaces to the depth of the root ball. The diameter of the hole shall be 3X the width of the root ball unless otherwise specified in the contract drawings.
4. Place root ball in hole and confirm that the top-most structural root (root collar) is located just above final grade, allowing for minimal settling. Adjust depth of hole as necessary by removing or adding soil. Firmly tamp center of hole to avoid excess settling.
5. Gently rotate plant to position strongest secondary branches away from vehicle or pedestrian traffic.
6. Backfill planting hole in 6" lifts. Gently tamp soil by hand after each lift, eliminating any voids. Confirm final grade is level with first structural root. Water thoroughly after backfilling to settle the soil, eliminate air pockets and re-wet the root system.
7. Thoroughly water the planting soil and root ball immediately after planting.

8. Apply 2" layer of mulch (see "Materials Standards") above planting area. Mulch shall taper back to grade at trunk to avoid contact with bark tissue.
9. Remove any wrapping materials, ribbons and twine.
10. If staking is required, always locate stakes outside of planting hole. Stakes and ties shall be removed at the end of the first year.



Tree Grate Program

Many street trees have decorative grates installed at the base to increase the walkable surface of a sidewalk. As the trees grow, these grates may shift and cause harm to the tree trunk or create potential tripping hazards for pedestrians. Maintenance focuses on the following priorities to maintain pedestrian safety and tree health:

- Increase grate aperture as trees grow
- Adjust or remove unstable grates
- Respond to reports and complaints of broken or unstable grates
- Remove debris and weeds from tree wells annually
- Identify and address root strapping, girdling roots, adventitious roots, suckers and irrigation damage
- Evaluate trees for additional needs, such as pruning for pedestrian clearance, vehicle clearance, sight distance or road signage

Low Impact Development Best Management Practices

Natural Drainage Practices (NDPs) are Low Impact Development BMPs that are often required, and should always be considered, to manage stormwater within the right-of-way. NDPs are an important part of City efforts to manage storm water and improve water quality running off of roads and other paved surfaces. Landscape contractors generally perform maintenance on the facilities maintained by the Parks Department on a weekly basis. The following documents describe the minimum standards for maintaining NDPs:

- City of Bellevue Utilities Department Surface Water Engineering Standards
- City of Bellevue Utilities Department Storm and Surface Water Maintenance Standards

8 Streetscape Management

Holiday Lighting

A Right-of-Way Use Permit is required to install holiday lighting on trees or other structures in the right-of-way. Applications can be submitted at www.mybuildingpermit.com. Additional information is available by emailing RightOfWayUse@bellevuewa.gov or calling (425) 452-4189.

- Unless otherwise stated in the Right-of-Way Use Permit, lights must be removed from trees between February 1st and October 31st.
- Trees may not be pruned or otherwise altered to attach lighting or decorations. No stapling or nailing allowed.
- It is the responsibility of the adjacent property owner to maintain any electrical equipment within the right-of-way and ensure compliance with National Electric Code (NEC) and Bellevue City Code.

Materials Standards


Plant Quality, Approval and Care

Careful attention during plant installation can prevent common issues that lead to increased maintenance costs. Ensuring high quality plant stock and proper care during storage, shipping and after installation can prevent the decline or death of plants and avoid unanticipated expenses.

The quality of each plant should be visually checked either at the nursery before shipping or at the time of delivery. Plants should exhibit good form, vigor and shape for their species and be free of major deformities. Roots (whether in balls, grow bags or containers) should be firm but not hard, healthy in appearance and evenly spaced around stems. Root balls should be free of girdling roots or an overabundance of root material for the size of the container (i.e. root bound containers). Branches should be evenly spaced throughout the plant and not clustered in one location.

The following specifications shall constitute acceptable and rejectable material upon delivery to project sites:

- Plants exhibiting crown form or unbalanced branch structure that cannot be corrected using standard practices will be rejected.
- Plants that arrive on-site with broken leaders will be rejected.
- Plants that have root defects that cannot be corrected using standard practices will be rejected.



Trees with excess circling roots will be rejected.

- All plant materials must be grown in a nursery under climate conditions similar to or harder than the project site.
- All plant materials shall meet or exceed the American Standards for Nursery Stock (ANSI Z60.1) most current version.
- Approved plant materials shall display other “acceptable” characteristics, per City of Bellevue standard details.

Soil Specifications

Not all soil is suitable for growing plants. Existing soils within the right-of-way are typically highly modified by construction activity (both past and present) and are of very poor quality. As a result, soil must be installed or amended as part of most new landscape installations.

The following products are pre-approved “Type A” for streetscape construction projects:

Soil Use	Approved Product (Provider)
Soil additions to established landscapes	Winter Mix (Cedar Grove), or Supreme Mix (Pacific Topsoils)
New Construction	Winter Mix (Cedar Grove)

All other products must meet the following specification for “Type A” topsoil:²

Sand	Greater than 0.05mm to less than 2mm – 60-70% by volume
Compost	30-40% by volume**
Silt	Greater than 0.002mm to less than 0.05mm – maximum of 35%*
Clay	Less than 0.002mm – maximum of 15%*
Organic Content	Percent of dry weight – 10% Minimum
Acidity (pH)	6.0 to 7.5
Physical contaminants (plastic, concrete, ceramics, metal, etc.) shall be less than 0.5 percent by weight. Plastic film shall be less than 0.1 percent by weight.	
Soil shall be free of phyto-toxic materials, viable seeds, roots or rhizomes of state listed noxious weeds	
Soluble salt contents shall be less than 3.0 mmhos/cm	

*Clay and Silt combined – no greater than 40%

**The compost component must meet the following requirements:

² Additional requirements may apply. Products that are not on the Approved Product Provider list must be approved by the City per the “Submittals” section in this document.

8 Streetscape Management

- Compost shall be the result of the biological degradation of recycled plant materials, under controlled conditions designed to promote aerobic decomposition
- Compost shall be certified in compliance with U.S. Composting Council STA program.
- Compost Maturity shall be greater than 80% in accordance with TMECC 04.10-A.
- Compost Stability shall be 7 or below in accordance with TMECC 05.08-B.
- Feedstocks shall originate from local recycling collection programs and contain a minimum of 10% post-consumer food waste.

Mulch Specifications

Mulching serves to conserve moisture, prevent soil erosion, suppress weed growth, moderate soil temperature and reduce compaction. See standard details for information on mulch placement and depth. More information on mulching is also located in Ch. 6 – Planting Bed Management. For right-of-way landscape installations, the following products are pre-approved:

Mulch Use	Approved Product (Provider)
Newly constructed beds, new plantings, beds needing nutrients, and after transplanting into established beds	Landscape Mulch (Cedar Grove) or Pacific Garden Mulch (Pacific Topsoils)
Formal established landscapes	Landscape Mulch (Cedar Grove)
Semi-formal and informal landscapes	Wood Chip Mulch

All other products must meet the following specifications:³

- Mulch for newly constructed sites shall be compost-based, 35%-50% bark and 50%-65% compost.
- The bark component shall be derived from Douglas fir, pine or hemlock species and not contain resin, tannin or other compounds in quantities that would be detrimental to plant life.
- The compost component must meet the following requirements:
 - Compost shall be the result of the biological degradation of recycled plant materials, under controlled conditions designed to promote aerobic decomposition
 - Compost shall be certified in compliance with U.S. Composting Council STA program.

³ Additional requirements may apply. Products that are not on the Approved Product Provider list must be approved by the City per the "Submittals" section in this document.

- Compost Maturity shall be greater than 80% in accordance with TMECC 04.10-A.
- Compost Stability shall be 7 or below in accordance with TMECC 05.08-B.
- Feedstocks shall originate from local recycling collection programs and contain a minimum of 10% post-consumer food waste.
- Mulch pH shall be between 5.5 and 7.5
- Physical contaminants (plastic, concrete, ceramics, metal, etc.) shall be less than 0.5 percent by weight. Plastic film shall be less than 0.1 percent by weight.
- Mulch shall be free of phyto-toxic materials, viable seeds, roots or rhizomes of state listed noxious weeds
- Carbon to nitrogen ratio shall be 25:1 to 35:1, as determined using TMECC 04.01 "Total Carbon" and TMECC 04.02D "Total Kjeldhal Nitrogen".

Submittals

At least 10 working days prior to placement of any soils or mulch on a project site, the supplier shall submit the following test results from an approved testing laboratory. The test should be prepared no more than 90 days prior to installation on the project site.

1. A one (1) gallon mix sample showing a representative sample of the material.
2. Grain size analysis results for Washed Sand and Sandy Loam.
3. STA/WSDOT Technical Data Sheet for Compost, from a STA accredited lab.
4. Soil fertility test, including the following parameters:⁴
 - Extractable analysis: nitrate nitrogen, ammonium nitrogen, phosphorus, potassium, calcium, magnesium, copper, zinc, manganese and iron.
 - Saturation extract values: calcium, magnesium, potassium, sodium, boron, sulfate, pH, lime content, salinity and sodium absorption ration (SAR).

⁴ The supplier shall be responsible for adding fertilizers and additives as recommended by the testing laboratory reports.

8 Streetscape Management

Soil Volume

Most urban environments are highly constrained, leaving little room for adequate soil volumes to support the trees we plant. In order to grow the large healthy shade trees without damaging adjacent hardscapes, we must provide enough soil.

All new trees require the following soil volumes, based on tree size:

- 500 ft³ : Small trees (10-25ft crown spread, ~8" mature DBH)
- 1000 ft³ : Medium trees (25-35ft crown spread, ~16" mature DBH)
- 1500 ft³ : Large trees (35+ft crown spread, ~24" mature DBH)

The following standards and exceptions apply to calculating soil volumes:

- The total soil volume provided for a tree shall be calculated (in cubic feet) by adding the available open soil volume to the available covered soil volume within a 50 foot radius of the tree.
- Open soil exclusively refers to either uncompacted native soils (no greater than 80% Proctor) or amended soils meeting the standards for approved "Type A" topsoil.
- Soil volumes for open soil shall be calculated (in cubic feet) by measuring the open soil volume area (in square feet) times the depth of the open soil, up to 3 feet.
- Covered soils shall be protected from compaction by a system of interlocking aggregate rock (structural soil) or by placement in a soil cell system.
- Soil volumes for covered soil shall be calculated by using only the space available to soil, and may not include the components providing structure (i.e. the volume of the aggregate in structural soil, or the of the soil cell system). A maximum of 25% of total structural soil volume may be counted toward available soil volume.
- The open and covered soil volumes are considered "available" to a tree only when they are directly connected to the tree by a continuous path for root growth no less than 24 inches wide and no less than 12 inches deep.
- Required soil volumes may be reduced up to 30% for trees sharing a continuous planter strip of at least 4 feet in width, or when soil cells form a direct path between planter pits. For example, the total required soil volume for large trees planted to this standard would be 1050 ft³.

8.4 Training

1. Provide training to all staff involved in construction activities to make sure they understand all construction site BMPs.
2. The site manager and other designated site managers shall receive the most recent training and education dealing with site management. This training includes the most recent advances for protecting trees on construction sites.
3. Staff that prune trees will be ISA certified. All contracted crews shall have at least one member on site that is ISA certified.
4. All contracted or volunteer planting crews shall be trained in proper shrub pruning and planting techniques by the site manager.
5. Streetscapes Contract Administrators and Lead Workers will be provided traffic control training. All contracted crews shall have at least one member with a Traffic Control Supervisor certification.



(This page intentionally left blank for note taking)



CHAPTER 9 – Trees & Natural Areas



9.1 Purpose

Trees and natural areas provide a multitude of benefits that enhance the quality of our lives. The maintenance and management of these valuable resources is essential for the long term welfare of Bellevue and its citizens. The health of the urban forest is a major indicator of the health of our ecosystem. This chapter identifies and defines the best management practices required to ensure a healthy urban forest.

9.2 Background

The Bellevue Parks Department manages over 2,100 acres of undeveloped natural areas consisting of forests, steep slopes, wetlands, riparian corridors, shorelines and meadows. The management and preservation of the City's natural areas is a long-term investment into the urban environment that must be managed with the same skill and diligence as any other City asset.

Public trees and forests in Bellevue can be classified into three categories:

1. Street Trees: Are part of improvements made within the City of Bellevue Right-of-Way through either Capital Improvement Program projects or private development. A detailed treatment of the Best Management Practices and City Codes associated with this resource is provided in Chapter 8 of this manual.

9 Trees & Natural Areas

2. Formal Park Areas: These trees require frequent maintenance and have a high likelihood of tree/people interaction. These trees also have a potential for mechanical injury and demand a high level of care and consideration during design and construction activities.

3. Natural Areas and Peripheries of Formal Park Areas: These trees require the least amount of maintenance because of their often remote and sheltered locations. The trees in these areas are managed not as individual trees, but rather as stands of trees linked to the associated plants and sites on which they reside. These trees can come in conflict with people when they occur along property lines, adjacent to man-made structures or near gathering places.

Design

Selection

Selecting trees that adapt well to their site and fulfill their landscape function is extremely important to the success and maintenance of a planting. The quality of young plants is also crucial. A plant species should be selected on the basis of its functional uses, its adaptation to the site and the amount of care it will require.

Landscape Functions

There are four main functions to consider when selecting trees to include in the landscape design:

1. Architectural Features: privacy, view enhancement and space articulation.
2. Engineering: reduce glare, direct traffic, filter air, reduce soil erosion and attenuate noise.
3. Climatic Influences: transpirational cooling; interception of solar radiation, reflection, and re-radiation; and modification of rain, fog and snow deposition.
4. Aesthetic Uses: form, color and texture.

Site Adaptation

It is important to plant the right tree in the right place. The intended landscape use and nature of a site should be considered when selecting for growth habit and ultimate size. Mature size is an important consideration. The tree should not outgrow its allotted space given such constraints as vistas and power-lines. Table 9.1 may be used as a guide in selecting the right tree.

Table 9.1 Tree Selection Factors

Feature	Benefit
Rate of Growth	Fast-growing trees tolerate difficult sites, are usually weak-wooded and subject to limb breakage; and generally are shorter lived. The opposite is generally true for slow-growing trees.
Wood Strength	When a tree decays or weakens, it can become a hazard to the surrounding area. Strength is based on the trees ability to withstand wind loads, snow bearing loads, water saturation or drought, and its adaptability to its surroundings.
Rooting	Roots keep the tree anchored in the ground. Through them pass nutrients and water that nourish and support the tree. Stressors such as: drought, flooding, disturbance, disease or damage can greatly affect tree roots and the health of the tree.
Plant Features	<ul style="list-style-type: none"> Leaves: Color, size, persistence Thorns and prickly foliage: Enhanced security vs. maintenance problems Flowers and fruit: Aesthetic consideration, wildlife habitat. Potentially increased maintenance.
Climate Adaptation	<ul style="list-style-type: none"> Plant hardiness and local minimum temperatures Moisture – natural or irrigated Light – reflect or allow for winter heating Wind – deflect or channel wind patterns
Soils	Poor soils can cause failure of planting. Amendment not desirable or feasible. Match plant to soil condition.
Air pollution	Choose trees with appropriate tolerance level.
Pest Resistance	Resistant plant material will reduce maintenance.
Native Plants	Native or indigenous plants may not perform as well as exotic or non-native species. Most urban landscape sites are no longer “native.” Soils, microclimates and water regimes have changed.
Selecting Quality Stock	Selection of quality planting stock is as important to success as selection of proper species, planting and maintenance. Root and shoot quality can determine not only performance but also survival.
Root Defects	Kink roots, girdling (circling roots) can eventually "choke" a tree.
Top & Trunk Characteristics	<ul style="list-style-type: none"> Height-to-Caliper ratio (see ANSI Z60.1 specs.) Crown configuration Branching pattern

9.3 Best Management Practices

The management and maintenance of trees by the City of Bellevue Parks & Community Services Department consists of a number of practices. The practices are covered in the following section and include: planting, pruning, removal, inventory and routine inspections, irrigation, fertilization and pest management. Activities associated with the protection and management of trees and vegetation before and during construction are covered in the Construction Site Management chapter.

Formal Park Tree Planting

- All plant material shall be nursery grown under climate conditions similar to or harder than at the site and meet or exceed The American Standards for Nursery Stock (ANSI Z60.1-1996).
- Ideal planting hole should be 2 to 5 times the diameter of the root spread or root ball.
- Minimum planting hole shall be 12 inches wider in diameter than root spread or root ball.
- The hole shall be no deeper than the ball and the ball shall sit firmly on undisturbed subsoil.
- Native soil shall be used to backfill the planting hole except in situations where the existing soil is contaminated or filled with rubble or pure clay.
- Balled-and-burlapped (B&B) trees shall be placed in the hole and plumbed vertically. All rope shall be removed from around the trunk of the tree and the top 1/2 of the burlap shall be folded back down into the hole. Whenever possible, remove the top 1/2 of burlap by cutting it away with a sharp knife. Trees in wire baskets shall have the top 1/2 of the basket removed, using bolt cutters, to expose the top 12 inches of the ball.
- B&B packaging material shall not be removed until the tree is placed in the hole and securely plumbed into its final position. No false balls shall be used.
- Soil should be backfilled in lifts of 4 to 6 inches at a time with compaction of each layer. Do not compact saturated soil. Water thoroughly after backfilling to settle the soil, eliminate air pockets and re-wet the root system.
- Trees planted in sandy or loamy soils should have a 3-inch-high berm erected just past the perimeter of the planting hole to funnel water to the root ball and wet the hole or sidewall interface. Berms should not be constructed in clay soils or on heavily compacted sites.

- All trees shall be mulched with 3 to 4 inches of shredded mulch or composted brush chips immediately after backfilling. Maintain 3 to 4 inches of mulch annually.
- Mulch shall extend past the diameter of the tree planting pit at least 6 inches.
- Mulch shall be kept away from the tree trunk. Mulch shall taper from the 3-inch depth back to grade right at the trunk to avoid decay of bark tissues.
- Newly planted trees shall be watered weekly through the first three growing seasons.
- Trees shall receive approximately 1 inch of water per week including rainfall.
- Weeds should be suppressed within the mulch ring to eliminate competition and for aesthetics in formal parks and along streets.
- Weeds and/or turf shall not be allowed to grow up to the tree trunk at any time. This increases the likelihood of mechanical trunk injury.
- Ideal months for planting are October through April, as long as the ground is unfrozen.
- Stake only in situations where normal planting procedures do not provide a stable plant. Otherwise, staking is generally not required.
- Stakes and ties shall be removed at the end of the first year.
- Root flare shall be at or slightly above grade to allow for slight settling.
- Tree trunks shall not be wrapped.
- Tree trunk wrapping materials, tags and all ties shall be removed at time of planting.

Natural Area Planting

- All plant material shall be nursery grown under climate conditions similar to or hardier than at the site and meet or exceed The American Standards for Nursery Stock (ANSI Z60.1-1996).
- A 5-by-5-foot area should be free of competing vegetation for 3 years.
- Staking of newly planted trees is generally not necessary. If staking is necessary because of size or conditions, stakes shall be removed at the end of the first year.
- New trees shall be watered bi-weekly during summer drought stress periods for the first two to three establishment seasons.

Container/Bare Root Planting

- All plant material shall be nursery grown under climate conditions similar to or hardier than at the site and meet or exceed The American Standards

9 Trees & Natural Areas

for Nursery Stock (ANSI Z60.1-1996). Container plants shall have the container removed prior to placement in the planting pit.

- Tease pot-bound roots with hands or tools prior to final placement in planting pit.
- Bare root plants shall be protected from root drying prior to and immediately after planting.
- Cleanly prune exceptionally long roots to create a uniform root mass.
- Plant bare root stock at the same grade as grown in the nursery.

Tree Removal

Due to the economic, environmental and social benefits of trees, their removal must be well thought out and documented. In general, tree removal in the City of Bellevue is regulated by BCC 23.76. At times, trees may be removed for new park construction, access or other issues not related to tree viability.

Like any living plant, trees have a life cycle and eventually decline as they age. All trees are subject to diseases, physical damage, insect infestation and drought conditions. Any one of these factors, alone or in combination, can contribute to the decline of a healthy tree. Quick removal restricts the spread of disease and reduces the possibility of human injury or property damage. When a tree is either dead or visibly declining, City staff or a professional arborist will evaluate the tree to determine if removal is warranted or necessary. Not all declining or dead trees will be removed, particularly if the tree doesn't present a danger to the public or to property. Where appropriate, trees will be left as wildlife snags in natural areas and new trees should be planted as a replacement.

Occasionally, healthy trees, without any known or apparent defects, will be removed from park property. If a tree is blocking roadway site lines, disrupting underground utilities, interfering with overhead utilities, damaging hard surfaces or presenting a risk to the public, it may be considered for removal. If tree pruning can address the site line issues, pruning will be considered as a first option before removal. Some urban trees are problematic based on species. Cottonwood (*Populus trichocarpa*), red alder (*Alnus rubra*) and big leaf maple (*Acer macrophyllum*) are all prone to limb failure, short life span and disease. These tree species may be removed based on consideration of future growth characteristics and issues associated with their location.

Hazard Trees

- Tree hazard assessments shall be performed by qualified personnel to the standards established by the International Society of Arboriculture.
- Hazard trees that cannot be made safe or functional by appropriate mitigation shall be candidates for removal.

- Hazard rating shall be the first determining factor in removal decisions.

Tree Removal Permitting

A clearing and grading permit is required to remove one or more trees if the total canopy area covers 1,000 square feet or greater on the ground. In sensitive areas, such as steep slopes, riparian corridors or along shorelines, all tree removals must be permitted through the Developmental Services Department. In addition, all tree removals occurring in the public Right-of-Way must be accompanied by a Right-of-Way Use Permit, regardless of the amount of canopy area.

Thinning

As a normal practice, new trees are planted in forested areas relatively close to each other. In Western Washington, it is common for the forest in early successional stages to be overcrowded with dense stands of young trees competing for air, light and nutrients. As the surviving trees mature, selective thinning is required to improve air circulation, encourage understory light and to provide adequate space for the future growth of the remaining trees. An effort to diversify tree species is a priority and diversity is a consideration for selecting the trees that will be removed. Trees should be removed early enough to promote healthy conditions for the remaining trees.

Stump Removal

In developed park areas, stumps should be removed to make the area more aesthetically acceptable and to eliminate hazards. Stump removal involves the grinding out of all stumps to a depth of 12 to 24 inches below the surface, leveling the entire area and top dressing with soil. In natural areas, stumps are generally left in place to provide wildlife habitat except in situations where it is necessary to control the spread of disease, such as laminated root rot.

Adjacent Property Tree Issues

When the City of Bellevue becomes aware of a dangerous tree on private property, which could impact park infrastructure or public safety, a letter will be sent to the property owner notifying them of the City's concern and putting them on notice for future liability. When a property owner contacts the City regarding a potentially dangerous park tree, staff will investigate the request and follow up with a written response. Citizen requests for removal or pruning based on increasing light, safety, and building preservation will be addressed with the property owner on site to develop an action plan. The City will try to accommodate the property owner's requests whenever it's practical or reasonable. The City will not remove park trees due to: trees having pollen, cones, seedpods and needles; trees blocking views from adjacent property; or trees creating conditions that might be considered a nuisance.

9 Trees & Natural Areas

Tree Failure & Liability

If a tree located on private property falls onto park property, the City will clear debris and remove limbs up to the park property line. If a tree located on parks property falls onto private property, the City will only clear debris and remove limbs up to the park property line. Under no circumstances shall City staff enter privately owned property to remove, clear or prune trees or parts of trees regardless of origin. Any adjacent property that is damaged during a weather-related event by trees that were originally located on parks property shall be referred to the City's Risk Management Office.

Transplanting

If trees are smaller than 10 to 12 inches in diameter, it is possible to transplant them with an appropriately-sized tree-spade. The cost of transplanting should be weighed against the cost of replacing the tree with a new smaller caliper tree. Establishment of large trees is often less successful than planting a new one. The value of the tree to be transplanted should also be taken into account when deciding on removal or replacement rather than transplanting. Different methods of appraising value are reviewed in the most recent edition of *Guide for Tree Appraisal* produced by the Council of Tree and Landscape Appraisers.

Irrigation

In general, established trees do not require supplemental irrigation except during periods of extreme drought.

- Valuable, specimen trees may be irrigated during periods of extreme drought.
- Turf irrigation around established trees needs to be modified to accommodate the water requirements of the trees.
- Water spray on trunks can lead to decay in some species. See Chapter 4, Irrigation and Water Management, for additional information on irrigation practices.

Pruning

Pruning is sometimes necessary for young trees. Branches that grow into a pedestrian pathway can be dangerous. Generally, branches that grow below 7 feet above a pathway or below 14 feet above a parking lot or driveway entrance shall be cut back. Dead branches should be pruned to restore vigor to a tree. All pruning shall be performed to current ANSI Z133 standards.

Learning the proper method is important as you can seriously wound or even kill a tree. The best time to prune living branches is late in the dormant season or very

early in spring before leaves form. Dead and dying branches can be pruned anytime. Use clean sharp tools and make clean cuts. Do not:

- Leave living or dead stubs
- Injure or remove the branch collar
- Paint cuts

Topping and/or heading cuts shall be prohibited.

Forest and Natural Area Management

Natural Resource Enhancement Plans

A Natural Resource Enhancement Plan is based on an analysis of the ecosystem and the interrelationships of the different components of natural systems, as well as the human impact on their functions. Natural Resource Enhancement Plans are created based on information gathered about the site both in the field and through available background data. This information is then utilized to reflect the goals of the community and the City of Bellevue. Identified within an Enhancement Plan are the overall intentions for the property.

A Natural Resource Enhancement Plan for a specific site contains the following elements, with maps to illustrate where possible:

- Property description and site history
- Sensitive area classifications
- Soils and topography
- Existing vegetation
- Liability trees and situations
- Wildlife
- Recreation
- Management prescriptions

Boundary Surveys and Staking

- Upon purchase/transfer of a new property to the City or when a property has not previously been surveyed, a boundary line survey should be conducted so both the City of Bellevue and the adjacent property owners are aware of the location of the property lines.
- Boundary surveys shall be conducted by a professional survey firm or City of Bellevue survey staff.
- Following a boundary survey or property inspection, City boundary stakes shall be installed at all corners and along lines to aid in the future identification of the legally surveyed property lines. When the stakes are

9 Trees & Natural Areas

installed, care should be taken to ensure that the stakes are placed accurately on the property line and installed securely.

Site Inventory

The first task in managing our resources following acquisition and liability mitigation is a thorough inventory of the resource itself. The resources needed to accomplish the site inventory include:

- Deeds and purchase documents
- City and county plat maps
- Registered surveys
- Topographic maps
- Aerial photos

Start with an inventory of the ownership. Locate the original closing papers, recorded easements, deeds of trust or any conveyance documents that describe the property. The goal is to discover the boundaries, legal histories and easement restrictions on the land to be managed. If files on the site are incomplete, the County Property or Records Department may prove helpful. Be sure to provide any parcel numbers, legal descriptions, plat names and even street addresses to assist in the research.

The next step in a site inventory is to collect site-specific information. Site-specific inventory information will help direct the implementation of operational activities necessary in maximizing open space objectives. The site-specific inventory information shall include:

- Site history
- Boundary delineation
- Site liabilities
- Vegetation habitat type and successional stage
- Soils, aspect, topography
- Fish and wildlife habitat
- Recreation opportunities
- Sensitive areas

All of the site inventory information should be documented and stored for future reference and the development of Natural Resource Enhancement plans.

Routine Site Inspections

All forest and natural areas shall be inspected on an annual basis. There are, however, two levels of inspection detail that the inspector may use, first and second-priority inspections.

The most detailed and comprehensive inspection is referred to as a first-priority inspection. First-priority inspections are conducted on sites scheduled to receive enhancements for the year or sites that are politically or environmentally sensitive.

As the names imply, first-priority inspections occur ahead of second-priority inspections. This is because first-priority inspections are meant to identify forest management areas of concerns and enhancement tasks, verify the existence of all boundary markers, discover any trespass issues (encroachments, dumping, or illegal tree cutting) and monitor the progress of past enhancement projects. A second-priority inspection, although not as time consuming, is still comprehensive and well documented. Second-priority inspections cover the balance of open space properties and consist of a general site reconnaissance. Second-priority inspections are focused on the discovery of potential liability situations.

While conducting a site inspection, it is important to respect the adjacent property owners' rights and concerns. The inspector is a representative of the City of Bellevue and should be polite, courteous and professional at all times.

Inspection Procedure

Pre-inspection planning needs to be done to ensure a safe, productive and successful inspection. Spending a few minutes planning and discussing the inspection will help eliminate wasting time over something forgotten.

- Before leaving the office, get a picture of the site characteristics and location.
- Determine whether you need to be carrying out a first or second-priority inspection and get answers to any questions you might have.
- Let someone in the office know your work plans and location, preferably your supervisor.

Property inspections can be a slow and demanding process. Thick vegetation, steep slopes, unmarked property lines and bad weather all conspire to make the going challenging.

- Use aerial photos to identify your location by looking for identifiable structures or rooflines.
- Walk the property line and document all property markers and hazardous trees.
- Look for and document with pictures any encroachments, dumping, vegetation removal and tree cutting. Identify the location on the map.
- If homeless camps or other illegal activities are discovered, notify the proper authorities for removal.

9 Trees & Natural Areas

If there are trails on the property, walk the trails and record their general level of upkeep. This brief walkthrough can help the trails crew address maintenance issues.

Record all of the data that was collected. Insert the inspection forms in the site book and report any issues to the supervisor. Clean and store all tools.

Liability Tree Monitoring

Once a tree is designated as a liability tree it shall become the burden of the staff at hand. Although it may be easier and less complicated to simply remove all liabilities, the conservation of trees is something that must be considered until the tree can either be replaced or the tree becomes too great of a liability and must be removed.

Trespass Enforcement

Trespass enforcement consists of remedying any of the following actions on park property: clearing of vegetation, including the topping of trees; dumping of debris; and encroachment by construction or developed structures. In 1993, the Parks & Community Services Department developed a Parks Department Encroachment Policy in response to numerous encroachment issues. In the years that followed, the Parks Department clearly identified many of its property boundaries by installing boundary markers. Inasmuch as the installation of these markers greatly reduces the number of trespass situations that arise, they still occur on a regular basis.

The Parks Department Encroachment Policy, although developed specifically for encroachment issues, can be applied to all trespass situations. The three steps the policy outlines for the enforcement of encroachment issues are as follows:

1. Voluntary Removal of Encroachment. This would primarily be facilitated by Parks' staff working directly with the property owner to find a mutually agreeable restoration plan and the implementation of such a plan. The interaction with the property owner is usually a mixture of both on site visits and formal letters.
2. Boundary Line Adjustment. This option will only be considered a possibility in a situation where the property owner is able to "exchange" land of equal size, value and condition for the land that is encroached. All costs associated with a Boundary Line Adjustment would be borne by the property owner. For clearing or dumping situations, this option would not be considered. City Council has final approval of all Boundary Line Adjustment decisions. In general, boundary line adjustments are only pursued if there is a clear public benefit to be gained.
3. Legal Action. This option is necessary in the rare case where the property owner refuses to accept the trespass as true or refuses to remedy the situation

voluntarily. The City Manager's approval is required for use of Legal Action for enforcement of a trespass.

Natural Resource Enhancement Implementation

This task should be utilized for all activities related to the implementation of a Natural Resource Enhancement Plan. This includes but is not limited to the following:

- Debris removal & cleanup
- Hazard tree removal
- Preparation and planting of enhancement sites with native plant species
- Silvicultural prescriptions
- Trail construction or upgrades

Silvicultural Prescriptions

Silvicultural prescriptions are also known as forest management practices. These shall be implemented in accordance with the City of Bellevue's land use policies for open space. Sound forest management practices support park functions by maintaining and enhancing a biologically diverse community consisting of a mixture of age classes and plant species, as well as wildlife habitat and recreational opportunities.

The management goals for most parks are as follows:

- Public safety
- Improve forest health
- Protect water quality
- Land-use and/or visual buffering
- Recreational opportunities

Sensitive/Critical Area Management

Sensitive or critical areas are defined as those areas that can be adversely affected by any non-natural process, causing degradation to that area, or its biological processes. The City of Bellevue Land Use Code and The Sensitive Areas Notebook define critical areas as:

- Areas of special flood hazard
- Riparian corridors, excluding Type C and D
- Wetlands, excluding Type C
- Areas of colluvial or landslide deposits on slopes of 15% or more
- Slopes of 40% or more
- Areas potentially affected by abandoned coal mines
- Shorelines and aquatic habitats

Bellevue Parks & Community Services Department recognizes the special importance of these areas, as well as others not defined by the Land Use Code, that fall under its

9 Trees & Natural Areas

stewardship. These sensitive habitats, their plant and animal communities, have a direct link with other habitats and waterways, affecting entire ecosystems. The goal is to preserve these areas to the fullest possible extent, for the preservation of these species and for the good of the community.

There are many regulations regarding working in these areas, and therefore, many special permits are required by either the City or the State. For further information, contact the Developmental Services Department or refer to the COB Land Use Code.

Water Quality Monitoring

Water quality is another important aspect for maintaining a healthy park system and urban environment. In Bellevue, many departments and outside agencies work together and communicate with Parks to ensure that monitoring and regulation of water quality and surrounding habitat persists. These include Bellevue's Developmental Services Department, Utilities Departments and the Washington State Department of Fish and Wildlife.

Riparian Corridors

Riparian corridors are sensitive areas that include an interactive vegetation community integrated with the water course ecosystem which provides food, shelter, breeding and rearing areas for aquatic and terrestrial animals and birds. They encompass the area that runs along both side of the water body, ranging from 10 - 50 feet wide, depending on the sensitivity classification. Included are wetlands and meadows.

- Improper clearing can have serious effects on the ecosystem, allowing for increased runoff, toxin accumulation, oxygen reduction to surrounding plants and water systems, and overall habitat destruction.
- Native vegetation is usually preserved or planted in order to mitigate any negative effects.
- If corridor is located within a Native Growth Protection Area (NGPA), it must be registered with the City.

Shoreline and Bank Stability

Reinforcing or protecting a shoreline should consider the least impact necessary to achieve reasonable stability. These practices include, but are not limited to:

- Traditional use of riprap should be used only as a last resort. Softer treatments, such as log placement and bioengineering plantings, are preferred where feasible.
- Treatments should consider seasonal differences, such as the Chittendon Locks operations, and regular seasonal water level changes.

Steep Slopes

Steep slopes are defined as any slope over 40% and are considered sensitive or critical areas. An exception are areas of colluvial or landslide deposits, in which case the minimum slope is 15% or greater. The surface slope, soil layers and ground water layers all can impact how stable a slope is. To minimize impacts to a slope and the surrounding area:

- Removing vegetation from the ground layer should be minimized and plantings should be stabilized with appropriate bioengineering techniques (e.g. netting, wattling, hydro-mulching, etc.).
- Revegetation should be evaluated so as not to cause more damage or disturbance to soil layers.
- Slide areas, or areas suspected of being slide-prone, should be evaluated by a geotechnical expert before extensive restoration begins.
- Storm-water runoff must be prevented from saturating or loading steep slopes. The appropriate drainage system should be in place and adequately maintained to intercept runoff flows before reaching the slope.

Slide Areas

Slide areas, or those suspected of being slide-prone, shall be evaluated by a geotechnical expert before extensive restoration is initiated. Strategies can be developed to help maintain or even improve slope stability. The standard practice of hydro-seeding repaired slide areas is prudent but does not restore stability. To restore stability and prevent further soil erosion, subsurface hydrology must be considered and woody vegetation re-established.

Wetlands

Wetlands are those sensitive areas that are a transition between terrestrial and aquatic systems where the water table is usually at or near the surface, or the land is covered by shallow water.

The plants that inhabit a wetland are hydrophytic, and adapted to living in hydric soils, sometimes under water. Wetlands serve an important function in that they act as a natural reservoir for storm runoff, offer flood control, recharge ground waters and filter off toxins that would otherwise find their way into the water table. They also provide necessary habitat for various wildlife species unique to any other habitat type.

Most wetlands found within the Bellevue Parks system are treated as sensitive areas and managed with the goal of maintaining the natural environment with the least amount of impact.

- Only invasive and noxious weeds are controlled through mechanical or cultural methods.

9 Trees & Natural Areas

- Approved wetland herbicides are used only when necessary and never near standing water. Such applications are made under an approved Aquatic Noxious Weed Control NPDES General Permit.
- Only native species are planted within a wetland area, unless the wetland is part of one of the agricultural areas that are preserved within the parks system.
- Trails are kept to a minimum and specially designed to decrease habitat disturbance.

Meadows

Meadows serve an important role in natural and sensitive areas. They provide necessary wildlife habitat, reduce flooding potentials downstream or in low lying areas and act as a natural filter as water passes through supplying needed nutrients to the area. The Bellevue Parks & Community Services Department has adopted many restorative and maintenance practices regarding meadows and wetland areas. They include grassland vegetative cover, meadow preservation, meadow restoration, habitat preservation and fire prevention.

Grassland Vegetative Cover

Healthy vegetative cover is important for erosion control, habitat and noxious weed control.

Exotic Grasses

Most urban meadow sites are previously disturbed sites resulting in regrowth of primarily exotic grasses. Once established, these exotic species should be accepted as the primary component of the vegetative cover.

Native Meadow Plants

Preservation of native plants should be attempted whenever possible.

Wet Meadows

Many meadow areas in this region remain in a saturated condition for 6 months or more. Avoiding significant maintenance activities during this period is recommended. Preservation and introduction of appropriate native plants into these sites will help ensure a healthy vegetative cover.

To preserve a grassland, wet meadow or perennial meadow in the Pacific Northwest requires an ongoing maintenance program.

- Disturbance: Avoid creating holes in the vegetative cover because it will open opportunities for noxious weeds to invade.
- Meadow Succession: The natural evolutionary process of forest/meadow succession will eventually colonize meadow areas with shrubs and trees. The management of this process will have a major impact on the character

and longevity of the meadow. The desired character of a meadow area should be defined. The meadow should be managed to prevent establishment of exotic trees and shrubs. Depending on the desired character of the meadow, all, some or none of the native plants attempting to colonize the site can be retained.

- **Exotic Weed and Brush Control:** Scotch broom and other noxious weeds colonize many meadow areas, especially if the vegetative cover is weak or not intact. If invasive brush is a minor problem, hand grubbing, use of weed wrenches or spot spraying with a broadleaf herbicide are options. When invasive brush is a major problem, it may be necessary to mow the meadow on an annual basis. Mowing should be timed to avoid disturbing wildlife. Spring should be avoided to allow protection for ground nesting birds. The site should be monitored for other wildlife activity before mowing occurs. Mowing should also be done before seed set of the targeted species. Mowing heights should be a minimum of 6 inches high to prevent excessive grass clippings and to minimize exposing bare ground.

Restoration and Construction of Meadows

The restoration or new construction of a meadow should consider the following:

- **Hydrologic Study of the Site.** Available moisture is the determining factor in appropriate plant selection.
- **Soil Study.** Many native plants require specific soil requirements to succeed.
- **Existing Vegetation.** The site should be assessed for desirable species as well as undesirable species. A small test plot can also help determine the potential weed seed bank in the soil profile. A thorough inventory of existing species can provide valuable information for selection of appropriate species.
- **Natural Succession.** Whenever possible, attempt to emulate the natural succession process by initially introducing primarily pioneering plant species and gradually expanding into later successional species as cultural conditions allow.
- **Wildlife Habitat.** The management practices of meadow areas should reflect the goal of preserving and enhancing desirable wildlife species.
- **Maintenance Activities.** Maintenance activities should be evaluated as to their impact on wildlife and appropriate decisions made.

9 Trees & Natural Areas

- Enhancements. Many desirable species can be attracted by enhancements such as nesting boxes, brush piles, rock piles, stumps, snags and specific plants.
- Environmental Education/Interpretation. When resources are available, it is important to address environmental education. Educated park users are much more likely to preserve and protect a site.

Organic Debris

Organic debris from maintenance practices will remain on site, as long as it does not interfere with other landscape functions and/or create a fire hazard. Types of interference include blocking trails, forming unstable cornices, diverting drainages and smothering desirable vegetation. Wherever possible, use the following practices:

- Organic debris should be cut and dispersed to maximize ground contact.
- Chipping woody debris is useful as long as debris is left in a depth of 3-inches or less.
- Leave uncut branches and logs in place to restrict traffic into natural areas.
- Stabilize logs to prevent sliding or rolling.
- Remove invasive species from the site.

Fire Prevention

A healthy, diverse plant community is fire resistant, but woody plant debris must be managed in any urban landscape. The following practices encourage fire prevention in natural and sensitive areas:

- Excessive accumulations of dead, woody plant debris should be avoided. Thinly scatter this debris away from park use areas.
- If tree pruning or removal debris remains in a native woodland site, the material should be cut, slashed and scattered well enough to directly contact the ground.
- Maintain transitions to developed landscapes to provide interruptions to the normal path that fire usually travel. This practice creates a more defensible landscape.
- Hydrants should be located along the edge of natural areas to provide immediate access for firefighting.
- Service roads into large woodland tracts should be maintained to allow access to Fire Department tanker trucks.
- Large woodland tracts with high fire potential should be studied for possible development of service roads.
- Areas of known homeless encampments should be frequently inspected and cleaned up to minimize the potential for wildfires.

9.4 Training

- Provide training to all construction personnel to make sure they understand all construction site BMPs, including streambed and bank protection, steep slopes and wetland protection.
- The site manager and other designated site managers shall receive the most recent training and education dealing with construction site management. This training includes the most recent advances for protecting trees on construction sites.
- Urban Forestry and site managers should receive training in appraising and evaluating tree and plant damage according to International Society for Arboriculture standards and natural area preservation techniques.
- Foresters and tree workers will be ISA certified.
- All contracted or volunteer planting crews shall be trained in proper planting techniques by the site manager.



9 Trees & Natural Areas

(This page intentionally left blank for note taking)



CHAPTER 10 – Trail System Management



10.1 Purpose

Trails play an integral role within the park and open space system. Trails are the most widely used recreational facility managed by the Parks & Community Services Department. They are used and supported by nearly 90% of Bellevue citizens. Trails provide non-motorized and recreational opportunities for walkers, bicyclists, joggers, hikers and birdwatchers. They are the string that physically connects parklands, neighborhoods, schools and businesses. Trails also provide staff access for maintenance and management of the parks and open space system. Bellevue's trails are designed and constructed in an environmentally sensitive manner to reduce soil compaction, erosion and runoff to protect sensitive areas from degradation.

10.2 Background

Bellevue's trail program oversees trail planning and development, project management, development mitigation, workload planning and maintenance of over 93 miles of pedestrian, equestrian and multi-purpose trails located on park property and public easements. Attention to trail planning and design has resulted in a system of pathways which provides a spectrum of opportunities for different users.

10 Trail System Management

Bellevue's trail system provides a physical link for citizens to value and appreciate the natural attributes of our open space and greenway system. Trails are constructed in a manner that minimizes the impact of human traffic in park natural areas and protects sensitive wildlife habitat while at the same time enhancing the visitor experience. Human contact with nature fosters citizen support for the overall goals and objectives of the City's park and open space plan and the natural resource management program.

Trail Design and Construction

Trail construction is guided by park development standards that consider drainage, slope, width, clearing limits, surface material and habitat value. The use of geotextiles on trail surfaces and water diversion BMPs provides effective drainage, soil stabilization and weed control. Stair and boardwalk construction provides access through narrow corridors, over wet ground and on steep slopes with less impact than traditional trail structures. The following considerations are reviewed based on site conditions and constraints.

Design Elements in Wetlands

Design and implementation of trails in a wetland environment requires consideration of certain risks associated with this type of sensitive area, such as:

- Water-quality impacts
- Sedimentation
- Introduction of toxins
- Increase in nutrient load
- Changes in pH, salinity and oxygen balance
- Increases in suspended and dissolved solids and turbidity
- Impediment of movement of storm waters (including soil compaction)
- Habitat impacts
- Fish and wildlife disturbances
- Aesthetic impacts
- Illicit access off developed trails (social trails)

In order to minimize impacts from trails in a wetland:

- When possible, higher ground shall be chosen for trail location.
- Stream crossings shall be at a minimal, but if necessary, shall be done at 90 degree angles.
- Culverts or bridges, if necessary, shall be used in such a way that the existing drainage will not be altered and passage for fish will not be affected.
- Culvert size is based upon maximum stream flow and site conditions.

- Streambanks and other sensitive areas will be minimally impacted, if at all.
- Geotextile fabric may be used in construction to increase the bearing strength of the trail, minimize fill requirements, disturbance and maintenance costs.
- Trail grades should range from 0 to 6% with a 3% or less side slope to ensure adequate drainage, minimize surface-water velocities and discourage rutting and erosion. Based on site conditions and site constraints, trails may be constructed with grades ranging from 15% to 20%. Steeper grades may require stairs to avoid erosion and other site impacts.

Design Elements in Upland Park Sites

Consideration shall be given regarding impact on neighboring properties, drainage, slope, width, clearing limits and surface materials for each individual park.

- If narrow corridors are present, stairs shall be considered.
- Steep slopes and wet areas shall be avoided, if possible, for trail development. If necessary, stairs and/or cantilevered boardwalks shall be utilized to decrease surface impact.
- Trail width shall be a minimum of 4 feet. Steeper upland sites may only allow for 3 feet due to topography constraints.
- Trails should follow slope contours to decrease disturbance as much as possible.
- Trail slope shall be based on site conditions and decided upon by the site manager.
- Trail grades should range from 0 to 6% with a 3% or less side slope to ensure adequate drainage, minimize surface-water velocities and discourage rutting and erosion. Based on site conditions and site constraints, trails may be constructed with grades ranging from 15% to 20%. Steeper grades may require stairs to avoid erosion and other site impacts.

10.3 Best Management Practices

Bark Trails

- Prior to surfacing, trail shall be manually grubbed out taking care not to disturb surrounding vegetation. Native plant species that occur within the proposed trail alignment will be transplanted on site as part of the trail construction process. Trail surface retaining poles may be used in areas

10 Trail System Management

- that are prone to sloughing and erosion, usually on the outsides of corners and in areas of grade change.
- Woody debris removed from the trail grade will be randomly scattered on site and will be left in ground contact oriented across slope. On sites with a high volume of debris during construction, mobile on site chipping will be implemented and resulting chips will be used as an underlayment trail surfacing material.
 - All trail work will be conducted within trail alignment to minimize side of trail disturbance and degradation.
 - Surface drainage techniques shall be utilized, such as:
 - Crowning
 - In-sloping and out-sloping at 3% or less grade
 - Culvert installation
 - Slope exposed gutters
 - Turn pike/ French drain systems
 - Trails shall maintain a 2 foot minimum horizontal clearance to any obstruction.
 - Trails shall maintain a 7 foot minimum vertical clearance from trail surface, across the horizontal clearance width.
 - Side-slope shall be graded no greater than a 3:1 slope and covered with Jute fabric and stapled. Grading shall be done so that accumulation of runoff does not collect at bottom of slope. A 2 foot wide transition edge is required prior to start of side-slope. Where required, toe of slope exposed gutters are used to route trail water runoff to culverts.
 - Geotextile fabric shall be laid between sub-grade and base course prior to surfacing, where needed. This is applicable to wetland sites and sites that have a soft base.
 - Sub-grade shall consist of undisturbed native soil. Sub-grade shall never be compacted.
 - Surface shall be grubbed to level trail grade to 3% or less to ensure trail drainage.
 - Trail surfacing shall consist of medium fine bark applied to a depth of 4 inches and raked out smoothly. If necessary, area adjacent to trail shall be revegetated or properly landscaped with native shrub/tree/groundcover species.
 - Trailheads will have developed signage, and if necessary, post and rail fencing along with a native shrub/tree palette (see associated standard details and/or specifications).

Crushed Rock/Gravel Trails

- Prior to surfacing, trail shall be manually grubbed out taking care not to disturb surrounding vegetation. Native plant species that occur within the proposed trail alignment will be transplanted on site as part of the trail construction process. Trail surface retaining poles may be used in areas that are prone to sloughing and erosion, usually on the outsides of corners and in areas of grade change.
- Woody debris removed from the trail grade will be randomly scattered on site and will be left in ground contact oriented across slope. On sites with a high volume of debris during construction, mobile on site chipping will be implemented and resulting chips will be used as an underlayment trail surfacing material.
- All trail work will be conducted within trail alignment to minimize side of trail disturbance and degradation
- Surface drainage techniques shall be utilized, such as:
 - Crowning
 - In-sloping and out-sloping at a 2% grade
 - Culvert installation
 - Slope exposed gutters
 - Turn pike/ French drain systems
- Trails shall maintain a 2 foot minimum horizontal clearance to any obstruction.
- Trails shall maintain a 7 foot minimum vertical clearance from trail surface, across the horizontal clearance width.
- Side-slope shall be graded to a 3:1 slope when possible. Grading shall be done so that accumulation of run-off does not collect at bottom of slope.
- Geotextile fabric is not usually used in park rock/gravel trails.
- Sub-grade shall be 5/8 inch crushed rock, compacted to 95% density. Disturbed native soil subgrade should be compacted to 95% density.
- Surfacing base shall be 4 inches of 5/8 minus crushed rock. Trail surface shall be 2 inches of compacted 3/8 minus crushed rock.
- If necessary, area adjacent to trail shall be revegetated or properly landscaped with native tree/shrub/groundcover species.
- Trailheads will have developed signage, and if necessary, post and rail fencing along with a native shrub/tree palette (see associated standard details and/or specifications).

10 Trail System Management

Asphalt Trails

- Prior to surfacing, trail shall be grubbed out by mechanical or manual means. Any areas adjacent to trail where vegetation was removed or damaged shall be replanted with native species.
- All hazard tree and tree limbs shall be removed from trail site.
- Subgrade shall consist of undisturbed native soil. If soil is disturbed, soil shall be compacted to 95% density.
- Geotextile fabric shall be laid between sub-grade and base course.
- Root barrier, if necessary, shall be installed prior to installation of asphalt. Root pruning, when necessary, shall be done by a certified arborist.
- Side-slope shall be graded to a 3:1 slope, when possible. Bottom of side-slope shall be graded to prevent accumulation of run-off.
- Trail surface slope shall be a maximum of 3%. Edges shall be thickened to 6 inches deep by 10 inches wide for erosion protection.
- Trees shall be maintained for a 7 foot vertical clearance from trail surface, across the horizontal clearance width. Equestrian trails shall be maintained for a vertical clearance of 10 feet.
- Asphalt top course shall be class "B" asphalt with a minimum thickness of 2.5 inches, and a maximum thickness of 4 inches.
- Base course shall be 5/8 inch minus crushed rock, compacted to 95% density, and a minimum thickness of 4 inches.
- Trail width shall be between 4-14 feet, depending on site conditions and designed functionality. Wider trails are not usually installed in Bellevue parks, but consideration will be made if necessary.
- If necessary, area adjacent to trail shall be revegetated with native tree/shrub/groundcover species. If trail crosses a turf area, disturbed turf shall be replaced.
- Trailheads will have developed signage, and if necessary, post and rail fencing along with a native shrub/tree palette (see associated standard details and/or specifications).

Stairs, Boardwalks & Retention Peeler Poles

- All trail structures will be constructed to Parks & Community Services standards and specifications.
- All treated wood materials used for construction shall not leach hazardous materials, and will be dark tinted ACQ/CBA pressure treated.
- All rough sawn and dimensional wood shall be of HEM-FIR #2 grade or better. All wood used for railings will be appearance grade non-insided.
- Boardwalk footings and stairs shall be placed on stable subgrade.

- Landings shall be composed of fill consisting of 3/8" minus crushed rock, compacted by hand. Railings will be used if edge is 30 inches or greater from grade, or is deemed necessary. Railings shall be installed on the right hand side heading upstairs.
- Trail retention peeler poles and stakes shall be lodge pole pine with ACQ/CBA treatment.

10.4 Training

All maintenance crew members are trained in proper trail planning, design, construction and maintenance. Crew members and staff are also trained certified arborists and pesticide applicators.



10 Trail System Management

(This page intentionally left blank for note taking)



CHAPTER 11 – Agricultural Areas



11.1 Purpose

The City of Bellevue Parks and Community Services Department manages the last remaining farm lands within the city. These lands are comprised of approximately 42 acres and are located in the rich peat soils of the Lake Hills Greenbelt and Mercer Slough Nature Park. These farmlands were established in the late 19th and early 20th centuries after clearing and draining opened the land for agriculture. Today these historic agricultural lands help preserve Bellevue’s agricultural past, provide community gathering spaces and increase wildlife habitat. The continued management of these agricultural lands is identified as a component of the master plans for each park. They are managed as farmed wetlands in an environmentally sensitive manner under the same set of multiple use goals consistent with other open spaces land to maximize public benefits.

11.2 Background

All remaining agricultural lands within the City are located within the Lake Hills Greenbelt and Mercer Slough Nature Park. Agriculture in the Lake Hills Greenbelt was established in the late 19th century when early pioneers drained the land between Larsen and Phantom lakes by diverting natural flows into Lake Sammamish.

11 Agricultural Areas

Agriculture in the Mercer Slough Farm was established shortly after the creation of the Chittenden locks lowered the level of Lake Washington 9-12 feet in 1917. The blueberry farms were established in the 1940's. Current City managed farms include the following:

- Larsen Lake Blueberry Farm (14 acres)
- Lake Hills Greenbelt truck farms (10 acres)
- Mercer Slough Blueberry Farm (18 acres)

Existing Site/Environmental Conditions

Current Landscape and Field Condition

All agricultural fields are located in wetlands associated with the Kelsey Creek drainage that have been converted to agriculture during the late 19th and early 20th centuries. The condition of current plant material may be a good indicator of existing cultural conditions. Master plans, soils types, moisture regimes, nutrient levels and types of pest populations determine farm renovation and plant selection options. Because of the wet soil condition and low air circulation associated with these sites, special attention must be given to cultural practices to help reduce root-rotting fungus such as *Phytophthora* and berry-infecting fungus such as *Monilina vaccinii-corymbosi* (Mummy berry).

Soil Type and Condition

Soil type can ultimately determine the longevity, mortality and health of the crop plants. The soils that make up both farms are predominately peats and/or mucks. Although blueberries like wet and acidic soil conditions, excessive water may cause root rot problems and must be carefully monitored and controlled through drainage.

Drainage

Because of the subsurface irrigation that exists at both sites, irrigation is typically not necessary. Drainage, however, is essential in helping to prevent disease and allowing access to the fields for maintenance activities. The maintenance of existing ditches and cross tiles is essential to help maximize yields and reduce disease.

Cultural Conditions

Cultural conditions such as existing plant health, soil, moisture, sunlight, wind, rainfall, pests and disease all have an important role in plant health. Environmentally sensitive cultural practices such as mowing, weeding, pruning, mulching, pollination and drainage are used to increase plant vigor.

Safety

Safety of citizens and farm workers is paramount in farm operations. Designation of U-pick areas, adequate signage, plantation design, plant maintenance, proper materials storage, harvesting coordination and elimination of undesirable pest populations all help to create a safe environment.

Cultivar Selection/Diversity

Species diversity offers a longer harvesting season and cross-pollination. Monocultures can be more susceptible to total failure in case of insect or disease problems.

11.3 Best Management Practices

The farms are components of Master Plans for both the Lake Hills Greenbelt and Mercer Slough Nature Park. BMP's for farm operations take into account the multiple use aspects of the parks and utilize environmentally sensitive cultural practices to help maximize public benefit and protect the environment. The uses of pesticides on the farms are extremely limited and, although not certified, the farms are operated using predominately organic farming techniques.

Major horticulture decisions regarding blueberry farms include nutrition, water management, pruning, pollination, harvesting and weed and pest management. Many cultural operations are timed to the annual growth cycle of the plants, which varies from year to year with climate and soil conditions. Table 11.1 shows a typical blueberry yearly calendar planning guide. It should be noted, however, the use of pesticides will be only considered as a last alternative.

11 Agricultural Areas

Table 11.1 Annual planning guide for blueberry fields

Growth Period	Approximate Dates	Cultural Operations
Dormant	Nov.—mid March	Prune, apply dormant spray for scale growth if necessary, apply copper for bacteria canker if necessary, and remove diseased and winter-injured tissue.
Leaf and flower bud break	Late March—late April	Apply fungicide for primarily mummy-berry if needed, control weeds and apply copper if needed.
Bloom Period	Late April—late May	Apply fungicides for mummy-berry if needed, apply insecticides to control aphids if needed, introduce bees for pollination.
Fruit Development	June and July	Cultivate or spray for weed control in row middles, install bird damage control devices.
Harvest	July—Sept.	Harvest and market fruit.
Post-harvest Growth	Sept.—mid October	Cultivate to control weeds, remove bird damage control devices.

Water Management

Blueberry plants have most of their effective root system in the upper 18 inches of soil. Normally, this would subject the plants to drought injury in the hot summer months when water availability decreases, however, the Lake Hills Greenbelt and Mercer Slough farms are located within wetlands comprised of hydric, peat soils which essentially eliminates the need for irrigation. The need for adequate drainage, however, becomes increasingly important for maintaining plant vigor.

Water management at the Mercer Slough farm faces additional drainage issues. Mercer Slough is an adjacent wetland to Lake Washington and the water level is artificially controlled by the Army Corps of Engineers through the operation of the Chittenden Locks in Seattle. The water level manipulation by the Corps creates a reverse hydrological effect in the wetland, keeping the level artificially higher in the summer months. This artificial hydrologic environment further exacerbates drainage issues that contribute to root rot and mummy-berry.

To assist with drainage, the slough was dredged in the early 20th century and an earthen dike running parallel to the channel was constructed. Individual blocks of berries are separated by dammed drainage ditches that flow east into the channel. Cross tiles running perpendicular to the drainage ditches pull ground water from the fields into the ditches. Water is pumped out of the ditches into the Mercer Slough channel via 2 Marlow (#MWS1512D4), 1 PH, 230 volt trash pumps. These pumps have a pumping capacity of approximately 360 gallons/min through 4" PVC pipes. These pumps utilize float valves triggered by rising water levels to control water levels. They also have the ability to grind up small woody debris to prevent clogging. Proper water management helps ensure fruit production, good floral initiation for the next year's crop and that fruit skin moisture is maintained to prevent cracking or shriveling.

Pruning

Annual pruning is essential to maintain blueberry plant vigor, increase productivity, aid in pest management, maintain fruit quality and develop appropriate growth habits. Annual moderate pruning produces bushes with the fewest canes, but greatest yields. Proper pruning balances the production of new wood while maintaining fruit production. Although the best time to prune is during late winter dormancy as carbohydrates produced in late fall have had sufficient time to be stored and winter injured wood can be easily removed, blueberries can be pruned anytime between the end of fall harvest and spring bud break. Disinfect loppers and pruners between bushes to help prevent the spread of disease.

Pruning Technique

Pruning with newly established plantings (1-2 years old) will primarily be directed at shaping the plant into an upright habit and encouraging new vegetative growth and vigor. Remove the older, twiggy growth from the base of the plants, strip blossoms off to accelerate plant and root growth.

In subsequent years (2-5), prune lightly to remove injured wood and twisted or low growing canes to promote new growth. Remove all but 2-3 newly produced canes at crown level. At 7 years old, plants should have 10 – 20 canes of different ages.

Pruning mature plants consists of cutting out old, larger, low producing canes and eliminating weak, twiggy growth in the top or outer areas of the bushes to facilitate aeration and encourage increased budding and large berries. In very mature neglected plantings, it may be beneficial to simply crown prune the entire plant at the base and start from scratch. The following represents a systematic approach to pruning:

11 Agricultural Areas

- In older plantings, remove 20% of older wood to stimulate new shoot growth.
- Remove low growth that would touch the ground when loaded with fruit.
- Cut off excess new growth that you don't want to develop.
- Remove any damaged canes and twigs.
- Cut out weak, twiggy growth from the top and outer parts of the plant to allow for light penetration and aeration through the plant.
- Prune to shape plant for appropriate harvest method (machine vs. hand picking).

Pollination

Although blueberry bushes are capable of setting fruit on 100% of their flowers, 80% is considered a full crop. The conservation of wild bee habitat such as fallen logs, ditch banks and natural areas close to the field enhances wild bee populations. Honeybee pollination, however, is essential for sustainable yields. The following standards ensure a high probability that proper pollination will occur:

- Make sure the crop is an attractive crop. This entails making sure that pruning cultivates plants with high bud counts, and the chosen cultivar has desirable corollas (shorter corollas have proven to be more attractive to honeybees than longer corollas).
- Ensure that there are at least 4-8 bees/plant at any time during the warmest part of the day during bloom.
- Hives must be in place when a minimum of 5% and a maximum of 25% of the flowers have opened.
- Hives must be placed in a wind-sheltered sunny location and preferably facing East.
- Proper pollination requires a minimum 1-3 hives/2 acres, depending on cultivar.
- Hives should be distributed evenly throughout the field: 300ft. apart along every 10th row.
- Remove all competition from plant areas (e.g. dandelions, clover, etc.)
- Additional efforts to encourage native mason bee population are also utilized.

Harvesting

U-pick and hand harvesting are done in both blueberry fields. Clearly designate blocks, varieties and U-pick areas for the public.

Diseases

- Disease problems shall be accurately identified and management strategies shall be tailored to actual diseases present in the field in current season.
- Disease resistant cultivars shall be used when planting new sites.
- Mummy-berry incidence and severity shall be documented and mapped (noting varietal differences) by determining number of strikes/bush for primary infection and percent infected fruit for secondary infections.
- One or more of the following strategies shall be used to suppress primary infection of mummy-berry (where needed):
 1. Apply a thick layer (3-4") of organic mulch beneath bushes to cover fallen fruit in mid-spring.
 2. Rake, disk or cultivate soil beneath bushes in spring prior to budbreak to disrupt mummy-berry spores.
 3. Apply 200 lbs/acre 50% urea pills beneath plants in spring prior to budbreak to 'burn' mummy-berry spores. Despite a strong offensive, Lime sulphur may also be effective at burning spores.
- Diseased wood shall be pruned and destroyed. Pruning tools shall be cleaned in a bleach solution between cuts.

Insects

- Insect problems shall be accurately identified and management strategies tailored to actual insect pests present in the field in current season.
- Insects that vector viral and MLO diseases (e.g. aphids and leafhoppers) shall be controlled, if necessary.
- Other insect pests (e.g. leaf rollers, gypsy moth, sawfly, Japanese beetle, spotted wing drosophila) will be monitored and controlled, if necessary.

Weeds

- Noxious weeds will not be tolerated and shall be removed from the sight wherever possible.
- Frequent mowing between rows shall be used to reduce weed competition.
- Invasive weeds may be somewhat tolerated, but shall be controlled through cultural and mechanical methods.

11 Agricultural Areas

Vertebrates

- Bird depredation may be managed with the use of a scare device (usually audio).
- Bellevue Parks does not currently have depredation problems with deer or other large ungulates.
- Rodent depredation is generally tolerated on farm fields, but shall be monitored and controlled if necessary.

11.5 Training

Full and part time crew personnel will be trained on all mowing and weed eating operations as well as correct pruning techniques.



Glossary of Terms

Agricultural Area – An area set aside for the use of growing and producing a crop.

As-built drawings – Final drawings of the actual installation of structures, materials and equipment.

Biological Control – The use of biological agents, such as insects, to control weeds.

Block – A designated number of rows of typically similar crop cultivars.

Caliper – An instrument for determining the diameter of a tree.

Call-Before-You-Dig – A statewide system that allows contractors to locate underground utilities before construction. This contact is mandatory. The phone number is **1-800-424-5555** or **811** (account #34476).

Catch Basin – A reservoir for collecting surface drainage or runoff. Most catch basins have some storage capacity in the bottom to trap sediments, debris and other particles that can settle out of stormwater.

Certified Arborist – An individual who has demonstrated knowledge and competency through obtainment of the current International Society of Arboriculture arborist certification, or who is a member of the American Society of Consulting Arborists.

Certified Forester – An individual who has a professional degree from an accredited forestry program and has demonstrated the education and knowledge required by the Society of American Foresters (SAF) to be certified through the SAF Certified Forester Program.

Chemical Control – The use of pesticides, both pre-and post-emergent.

Clean Green – Refers to various plant debris such as leaves, pruned limbs, etc. that has not been contaminated with garbage and is suitable for recycling and composting.

City's Storm Drainage System – A conveyance, or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, manmade channels, or storm drains) that are owned by the City or used for collecting or conveying stormwater; which is not combined with sewer; and which is not part of a publicly owned treatment works (POTW).

Compaction – An increase in the density of something, through the act of crushing or compressing.

Construction Site Management – Refers to the management of construction activities during three phases of site development: pre-construction, construction, and post-development. These include BMP's for erosion control, shrubs, trees, drainage patterns and irrigation systems. Tree preservation is a special concern during construction because tree roots can often extend throughout an entire site, and mature trees increase property value.

Courtesy strips – Hard surface strips running parallel to the curb that provide a place for motorists to exit without stepping in the planter strip.

Critical Root Zone (CRZ) – Commonly defined as the area between the tree trunk and the outer edge of a tree's canopy, or drip line, where the majority of primary, or critical, roots reside. However, it is important to recognize that root systems vary in depth and spread based on the size of the tree, species, soil conditions, water table and other related factors. A commonly accepted method of calculating the outer edge of the CRZ is by multiplying the measured DBH by 12.

Crop – A cultivated plant or agricultural good that produces a yield in a particular season.

Cultivar – A race or variety of a plant that has been created or selected intentionally, from a natural species, and maintained through cultivation. Varieties are created to enhance a specific

characteristic, such as the fruit size, disease resistance, ability to withstand frost, color, etc.

Developmental Services Division (DSD) – City department that establishes land use and zoning guidelines, provides code enforcement, issues permits and provides inspections for construction, renovation and enhancement projects.

Diameter at Breast Height (DBH) – The diameter of the tree trunk at four and one-half feet (or 54 inches) above natural grade level. The diameter may be calculated by using the following formula: $DBH = \text{circumference at 4.5-feet} \div 3.14$. To determine the DBH of multi-trunk trees or measuring trees on slopes, consult the current *Guide for Plant Appraisal*, published by the Council of Tree and Landscape Appraisers.

Disease Control – The maintenance of healthy plants accomplished by good cultural practices.

Easements – BCC 14.60 defines an “easement” as a “grant of an interest in land by the property owner for a designated use by another person or entity or the public in general.” See “Right-of-Way.”

Edging – Grass removal along the edges of turf areas.

Evapotranspiration – The sum of water lost from the soil surface (evaporation) and the amount of water used by the plant (transpiration).

Geotextile fabric – A synthetic woven fabric used to reinforce and support surface materials and enhance drainage.

Grade – The degree of inclination of the trail surface, measured from ground/base level. Grade also relates to the degree of trail side slope.

Harvester – Machine used for the mechanical harvest of crop, specifically blueberries.

Hazardous Tree – A tree that possesses a structural defect which poses an imminent risk if the tree or part of the tree could fall on someone or something of value (target).

Fertilizing – The use of organic or inorganic materials to adjust fertility levels in the soil.

Formal Beds – Planting beds that may include ornamentals, annuals and perennials as part of a landscape design. Formal beds are often irrigated.

Informal Beds – Planting beds that may include native plantings without a formalized landscape design. Informal beds are often not irrigated.

Insect Control – The suppression or eradication of harmful insects in the landscape.

Integrated Pest Management – A decision-making process to determine if, where, when and how pest problems will be managed. An IPM program includes all potential pest control strategies, but focuses on non-chemical controls whenever possible, in order to perpetuate a sustainable environment.

Irrigation – The supply of water to plantings, either through automatic irrigation systems or manual systems.

Low-impact-development (LID) – A set of principles and design strategies that emphasize conservation, use of on-site natural features and site planning to minimize impervious surfaces, native vegetation loss and stormwater runoff.

Manual or Mechanical Control – The use of hand and power tools to remove unwanted vegetation.

Monitor Tree – A tree that, because of its value, warrants further monitoring to determine an appropriate management strategy.

MSDS – Material Safety Data Sheets or MSDS are prepared by manufacturers of chemical products to relay the necessary safety and protective information to users about the said chemical compounds.

Mulch Mowing – Grass clippings left after mowing, that provide nutrients and organic matter to the soils.

National Pollutant Discharge Elimination System (NPDES) – Permitting program that is a requirement of the federal Clean Water Act, which is intended to protect and restore waters for “fishable, swimmable” uses. The Federal Environmental Protection Agency (EPA) has delegated permit authority to state environmental agencies. In Washington, the NPDES-delegated

permit authority is the Washington State Department of Ecology (DOE).

Nursery – A facility for the propagation, growing and storage of plants for use on developed and undeveloped park property.

Pest – The word "pest" has been broadly defined in this document to include "injurious" insect species, plant pathogens, noxious or invasive vegetation, vertebrate animals such as rodents, structural pests or any other factor that creates an unhealthy environment for landscapes and structures.

Pesticide – Any material including agricultural chemicals, herbicides, insecticides and fungicides, or biological agents applied to a target pest as a control measure.

Planting Beds – Planting beds are non-turf, planted areas that include woody plant material such as shrubs, trees and ground covers. Planting beds also include floral color displays containing herbaceous plants such as perennials, annuals and bulbs.

Plant Materials – All living plants used in landscape design, including grasses, groundcover, flowers, vines, shrubs and trees.

Poly-house or Shade House – Terms for greenhouse-type structure that provides a minimal level of cold weather or sun protection required by nursery crops.

Project Arborist – Depending on the situation, the role of Project Arborist as determined by the City may be filled by any number of people, including City staff, ISA or SAF certified staff from third party companies, or qualified staff from landscape architect firms.

Project Manager – Refers to either the person assigned to the construction project by the department or the contractor who is responsible for managing the overall project. Project management duties include schedule, budget and related logistics, including construction site management.

Right-of-Way – Public land that is open to the general public. In the Definitions section of the Transportation Development Code, BCC 14.60, a Right-of-Way is defined as: "All public streets and

property dedicated to public use for streets together with public property reserved for public utilities, transmission lines and extensions, walkways, sidewalks, bikeways or equestrian trails."

Root Buffer – A temporary layer of material to protect the soil texture and roots. The buffer shall consist of a base course of wood chips spread over the root area to a minimum of 6-inch depth, capped by a layer of 3/4-inch quarry gravel to stabilize 3/4-inch plywood on top.

Row – Straight line of crops placed next to each other possibly designated with a number for easy identification and placement.

Senior Gardening Staff – Resource management staff person responsible for managing the nursery. Senior gardeners are "journey-level" positions, possessing a broad range of horticultural knowledge and skills.

Sensitive Area – An area mapped or defined in the City of Bellevue Sensitive Area Notebook as a sensitive area including areas of special flood hazard, wetlands, riparian corridors and slopes equal to or exceeding 15 percent.

Setback – The distance which a building or other structure is set back from another object deemed to need protection, such as a utility, viewshed, right-of-way or property line.

Significant Tree – A healthy evergreen or deciduous tree, 8" in diameter or greater, measured four feet above existing grade (LUC 20.50.046).

Snag – Any standing dead tree.

Soil Compaction – The compression of soil particles that may result from the movement of heavy machinery and trucks, storage of construction materials, structures, paving, etc. within the *tree protection zone*. Soil compaction can result in atrophy of roots and potential death of the tree, with symptoms often taking 3 to 10 years to manifest.

Stormwater Pollution Prevention Plan (SWPPP) – Provides recommendations on how to reduce pollutants in storm water discharges to comply with the National Pollutant Discharge Elimination Systems (NPDES).

Street Frontage – Any part of private or public property which borders a public street or includes a right-of-way easement (BCC 14.60).

Street Tree – Any tree or large shrub growing within the public right-of-way or easement. A Right-of-Way Use Permit from the City of Bellevue Transportation Department is required prior to any work on or around these trees.

Synthetic Turf – Artificial grass, or synthetic turf, is a man-made product manufactured to look like natural grass. Artificial grass is a carpet-like material used for a variety of indoor and outdoor surfaces, and is made of recycled or synthetic material.

Target – A term used to include people, vehicles, structures or something subject to damage by a tree. A tree cannot be a hazard if a target is absent within the falling distance of a tree or its parts. A defective tree in a non-populated area away from pathways may not be considered a hazard.

Temporary Erosion & Sedimentation Control (TESC) – Any temporary measures taken to reduce erosion; control siltation and sedimentation; and ensure that sediment-laden water does not leave the site.

Threshold (IPM) – The point at which pest injury can no longer be tolerated without compromising the health or aesthetic value of a plant, ecosystem or other assets of value including human health. Once a threshold is being approached, some control measure may be necessary to suppress pest activity to acceptable levels.

Topping – The reduction of a tree's size using heading cuts that shorten limbs or branches back to a predetermined crown limit.

Trail – Refers to a marked or beaten path, going through or connecting destinations.

Tree Appraisal – A method of determining the monetary value of a tree as it relates to the real estate value of the property, neighborhood or community. When required, a *certified arborist* or forester determines the appraisal by adjusting a tree's basic value by its condition, location and species using the most recent edition of the *Guide for Plant Appraisal*, published by the Council of Tree and Landscape Appraisers.

Tree Protection Fencing – A temporary enclosure erected around a tree to be protected at the boundary of the *tree protection zone*. Tree protection fencing should consist of five or six foot high chain link (or construction) fence, mounted on two inch diameter galvanized iron posts, driven into the ground to a depth of at least 2-feet at no more than 10-foot spacing. The fence serves three primary functions: 1) to keep the crown, branch structure and trunk clear from direct contact and damage by equipment, materials or disturbances; 2) to preserve roots and soil in an intact and non-compacted state; and 3) to identify the tree protection zone in which no soil disturbance is permitted and activities are restricted.

Tree Protection Zone (TPZ) – The area of ground around the base of the tree, as determined by tree species, size, condition, site history and soil conditions, deemed necessary to ensure the safety and health of the tree during and after construction. As a general guideline, the TPZ should be 1 foot diameter for each inch of trunk diameter. This distance may be increased for older trees with moderate to poor construction tolerances.

Trenching – Any excavation to provide irrigation, install foundations, utility lines, services, pipe, drainage or other property improvements below grade.

Trimming – Mowing and grass removal in areas that cannot be accessed by large riding mowers.

Turf – Any lawn or grasses grown in developed parks, streetscapes or public facilities. Turf areas vary widely in type of use from highly maintained athletic fields and golf courses to rough mow areas.

U-pick – Refers to the act of letting the customers pick the amount or type of produce desired. This reduces farm labor costs, assists with bird control, allows for more even ripening and provides a recreational opportunity.

Vertical Mulching – Auguring, hydraulic or air excavation of vertical holes within a tree's root zone to loosen and aerate the soil, typically to mitigate compacted soil. Holes are typically penetrated 4 to 6 feet on center, 2 to 3 feet deep, 2 to 6 inches in diameter and backfilled with either perlite, vermiculite, peat moss or a mixture thereof.

Weed Control – The control of undesirable plant species.

Water Management – Term for the efficient use of supplemental irrigation water required for most landscapes in the Puget Sound region.

Warning Sign – A warning sign shall be prominently displayed on each fence. The sign shall be a minimum of 8.5 x 11-inches and clearly state: "WARNING – *Tree Protection Zone* - This fence shall not be removed and any injury to this or these trees is subject to penalty according to BCC 14.06.100."



References

Some of the information found in this manual has been based on materials extracted from the following sources:

- American Association of Nurserymen (AAN) - 206-789-2900
- American Society of Landscape Architects (ASLA) - www.asla.org
- City of Seattle, Department of Parks & Recreation - www.ci.seattle.wa.us/parks
- Environmental Protection Agency (EPA) - www.epa.gov
- Irrigation Association (IA) - www.irrigation.org
- King County Noxious Weed Control Board - www.kingcounty.gov
- National Arbor Day Foundation (NAF) - www.arborday.org
- National Recreation and Park Association (NRPA) - www.nrpa.org
- Society of American Foresters (SAF) - www.safnet.org
- Washington Department of Ecology (WDOE) - www.ecy.wa.gov
- Washington Department of Fish and Wildlife (WFW) - wdfw.wa.gov
- Washington Food and Drug Administration (WFDA) - www.fda.gov
- Washington State Department of Natural Resources (WDNR) - www.dnr.wa.gov

Appendix 1 - Water Shortage Response Plan

The following information details the water shortage response plan specific to sites managed by the Bellevue Parks & Community Services Department. For information regarding the citywide water shortage response plan, please see the latest version of the City of Bellevue Utilities Water Shortage Contingency Plan (WSCP).

The Bellevue Parks & Community Services Department, in cooperation with the Bellevue Utilities Department, has adopted an aggressive, pro-active response plan to meet the demands of our current regional water shortage. The actions outlined in the Parks Water Shortage Response Plan, based on practices implemented during drought conditions in 1992, 2001 and 2015, will allow the department to meet all of our conservation goals — and model desired behavior for the community. We encourage others to adopt similar procedures and conservation measures as they may apply. Together we can minimize impacts to our landscapes, and our daily lives, during these challenging times.

This water shortage response plan serves as our immediate response to the Voluntary Stage of phased curtailment of water consumption. It will reduce normal irrigation use by 15%. It allows us to protect our investment in expensive trees and shrubs, and the many benefits they provide, while dramatically reducing irrigation to turf areas.

This plan meets water conservation goals while still allowing select green spaces for the public to enjoy. It has built-in flexibility to reduce irrigation consumption should the water crisis escalate or resume typical managed irrigation should regional supplies allow. The Parks & Community Services Department will work closely with the Bellevue Utilities Department to monitor regional water supplies and respond to any changes that occur.

BACKGROUND:

The City has had an active Water Conservation Program in place for nearly 30 years. It is an integral facet of our planning processes and our Parks Capital Improvement and Renovation Plan. Historically, water conservation has been taken into careful consideration during the design and planning of all parks projects. Parks are designed to require a minimal amount of maintenance, which includes watering.

WATER USE IN PARKS:

- The Bellevue Parks & Community Services Department manages over 2,700 acres of public property. Only about 16% (445 acres) is irrigated by domestic water supply.
- Over two thirds of the parklands, native forests and wetlands, do not require watering.
- The Bellevue Golf Course is irrigated using an on-site well and reservoir system.
- Newcastle Beach Park and Clyde Beach Park are irrigated by pumping water from Lake Washington through an approved permit with the Washington State Department of Ecology.
- Irrigation at the largest park sites is efficiently controlled through a computer system linked to an on-site weather station. The system calculates the evapo-transpiration (ET) rate for any given period and delivers only the proper amount of water, eliminating waste.
- Most water features in our parks are recirculating systems.
- Plumbing fixtures in all parks – and city – facilities are low flow/low volume fixtures.

In 1992 and 2001, Bellevue found itself in the midst of a drought situation that resulted in mandatory water rationing. During those events, the Parks & Community Services Department implemented water conservation measures that resulted in a significant reduction in water consumption. Since that time, we have made many system improvements that enable us to control irrigation on plant zones and reduce the risk of tree and shrub loss in City parks and streetscapes. Initial drought response efforts will affect turf areas that are less costly to renovate than trees and shrubs. Select green spaces will still be preserved selectively throughout our system for citizens to enjoy.

The following describes in more detail the specific conditions that will apply to the four stages of the Parks & Community Services Water Shortage Response Plan.

PLAN IMPLEMENTATION

When there is notice of a drought emergency, Parks & Community Services will implement a Water Shortage Response Plan. The Parks & Community Services Department will manage the City's park resource system according to the following guidelines until the Utilities Department determines that water supplies are adequate to resume additional irrigation in parks. This plan is designed to provide flexibility to modify park irrigation usage, up or down, as the drought conditions become more or less severe.

PHASE 1 – ADVISORY STAGE

Irrigation systems will be programmed to reduce irrigation to turf and planting areas on streetscapes, utility sites and city parks except as designated below. These measures, expected to reduce system-wide water use by up to 15%, will remain in effect until the water supply forecast improves. Activated irrigation systems are proactively monitored and tested to ensure that system watering times and amounts are functioning efficiently with no breaks in underground lines. During this stage you may see irrigation systems in within the park system operating during the day time for testing and system repair.

Turf Area Exceptions: Reduced irrigation (95% of evapo-transpiration rate) at:

- Inner circle of Downtown Park
- Seven City beach parks
- Robinswood Park - lawn between house and pond, Cabana lawn
- Newly planted turf areas that are not fully established
- Athletic fields – minimal watering for safety
- Crossroads Park

PHASE II - VOLUNTARY STAGE

Irrigation systems will be programmed to reduce irrigation to turf and planting areas on streetscapes, utility sites and city parks except as designated below. These measures, expected to reduce system-wide water use an additional 10%, will remain in effect until the water supply forecast improves.

Turf Area Exceptions: Reduced irrigation (90% of evapo-transpiration rate) at:

- Inner circle of Downtown Park
- Seven City beach parks
- Robinswood Park - lawn between house and pond, Cabana lawn
- Newly planted turf areas that are not fully established
- Athletic fields – minimal watering for safety
- Crossroads Park
- The water feature at the Lake Hills Ranger station will be shut off.

New projects not under contract will be deferred.

PHASE III – MANDATORY STAGE

Phase III actions will further reduce irrigation by an appropriate percentage of the estimated total in accordance with supply forecasts. Bellevue Golf Courses - irrigate greens and tees; reduced irrigation (90% of estimated total) on fairways.

Streetscape, utility sites and park site turf area irrigation will be shut off except those sites designated below. Shrubs and trees will be irrigated by hand or with updated, efficient irrigation systems such as drip, bubbler or computer-controlled systems designed to separate turf areas from tree and shrub zones. The goal is to keep tree and shrub bed plant material alive to protect the public's investment.

In addition, water use will be reduced at park water features as designated below.

Park Water Features:

- Downtown Park - Belvedere fountain will be turned off.
- Downtown Park - Canal will remain operating (recirculating system) in order to maintain water quality. Signage advising park visitors of the new hours will be posted.
- Downtown Park - Water fall operation hours will be reduced. Signage advising park visitors of the new hours will be posted.
- Crossroad Park - the Crossroads spray park hours will be reduced. Daily operation will be from 12:00pm to 7:00pm. Signage advising park visitors of the new hours will be posted.
- Bellevue Botanical Garden - water features will operate daily from 8:00am to 4:00pm. Signage to educate park visitors about the water conservation efforts will be posted.

Turf Area Exceptions: Reduced irrigation (85% of evapo-transpiration rate) at:

- Inner circle of Downtown Park
- Seven city beach parks
- Robinswood Park - lawn between house and pond, Cabana lawn
- Newly planted turf areas that are not fully established
- Athletic fields – minimal watering for safety
- Crossroads Park
- The water feature at the Lake Hills Ranger station be shut down.

PHASE IV – EMERGENCY CURTAILMENT STAGE

During Phase IV, shrubbery and planter bed irrigation systems will be shut off and/or significantly reduced (with the exception of the collections at the Bellevue Botanical Garden). Tree irrigation will be reduced and monitored, "survival watering", with the use of manual watering or through appropriately zoned irrigation systems.


Lawn irrigation at exempted parks will be further reduced and/or shut off on an incremental basis dependent upon the severity of the water shortage and demand reduction needed, as determined by the Utilities and Parks & Community Services Departments. Further restrictions on water features will be implemented, or features will be shut off.


- Downtown Park Center Circle
- Seven City beach parks
- Robinswood Cabana area lawn
- Bellevue Botanical Garden plant collections
- Athletic field activity areas
- Crossroads International circle

CONTACTS:

Parks & Community Services Department: (425) 452-6855

Utilities Department: (425) 452-4127




 pdfelement

Appendix 2 – Standard Detail Drawings

The following inventory of standard detail drawings is up to date as of August, 2016. To obtain copies of the most current drawings, or to request the associated CAD (.dwg) file, please contact Parks & Community Services at (425) 452-6855.






City of
Bellevue

TITLE:

SIGN - PARK ENTR - LARGE

DRAWING #:	PK-SI-01
SCALE:	1/2" = 1'
REVISION DATE:	01-2011
DEPARTMENT:	PARKS




City of
Bellevue


TITLE:

SIGN - PARK ENTR - SMALL

DRAWING #:	PK-SI-02
SCALE:	3/4" = 1'
REVISION DATE:	01-2011
DEPARTMENT:	PARKS



PICNIC AREA




RESTROOM




PLAYGROUND



TRAILS



FORMAL GARDEN




BOAT LAUNCH



BASEBALL/
SOFTBALL




BASKETBALL




SOCCER



TENNIS



WATER
FEATURE




BIKE TRAILS



SWIMMING
AREA



BOATING




FISHING



SKATE PARK



COMMUNITY
CENTER




WILDLIFE




EXERCISE
EQUIPMENT




A.D.A.
ACCESSIBILITY




PHOTOGRAPHY



SITE SEEING



GOLF



BLUEBERRY
FARM

NOTE: ANY SYMBOL NOT SHOWN SHALL BE REVIEWED AND APPROVED BY BELLEVUE PARKS & COMMUNITY SERVICES BEFORE USE ON PARK ENTRY SIGNS.




City of
Bellevue

TITLE:

SIGN - PARK ENTR - APPROVED S MBOLS

DRAWING #:	PK-SI-03
SCALE:	N T S
REVISION DATE:	0 -201
DEPARTMENT:	PARKS



1'-6" RADIUS, TYP.

1/8" FLAT SHEET ALUMINUM SIGN BACKING WITH WHITE LETTERING AND LOGOS, SEE NOTES 1 AND 3

- SANDWICH SIGN IN 3/16" GROOVE CUT DOWN THE CENTER OF THE POST
- SIGN FACING IDENTICAL ON BOTH SIDES, EXCEPT ARROW
- SECURE TO POST WITH (3) EACH 1/2"x5" GALV. CARRIAGE BOLTS, NUTS AND WASHERS, RECESSED 1/2", TYP.

6x6 POST, SEE NOTE 2

(3) 1 3/4" DIA. HOLES DRILLED THROUGH POST PERPENDICULAR TO VEHICULAR TRAFFIC AT 6" INTERVALS

FINISH GRADE

UNDISTURBED NATIVE SOIL

1/2"x10" STEEL ROD THROUGH POST, TYP.

CONCRETE FOOTING

NOTES:

1. SIGN BACKING TO BE POWDER COATED TIGER "TURQUOISE BLUE" #RAL-5018 OR APPROVED EQUAL AND SHALL RECEIVE NON-REFLECTIVE ANTI-GRAFFITI LAMINATE.
2. POST TO BE PRESSURE TREATED D.F. #2 OR BETTER AND PAINTED 2 COATS "CAPE COD GRAY" OR EQUAL.
3. ALL LETTERING AND GRAPHICS TO BE "WHITE", MACHINE-CUT, NON-REFLECTIVE VINYL (3-M SCOTCHCAL #3470 OR EQUAL). "CITY OF BELLEVUE" LETTER STYLE TO BE 1 1/2" HIGH CAPS SWISS 721 BT, CURVED TO 2'-3" RADIUS (TYP.). ALL OTHER LETTERING TO BE PALATINO AND SIZED AS NECESSARY (NO SMALLER THAN 2", TYP.)
4. TEXT SHOWN IS FOR REFERENCE ONLY. FINAL TEXT TO BE DETERMINED BY BELLEVUE PARKS & COMMUNITY SERVICES. SUBMIT SIGN PROOF FOR FINAL APPROVAL PRIOR TO FABRICATION.




City of Bellevue

TITLE:

SIGN - WA WINDING HATCHET

DRAWING #:	PK-SI-04
SCALE:	1/2" = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS



- NOTES:**
1. SIGN BACKING TO BE POWDER COATED TIGER "TURQUOISE BLUE" #RAL-5018 OR APPROVED EQUAL AND SHALL RECEIVE NON-REFLECTIVE ANTI-GRAFFITI LAMINATE.
 2. POST TO BE PRESSURE TREATED D.F. #2 OR BETTER AND PAINTED 2 COATS "CAPE COD GRAY" OR EQUAL.
 3. ALL LETTERING AND GRAPHICS TO BE "WHITE", MACHINE-CUT, NON-REFLECTIVE VINYL (3-M SCOTCHCAL #3470 OR EQUAL). "CITY OF BELLEVUE" LETTER STYLE TO BE 1 1/2" HIGH CAPS SWISS 721 BT CURVED TO 1'-3" RADIUS (TYP.). ALL OTHER LETTERING TO BE PALATINO AND SIZED AS NECESSARY (NO SMALLER THAN 2", TYP.)
 4. TEXT SHOWN IS FOR REFERENCE ONLY. FINAL TEXT TO BE DETERMINED BY BELLEVUE PARKS & COMMUNITY SERVICES. SUBMIT SIGN PROOF FOR FINAL APPROVAL PRIOR TO FABRICATION.




City of Bellevue

TITLE:

SIGN - WA INDING HATCHET WITH TRAIL DIRECTIONAL SIGNS - HATCHET DETAIL

DRAWING #:	PK-SI-01A
SCALE:	1/2" = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS



NOTES:

1. SIGN BACKING TO BE POWDER COATED TIGER "TURQUOISE BLUE" #RAL-5018 OR APPROVED EQUAL AND SHALL RECEIVE NON-REFLECTIVE ANTI-GRAFFITI LAMINATE.
2. ALL LETTERING AND GRAPHICS TO BE "WHITE", NON-REFLECTIVE, DIGITAL PRINT ON 3M.
3. "CITY OF BELLEVUE" LETTER STYLE TO BE 3/8" HIGH CAPS SWISS 721 BT, CURVED TO 2" RADIUS (TYP.). TRAIL SYSTEM GRAPHICS WILL VARY. TRAIL INFORMATION TEXT TO BE 3/8" HIGH CAPS ZURICH CN BT.
4. TEXT SHOWN IS FOR REFERENCE ONLY. FINAL TEXT TO BE DETERMINED BY BELLEVUE PARKS & COMMUNITY SERVICES. SUBMIT SIGN PROOF FOR FINAL APPROVAL PRIOR TO FABRICATION.




City of
Bellevue

TITLE:

**SIGN - WA WINDING HATCHET WITH TRAIL
DIRECTIONAL SIGNS - SIGN DETAIL**

DRAWING #:	PK-SI-01-B
SCALE:	3" = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS



- 3/8" DIA. HOLE, TYP.
- MOUNT SIGN WITH 1/4" DIA. GALV. LAG SCREWS AND WASHERS, TYP.
- 1/8" FLAT SHEET ALUMINUM BACKING WITH WHITE LETTERING AND GRAPHICS, SEE NOTES 1 AND 2
- 1/4" SOLID BORDER, TYP.

NOTES:

1. SIGN BACKING TO BE POWDER COATED TIGER "TURQUOISE BLUE" #RAL-5018 OR APPROVED EQUAL AND SHALL RECEIVE NON-REFLECTIVE ANTI-GRAFFITI LAMINATE.
2. ALL LETTERING AND GRAPHICS TO BE "WHITE", MACHINE-CUT, NON-REFLECTIVE VINYL (3M SCOTCHCAL #3470 OR APPROVED EQUAL). "PARKS & COMMUNITY SERVICES" LETTER STYLE TO BE 3/8" HIGH CAPS SWISS 721 BT. ALL OTHER LETTER STYLES SHALL BE SWISS 721 BT AND SIZED AS NECESSARY (NO SMALLER THAN 3/8", TYP.).
3. TEXT & GRAPHICS SHOWN ARE FOR REFERENCE ONLY. FINAL TEXT & GRAPHICS TO BE DETERMINED BY BELLEVUE PARKS & COMMUNITY SERVICES. SUBMIT SIGN PROOF FOR FINAL APPROVAL PRIOR TO FABRICATION.




City of
Bellevue

TITLE:

SIGN - INFORMATIONAL - 12" x 18"

DRAWING #:	PK-SI-06
SCALE:	3" x 1"
REVISION DATE:	04-2010
DEPARTMENT:	PARKS



NOTES:

1. SIGN BACKING TO BE POWDER COATED TIGER "TURQUOISE BLUE" #RAL-5018 OR APPROVED EQUAL AND SHALL RECEIVE NON-REFLECTIVE ANTI-GRAFFITI LAMINATE.
2. ALL LETTERING AND GRAPHICS TO BE "WHITE", MACHINE-CUT, NON-REFLECTIVE VINYL (3M SCOTCHCAL #3470 OR APPROVED EQUAL). "PARKS & COMMUNITY SERVICES" LETTER STYLE TO BE 1/2" HIGH CAPS SWISS 721 BT. ALL OTHER LETTER STYLES SHALL BE SWISS 721 BT AND SIZED AS NECESSARY (NO SMALLER THAN 3/8", TYP.).
3. TEXT & GRAPHICS SHOWN ARE FOR REFERENCE ONLY. FINAL TEXT & GRAPHICS TO BE DETERMINED BY BELLEVUE PARKS & COMMUNITY SERVICES. SUBMIT SIGN PROOF FOR FINAL APPROVAL PRIOR TO FABRICATION.




City of
Bellevue

TITLE:

SIGN - INFORMATIONAL - 1' x 24"

DRAWING #:	PK-SI-0□
SCALE:	2" □ 1□
REVISION DATE:	0□-201□
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

SIGN - INFORMATIONAL - 24" x 24"

DRAWING #:	PK-SI-00
SCALE:	2" = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS



- 3/16"–1/4" DIA. HOLE, TYP.
- MOUNT SIGN WITH 3/4" x 1/8" DIA. SS SQUARE DRIVE WOOD SCREWS WITH FLAT RECESSED HEAD, TYP.
- 1/8" FLAT SHEET ALUMINUM BACKING WITH WHITE LETTERING AND GRAPHICS, SEE NOTES 1 AND 2
- 1/8" SOLID BORDER, TYP.

NOTES:

1. SIGN BACKING TO BE POWDER COATED TNE MEC "FJORD" #BA22 OR APPROVED EQUAL AND SHALL RECEIVE NON-REFLECTIVE ANTI-GRAFFITII LAMINATE.
2. ALL LETTERING AND GRAPHICS TO BE "WHITE", NON-REFLECTIVE DIGITAL PRINT ON 3M. "PARKS & COMMUNITY SERVICES" LETTER STYLE TO BE 3/16" HIGH CAPS SWISS 721 BT. ALL OTHER LETTER STYLES SHALL BE SWISS 721 BT AND SIZED AS NECESSARY (NO SMALLER THAN 1/8", TYP.).
3. TEXT & GRAPHICS SHOWN ARE FOR REFERENCE ONLY. FINAL TEXT & GRAPHICS TO BE DETERMINED BY BELLEVUE PARKS & COMMUNITY SERVICES. SUBMIT SIGN PROOF FOR FINAL APPROVAL PRIOR TO FABRICATION.




City of
Bellevue

TITLE:

SIGN - INFORMATIONAL - 6" x 10" - FOR BOLLARDS

DRAWING #:	PK-SI-01
SCALE:	3" = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS



3/16" - 1/4" DIA. HOLE, TYP.
 - MOUNT SIGN WITH 3/4" x 1/8" DIA. SS SQUARE DRIVE WOOD SCREWS WITH FLAT RECESSED HEAD, TYP.

1/8" FLAT SHEET ALUMINUM BACKING WITH WHITE LETTERING AND GRAPHICS, SEE NOTES 1 AND 2

1/8" SOLID BORDER, TYP.

NOTES:

1. SIGN BACKING TO BE POWDER COATED TNE MEC "FJORD" #BA22 OR APPROVED EQUAL AND SHALL RECEIVE NON-REFLECTIVE ANTI-GRAFFITII LAMINATE.
2. ALL LETTERING AND GRAPHICS TO BE "WHITE", NON-REFLECTIVE DIGITAL PRINT ON 3M. "PARKS & COMMUNITY SERVICES" LETTER STYLE TO BE 3/16" HIGH CAPS SWISS 721 BT. ALL OTHER LETTER STYLES SHALL BE SWISS 721 BT AND SIZED AS NECESSARY (NO SMALLER THAN 1/8", TYP.).
3. TEXT & GRAPHICS SHOWN ARE FOR REFERENCE ONLY. FINAL TEXT & GRAPHICS TO BE DETERMINED BY BELLEVUE PARKS & COMMUNITY SERVICES. SUBMIT SIGN PROOF FOR FINAL APPROVAL PRIOR TO FABRICATION.




City of Bellevue

TITLE:

SIGN - INFORMATIONAL - 6" x 1" - FOR BOLLARDS

DRAWING #:	PK-SI-10
SCALE:	3" x 1"
REVISION DATE:	01-2010
DEPARTMENT:	PARKS



NOTE:

1. USE 6x6 D.F. #2 OR BETTER PT POST FOR ANY SIGN THAT IS INSTALLED HIGHER THAN 6'.
2. SIGN WITH GRAPHICS SHOWN IS FOR REFERENCE ONLY.




City of Bellevue

TITLE:

SIGN - INFORMATIONAL - TYPICAL INSTALLATION

DRAWING #:	PK-SI-11
SCALE:	1" = 1'
REVISION DATE:	03-2010
DEPARTMENT:	PARKS




City of Bellevue


TITLE:

SIGN - INFORMATIONAL - TYPICAL INSTALLATION - BOLLARD

DRAWING #:	PK-SI-12
SCALE:	1" = 1'
REVISION DATE:	03-2016
DEPARTMENT:	PARKS



A-BOLLARD DETAIL (1"= 1'-0")



NOTE:
 TEXT SHOWN IS FOR REFERENCE ONLY. FINAL TEXT TO BE DETERMINED BY BELLEVUE PARKS & COMMUNITY SERVICES. SUBMIT SIGN PROOF FOR FINAL APPROVAL PRIOR TO FABRICATION.


B-SIGN DETAIL (1/2"= 1'-0")




TITLE:

SIGN - DIRECTIONAL BOLLARD

DRAWING #:	PK-SI-13A
SCALE:	AS SHOWN
REVISION DATE:	03-2016
DEPARTMENT:	PARKS



A-BOLLARD DETAIL (1"= 1'-0")



B-SIGN DETAIL (1/2"= 1'-0")

NOTE:
 TEXT SHOWN IS FOR REFERENCE ONLY. FINAL TEXT TO BE DETERMINED BY BELLEVUE PARKS & COMMUNITY SERVICES. SUBMIT SIGN PROOF FOR FINAL APPROVAL PRIOR TO FABRICATION.




City of Bellevue


TITLE:

SIGN - DIRECTIONAL BOLLARD - LAKE TO LAKE TRAIL

DRAWING #:	PK-SI-13B
SCALE:	AS SHOWN
REVISION DATE:	03-2016
DEPARTMENT:	PARKS



A-BOLLARD DETAIL (1"= 1'-0")



NOTE:
TEXT SHOWN IS FOR REFERENCE ONLY. FINAL TEXT TO BE DETERMINED BY BELLEVUE PARKS & COMMUNITY SERVICES. SUBMIT SIGN PROOF FOR FINAL APPROVAL PRIOR TO FABRICATION.

B-SIGN DETAIL (1/2"= 1'-0")




City of Bellevue


TITLE:

SIGN - DIRECTIONAL BOLLARD - MOUNTAINS TO SOUND GREENWAY TRAIL

DRAWING #:	PK-SI-13C
SCALE:	AS SHOWN
REVISION DATE:	03-2016
DEPARTMENT:	PARKS



A-BOLLARD DETAIL (1"= 1'-0")



B-SIGN DETAIL (1/2"= 1'-0")

NOTE:
TEXT SHOWN IS FOR REFERENCE ONLY. FINAL
TEXT TO BE DETERMINED BY BELLEVUE PARKS
& COMMUNITY SERVICES. SUBMIT SIGN PROOF
FOR FINAL APPROVAL PRIOR TO FABRICATION.




City of
Bellevue


TITLE:

SIGN - DIRECTIONAL BOLLARD - REMOVABLE


DRAWING #:	PK-SI-14A
SCALE:	AS SHOWN
REVISION DATE:	03-2016
DEPARTMENT:	PARKS




FRONT VIEW



SIDE VIEW



ISOMETRIC VIEW - N.T.S.



PLAN VIEW

- ① 3/8" THICK GALV. STEEL PLATE
- ② REMOVABLE PIN: 3/4" DIA. GALV. STEEL ROD
- ③ PIN RECEIVER: 1" DIA. x 1/8" THICK GALV. STEEL PIPE WITH 3/8" NOTCH TO RECEIVE PIN
- ④ (6) 5/8" DIA. HOLES
- ⑤ 1/2" DIA. HOLE TO RECIEVE PAD LOCK
- ⑥ INCISE BOLLARD 1/4" TO FIT INSIDE BRACKET




City of Bellevue


TITLE:

SIGN - DIRECTIONAL BOLLARD - REMOVABLE - SLIDE THROUGH BRACKET DETAIL


DRAWING #:	PK-SI-14B
SCALE:	1 1/2" = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS




SIDE VIEW



FRONT VIEW



ISOMETRIC VIEW - N.T.S.



PLAN VIEW

- ① 3/8" THICK GALV. STEEL PLATE
- ② 1/4"x1 1/4"x1 1/4" GALV. ANGLE IRON
- ③ 1/4"x1" GALV. STEEL BAR
- ④ 2" DIA. SCH 40 GALV. STEEL POST
- ⑤ 1/2" DIA. GALV. STEEL ROD
- ⑥ FINISHED GRADE OF HARDSURFACE PAVEMENT




City of
Bellevue

TITLE:

**SIGN - DIRECTIONAL BOLLARD - REMOVABLE -
ANCHOR DETAIL**

DRAWING #:	PK-SI-14C
SCALE:	1/2" = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS




City of Bellevue

TITLE:

SIGN - MUTT MITT DISPENSER - PARKS

DRAWING #:	PK-SI-1□
SCALE:	1" □ 1□
REVISION DATE:	0□-201□
DEPARTMENT:	PARKS




City of Bellevue

TITLE:



SIGN - MUTT MITT DISPENSER - TRAILS

DRAWING #:	PK-SI-16
SCALE:	1" = 1'
REVISION DATE:	03-2016
DEPARTMENT:	PARKS




PLAN

SEA REACH 36.5"x24.5" F CHANNEL EXTRUSION AND BACK PLATE ASSEMBLY (PRODUCT #F63TXN311), OR APPROVED EQUAL -PAINT BACK PLATE FRAME NPS BROWN, TYP.



ELEVATION



SECTION




City of Bellevue

TITLE:

SIGN - INTERPRETIVE

DRAWING #:	PK-SI-1□
SCALE:	$\frac{1}{2}$ " □ 1"
REVISION DATE:	03-2016
DEPARTMENT:	PARKS



NOTES:

1. UNLESS OTHERWISE SPECIFIED, ALL WOOD TO BE SELECT TIGHT KNOT WESTERN RED CEDAR OR APPROVED EQUAL.
2. ALL EXPOSED CEDAR AND ROUGH SAWN FIR SHEATHING TO RECEIVE TWO COATS SIKKENS PROLUXE STAIN OR APPROVED EQUAL. STAIN COLOR TO BE APPROVED BY PARKS & COMMUNITY SERVICES.
3. ALL BOLTS, NAILS, STAPLES AND HARDWARE TO BE HOT DIPPED GALVANIZED.
4. ROOF SHAPE AND MATERIALS MAY VARY TO MATCH EXISTING ONSIGHT BUILDINGS AND STRUCTURES.




City of
Bellevue

TITLE:

SIGN - 1 OR 2 SIDED KIOSK - FRONT ELEVATION

DRAWING #:	PK-SI-1A
SCALE:	3/8" = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS

NOTCH RAFTERS AT BEAMS, TYP.



2", TYP.

3/4" CHAMFER AT ALL BEAM ENDS, TYP.

10", TYP.

4'-8"

8'-9 1/2"

7'-0"

6'-6"

3'-5"

FINISH GRADE

90°

2'-0"

4"

2'-0"

12

6

4x4 CEDAR PURLIN BEAM

1/2"x12" CARRIAGE BOLT, NUT AND WASHER TO SECURE BEAMS TO POSTS, RECESSED 1/2", TYP.

KIOSK ROOF, SEE ELEVATION AND ROOF LAYOUT

4x4 CEDAR PURLIN BEAM

1x2 CEDAR TRIM AT RAKES, TYP.

EDGE FLASHING AT EAVES, TYP.

4x4 CEDAR RAFTERS, SEE ROOF LAYOUT

4x4 CEDAR ROOF SUPPORT BEAM

1/2"x9" CARRIAGE BOLT, NUT AND WASHER TO SECURE ROOF SUPPORT BEAMS TO ANGLED ROOF BRACE AND POSTS, RECESSED 1/2", TYP.

4x4 CEDAR ANGLED ROOF BRACE

1/2"x6 1/2" LAG BOLT AND WASHER TO SECURE ROOF BRACE TO POST, RECESSED 1/2", TYP.

6x6 CEDAR POST

SIMPSON CB-66 COLUMN BASE BRACKET OR APPROVED EQUAL

-SECURE BRACKET TO POST WITH (2) EA. 1/2"x6 1/2" CARRIAGE BOLT, NUT AND WASHER, TYP.

CONCRETE FOOTING

5/8" MINUS CRUSHED GRAVEL COMPACTED TO 95% DENSITY




City of Bellevue


TITLE:

SIGN - 1 OR 2 SIDED KIOSK - SIDE ELEVATION

DRAWING #:	PK-SI-1EB
SCALE:	3/8" = 1'-0"
REVISION DATE:	01-2010
DEPARTMENT:	PARKS



ROOF LAYOUT ($\frac{3}{8}$ " = 1'-0")



DISPLAY CASE PLAN ($\frac{3}{4}$ " = 1'-0")




City of
Bellevue

TITLE:

SIGN - 1 OR 2 SIDED KIOSK - ROO LA O T
 DISPLA CASE SECTION

DRAWING #:	PK-SI-1-EC
SCALE:	AS SHOWN
REVISION DATE:	0-2010
DEPARTMENT:	PARKS



NOTES:

1. UNLESS OTHERWISE SPECIFIED, ALL WOOD TO BE SELECT TIGHT KNOT WESTERN RED CEDAR OR APPROVED EQUAL.
2. ALL EXPOSED CEDAR AND ROUGH SAWN FIR SHEATHING TO RECEIVE TWO COATS SIKKENS PROLUXE STAIN OR APPROVED EQUAL. STAIN COLOR TO BE DETERMINED BY PARKS & COMMUNITY SERVICES.
3. ALL BOLTS, NAILS, STAPLES AND HARDWARE TO BE HOT DIPPED GALVANIZED.
4. ROOF SHAPE AND MATERIALS MAY VARY TO MATCH EXISTING ONSIGHT BUILDINGS AND STRUCTURES.




**City of
Bellevue**

TITLE:

SIGN - 3 SIDED KIOSK - FRONT ELEVATION

DRAWING #:	PK-SI-10A
SCALE:	3/8" = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:


SIGN - 3 SIDED KIOSK - REAR ELEVATION

DRAWING #:	PK-SI-1EB
SCALE:	3/8" = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS




- 4x4 CEDAR RAFTERS
- 4x4 CEDAR ROOF SUPPORT BEAMS BETWEEN RAFTERS
- 4x4 CEDAR SUPPORT BEAMS BETWEEN POSTS
-ANCHORED TO POSTS WITH 1/2"x5" CARRIAGE BOLT, NUT AND WASHER, RECESSED 1/2", TYP.
- KIOSK POST: (2) 3x8 CEDAR, SEE POST DETAIL
- 6" DIA. COPPER SPHERE ROOF FINIAL, TYP.
- KIOSK ROOF (BY LAYER):
 - 5/8" ROUGH SAWN FIR PLYWOOD SHEATHING, FACING DOWN, STAINED TO MATCH RAFTERS
 - 3/4" CDX PLYWOOD SHEATHING
 - #15 ROOF FELT UNDERLAYMENT
 - #1 GRADE PRE-STAINED CEDAR SHAKES/SHINGLES
 - *NO NAIL/STAPLE PROTRUSIONS THROUGH UNDERSIDE

A-ROOF LAYOUT (3/8" = 1'-0")



B-SUPPORT BRACING AT RAFTER (3/4" = 1'-0")



C-ANGLED SUPPORT BRACING AT POST (3/8" = 1'-0")




City of Bellevue

TITLE:

SIGN - 3 SIDED KIOSK - ROOF LAYOUT BRACING DETAILS

DRAWING #:	PK-SI-11C
SCALE:	AS SHOWN
REVISION DATE:	01-2011
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

SIGN - 3 SIDED KIOSK - DISPLAY CASE PLAN

DRAWING #:	PK-SI-1ED
SCALE:	3/4" = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS




City of Bellevue

TITLE:


SIGN - 3 SIDED KIOSK - POST DETAIL

DRAWING #:	PK-SI-1E
SCALE:	$\frac{3}{4}$ " = 1'
REVISION DATE:	01-2010
DEPARTMENT:	PARKS



BLUE LETTERING AND GRAPHICS ON WHITE BACKGROUND, CARSONITE TEMPLATE #17653PB

SIGN FACES (3" = 1'-0")



POST INSTALLATION (1" = 1'-0")




City of Bellevue

TITLE:

SIGN - BOUNDARY EASEMENT MARKER

DRAWING #:	PK-SI-20
SCALE:	AS SHOWN
REVISION DATE:	01-2011
DEPARTMENT:	PARKS



NOTES:

1. A.D.A. REGULATORY SIGNS SHALL BE M.U.T.C.D. #R7-801 AND #R7-801A (VAN ACCESSIBLE).
2. SIGN POST SHALL BE 2"x2" SQUARE STEEL POSTS, MIN. 14 GA. WITH 7/16" DIE-PUNCHED KNOCKOUTS ON 1" CENTERS FULL LENGTH ON ALL FOUR SIDES.
3. FOR HARD SURFACE INSTALLATIONS, CORE 4" DIA. HOLE. ANCHOR LENGTH MAY BE DECREASED TO 12".
4. POST SHALL BE ROLLED CARBON SHEET METAL STEEL, SHALL MEET REQUIREMENTS OF ASTM A653 GRADE 50, AND SHALL BE HOT DIPPED GALVANIZED IN ACCORDANCE WITH ASTM A653, G90, STRUCTURAL QUALITY GRADE 50.
5. ANCHOR SHALL HAVE FOUR 7/16" DIA. HOLES, ONE EACH SIDE, 2" FROM TOP END. ANCHOR SHALL MEET REQUIREMENTS OF ASTM A500 GRADE B AND SHALL BE HOT DIPPED GALVANIZED.
6. DRIVE RIVETS TO BE TL3806 3/8" DIA.
7. CORNER BOLTS TO BE TLCB516M
8. SIGN HEIGHT SPECIFIED ON THIS DETAIL DOES NOT APPLY TO OTHER REGULATORY SIGNS.
9. POST AND ANCHOR SPECIFICATIONS ARE BASED OFF OF BELLEVUE TRANSPORTATION STANDARD DRAWING #TE-21.




City of Bellevue

TITLE:

SIGN - PARKING LOT - ADA PARKING STALL

DRAWING #:	PK-SI-21
SCALE:	1" = 1'-0"
REVISION DATE:	01-2010
DEPARTMENT:	PARKS



NOTES:

1. SIGNS SHALL MEET ALL REQUIREMENTS AS ESTABLISHED IN THE LATEST EDITION OF THE FEDERAL HIGHWAY ADMINISTRATION'S MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (M.U.T.C.D.).
2. SIGN POST SHALL BE 2"x2" SQUARE STEEL POSTS, MIN. 14 GA. WITH 7/16" DIE-PUNCHED KNOCKOUTS ON 1" CENTERS FULL LENGTH ON ALL FOUR SIDES.
3. FOR HARD SURFACE INSTALLATIONS, CORE 4" DIA. HOLE. ANCHOR LENGTH MAY BE DECREASED TO 12".
4. POST SHALL BE ROLLED CARBON SHEET METAL STEEL, SHALL MEET REQUIREMENTS OF ASTM A653 GRADE 50, AND SHALL BE HOT DIPPED GALVANIZED IN ACCORDANCE WITH ASTM A653, G90, STRUCTURAL QUALITY GRADE 50.
5. ANCHOR SHALL HAVE FOUR 7/16" DIA. HOLES, ONE EACH SIDE, 2" FROM TOP END. ANCHOR SHALL MEET REQUIREMENTS OF ASTM A500 GRADE B AND SHALL BE HOT DIPPED GALVANIZED.
6. DRIVE RIVETS TO BE TL3806 3/8" DIA.
7. CORNER BOLTS TO BE TLCB516M
8. SIGN HEIGHT SHALL BE 6' FROM BOTTOM OF LOWER SIGN TO GRADE FOR MULTIPLE SIGNS ON ONE POST.
9. SIGN HEIGHTS SPECIFIED ON THIS DETAIL DO NOT APPLY TO A.D.A. PARKING SIGNS.
10. POST AND ANCHOR SPECIFICATIONS ARE BASED OFF OF BELLEVUE TRANSPORTATION STANDARD DRAWING #TE-21.



City of
Bellevue

TITLE:

SIGN - PARKING LOT - TYPICAL INSTALLATION

DRAWING #:	PK-SI-22
SCALE:	1" = 10'
REVISION DATE:	03-2010
DEPARTMENT:	PARKS



NOTES:

1. SIGN BACKING TO BE 1/2" PLYWOOD SHEATHING PAINTED WHITE WITH VINYL T-MOLDING EDGE AS SUPPLIED BY A-SIGN COMPANY (ASIGNCO@FRONTIER.COM).
2. LETTERING AND GRAPHICS TO BE "BLUE" MACHINE-CUT, NON-REFLECTIVE VINYL (3-M SCOTCHCAL #3470 OR EQUAL). TEXT STYLE AND SIZE WILL VARY.
3. SIGN FACING TO BE IDENTICAL ON BOTH SIDES UNLESS OTHERWISE SPECIFIED.
4. TEXT SHOWN IS FOR REFERENCE ONLY.




City of Bellevue

TITLE:

SIGN - A FRAME - MOVEABLE - SIDEWALK OR PARKING LOT DISPLAY

DRAWING #:	PK-SI-23
SCALE:	1/2" = 1'
REVISION DATE:	01-2011
DEPARTMENT:	PARKS



NOTES:

1. SIGN BACKING TO BE 1/2" PLYWOOD SHEATHING PAINTED WHITE WITH VINYL T-MOLDING EDGE AS SUPPLIED BY A-SIGN COMPANY (ASIGNCO@FRONTIER.COM).
2. LETTERING TO BE MACHINE-CUT, NON-REFLECTIVE VINYL (3-M SCOTCHCAL #3470 OR EQUAL). TEXT STYLE TO BE SWISS 721 BT OR APPROVED EQUAL. "FIELD RESERVED" TEXT TO BE BLUE. "FIELD CLOSED" TEXT TO BE RED.
3. SIGN FACING TO BE IDENTICAL ON BOTH SIDES.





City of
Bellevue

TITLE:

**SIGN - A FRAME - MOVEABLE - SPORT FIELD
RESERVED/CLOSED**

DRAWING #:	PK-SI-24
SCALE:	1" = 1'
REVISION DATE:	01-2011
DEPARTMENT:	PARKS



MILLING & DRILLING
DIMENSIONS (1 1/2" = 1'-0")

NOTES:

1. POSTS: 5'x5 1/2" DIA. ROUND POSTS MILLED FROM PINE, OR AS APPROVED BY PARKS & COMMUNITY SERVICES. END AND 90° POST HOLES TO BE DRILLED AT HALF PENETRATION, LINE (180°) POST HOLES TO BE DRILLED AT FULL PENETRATION.
2. RAILS: 10'x3 1/2" DIA. ROUND RAILS MILLED FROM PINE, OR AS APPROVED BY PARKS & COMMUNITY SERVICES.
3. ALL MATERIALS TO BE PRESSURE TREATED WITH ACQ (ALKALINE COPPER QUATERNARY COMPOUNDS) PRIOR TO SITE DELIVERY AND INSTALLATION.
4. SECURE RAILS BY DRIVING 3" WOOD SCREWS THROUGH THE BACKSIDE (SIDE FACING AWAY FROM TRAIL, PARKING LOT, ETC.) OF POSTS.
5. CHAIN LINK FABRIC TO BE 30" HIGH BLACK POLY COATED 8 GA. FINISHED WITH 9 GA. CORE, KNUCKLE SELVAGE ON TOP AND BOTTOM. SECURE TO POST WITH GALV. STAPES AT 1'-0" O.C., TYP.

ELEVATION (3/4" = 1'-0")





City of
Bellevue

TITLE:

ENCE - POST 2 RAIL - WITH ABRIC

DRAWING #:	PK-E-02
SCALE:	AS SHOWN
REVISION DATE:	02-201
DEPARTMENT:	PARKS



NOTES:

1. POSTS: 7'x5 1/2" DIA. ROUND POSTS MILLED FROM PINE, OR AS APPROVED BY PARKS & COMMUNITY SERVICES. END AND 90° POST HOLES TO BE DRILLED AT HALF PENETRATION, LINE (180°) POST HOLES TO BE DRILLED AT FULL PENETRATION.
2. RAILS: 10'x3 1/2" DIA. ROUND RAILS MILLED FROM PINE, OR AS APPROVED BY PARKS & COMMUNITY SERVICES.
3. ALL MATERIALS TO BE PRESSURE TREATED WITH ACQ (ALKALINE COPPER QUATERNARY COMPOUNDS) PRIOR TO SITE DELIVERY AND INSTALLATION.
4. SECURE RAILS BY DRIVING 3" WOOD SCREWS THROUGH THE BACKSIDE (SIDE FACING AWAY FROM TRAIL, PARKING LOT, ETC.) OF POSTS.





City of Bellevue

TITLE:

ENCE - POST 3 RAIL

DRAWING #:	PK-E-03
SCALE:	AS SHOWN
REVISION DATE:	02-201
DEPARTMENT:	PARKS



**MILLING & DRILLING
DIMENSIONS (1 1/2" = 1'-0")**

NOTES:

1. POSTS: 7'x5 1/2" DIA. ROUND POSTS MILLED FROM PINE, OR AS APPROVED BY PARKS & COMMUNITY SERVICES. END AND 90° POST HOLES TO BE DRILLED AT HALF PENETRATION, LINE (180°) POST HOLES TO BE DRILLED AT FULL PENETRATION.
2. RAILS: 10'x3 1/2" DIA. ROUND RAILS MILLED FROM PINE, OR AS APPROVED BY PARKS & COMMUNITY SERVICES.
3. ALL MATERIALS TO BE PRESSURE TREATED WITH ACQ (ALKALINE COPPER QUATERNARY COMPOUNDS) PRIOR TO SITE DELIVERY AND INSTALLATION.
4. SECURE RAILS BY DRIVING 3" WOOD SCREWS THROUGH THE BACKSIDE (SIDE FACING AWAY FROM TRAIL, PARKING LOT, ETC.) OF POSTS.
5. CHAIN LINK FABRIC TO BE 42" HIGH BLACK POLY COATED 8 GA. FINISHED WITH 9 GA. CORE, KNUCKLE SELVAGE ON TOP AND BOTTOM. SECURE TO POST WITH GALV. STAPES AT 1'-0" O.C., TYP.


ELEVATION (3/4" = 1'-0")



TITLE:

ENCE - POST 3 RAIL - WITH ABRIC

DRAWING #:	PK-E-04
SCALE:	AS SHOWN
REVISION DATE:	02-201
DEPARTMENT:	PARKS



NOTES:

1. ALL POSTS AND RAILS TO BE DOMESTICALLY MANUFACTURED SS40 MEETING ASTM F-1043-95 SPECIFICATIONS.
2. CHAIN LINK FABRIC TO BE INSTALLED FACING PARK PROPERTY OR SPORT COURT/FIELD SIDE.
3. USE INTERMEDIATE RAILS FOR FENCES 8' OR HIGHER, CENTERED IN RELATION TO OVERALL HEIGHT.
4. USE 1 3/4" OR SMALLER MESH SIZE FABRIC FOR TENNIS COURTS.
5. ALL BOLTS, NUTS, WASHERS AND MISC. PARTS SHALL BE HOT DIPPED GALVANIZED OR COLOR COATED PER SPECIFICATIONS.




**City of
Bellevue**

TITLE:

FENCE - CHAIN LINK

DRAWING #:	PK-E-0□
SCALE:	1/2" = 1' □
REVISION DATE:	02-201□
DEPARTMENT:	PARKS




City of Bellevue

TITLE:

FENCE - CHAIN LINK WITH PRIVACY SLATS

DRAWING #:	PK-E-06
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



NOTES:

1. ALL POSTS AND FRAMING TO BE DOMESTICALLY MANUFACTURED SS40 MEETING ASTM F-1043-95 SPECIFICATIONS.
2. USE MID RAIL WITHIN GATE FRAME FOR GATES 6' AND HIGHER.
3. ALL BOLTS, NUTS, WASHERS AND MISC. PARTS SHALL BE HOT DIPPED GALVANIZED OR COLOR COATED PER SPECIFICATIONS.




City of
Bellevue

TITLE:

ENCE - CHAIN LINK SINGLE SWING GATE

DRAWING #:	PK-E-0
SCALE:	1/2" = 1'
REVISION DATE:	02-201
DEPARTMENT:	PARKS



NOTES:

1. ALL POSTS AND FRAMING TO BE DOMESTICALLY MANUFACTURED SS40 MEETING ASTM F-1043-95 SPECIFICATIONS.
2. USE MID RAIL WITHIN GATE FRAME FOR GATES 6' AND HIGHER.
3. ALL BOLTS, NUTS, WASHERS AND MISC. PARTS SHALL BE HOT DIPPED GALVANIZED OR COLOR COATED PER SPECIFICATIONS.




City of
Bellevue

TITLE:

ENCE - CHAIN LINK DOUBLE SWING SERVICE GATE

DRAWING #:	PK-E-0
SCALE:	1/2" = 1'
REVISION DATE:	02-201
DEPARTMENT:	PARKS



SECTION

ELEVATION


NOTES:

1. ALL LUMBER SHALL BE PRESSURE TREATED D.F. #2 OR BETTER. TREATMENT SHALL BE CA-C (WOLMANIZED) AWP A RETENTION STANDARDS FOR APPLICABLE GROUND AND ABOVE GROUND APPLICATIONS, OR OWNER APPROVED EQUAL.
2. UNLESS OTHERWISE DIRECTED BY OWNER, INSTALL DIAGONAL BRACE RAILING (4x4) AT ALL END AND CORNER SECTIONS WITH TOP OF BRACE AT TOP OF END SECTION/CORNER.
3. USE BISCUIT JOINTS AT ALL 2x8 TOP CAP SEAMS. EASE ALL EXPOSED EDGES 1/4" RADIUS. JOINTS TO BE ALTERNATED WITH 2x4 HORIZONTAL RAIL JOINTS.
4. GRIND BOLTS FLUSH WITH HEX NUT. TREAT EXPOSED ENDS WITH RUST PROTECTING GALV. PAINT.
5. 16'x5' HOG WIRE PANELS: 0.25" DIA. GALV. ROD WIRING WITH 2"x4" MESH OPENINGS.
6. THE HEIGHT BETWEEN FINISHED GRADE AND BOTTOM RAIL SHALL BE 6" WHENEVER POSSIBLE BUT MAY BE ADJUSTED AS NECESSARY ON SLOPED GRADES TO MAINTAIN LEVEL RAILS.



TITLE:
 FENCE - BOARD WITH FABRIC - STANDARD

DRAWING #:	PK-E-00A
SCALE:	N.T.S.
REVISION DATE:	12-2010
DEPARTMENT:	PARKS



SECTION

ELEVATION

NOTES:

1. ALL LUMBER SHALL BE PRESSURE TREATED D.F. #2 OR BETTER. TREATMENT SHALL BE CA-C (WOLMANIZED) AWPA RETENTION STANDARDS FOR APPLICABLE GROUND AND ABOVE GROUND APPLICATIONS, OR APPROVED EQUAL.
2. FASTENING HARDWARE TO BE #10 WOOD SCREWS, HOT DIPPED GALVANIZED OR STAINLESS STEEL, OR APPROVED EQUAL.
3. UNLESS OTHERWISE DIRECTED BY OWNER, INSTALL DIAGONAL BRACE RAILING (4x4) AT ALL END AND CORNER SECTIONS WITH TOP OF BRACE AT TOP OF END SECTION/CORNER.
4. USE BISCUIT JOINTS AT ALL 2x6 TOP CAP SEAMS. EASE ALL EXPOSED EDGES 1/4" RADIUS.
5. 16'x5' HOG WIRE PANELS: 0.25" DIA. GALV. ROD WIRING WITH 2"x4" MESH OPENINGS, OR APPROVED EQUAL.
6. THE HEIGHT BETWEEN FINISHED GRADE AND BOTTOM RAIL SHALL BE 6" WHENEVER POSSIBLE BUT MAY BE ADJUSTED AS NECESSARY ON SLOPED GRADES TO MAINTAIN LEVEL RAILS.




City of
Bellevue

TITLE:

FENCE - BOARD WITH FABRIC - PICTURE FRAME

DRAWING #:	PK- <input type="checkbox"/> E-01B
SCALE:	N/T'S <input type="checkbox"/>
REVISION DATE:	12-2011 <input type="checkbox"/>
DEPARTMENT:	PARKS



NOTES:

1. ALL CHAMFERS ON POSTS AND RAILS SHALL BE CUT PRIOR TO PRESSURE TREATING.
2. ALL CUTS MADE IN THE FIELD SHALL BE SEALED WITH (2) COATES COPPER NAPHTHENATE WOOD PRESERVATIVE.




City of Bellevue

TITLE:

ENCE - WOODEN BALL RAIL - ELEVATION

DRAWING #:	PK-E-10A
SCALE:	3/4" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



NOTES:

1. ALL CHAMFERS ON POSTS AND RAILS SHALL BE CUT PRIOR TO PRESSURE TREATING.
2. ALL CUTS MADE IN THE FIELD SHALL BE SEALED WITH (2) COATES COPPER NAPHTHENATE WOOD PRESERVATIVE.




City of Bellevue

TITLE:

ENCE - WOODEN BOLL RAIL - SECTION

DRAWING #:	PK-E-10B
SCALE:	1" = 1'
REVISION DATE:	02-201
DEPARTMENT:	PARKS



NOTES:

1. POSTS TO BE NON-INCISED PRESSURE TREATED D.F. #2 OR BETTER. CHAMFERS AT TOP OF POSTS TO BE CUT PRIOR TO PRESSURE TREATING.
2. FENCE TRIM AND SLATS TO BE TIGHT KNOT WESTERN RED CEDAR OR APPROVED EQUAL.
3. CAP, TRIM AND SLATS (BOTH SIDES) TO RECEIVE (2) COATS SIKKENS CETAL SRD "NATURAL OAK" STAIN OR APPROVED EQUAL.
4. ALL SCREWS, NAILS AND MISC. HARDWARE USED TO FASTEN MATERIALS SHALL BE HOT DIPPED GALVANIZED.




**City of
Bellevue**

TITLE:

FENCE - WOODEN PRIVACY

DRAWING #:	PK-E-11
SCALE:	1/2" = 1'
REVISION DATE:	03-2010
DEPARTMENT:	PARKS




City of Bellevue

TITLE:

ENCE - BALL CONTROL

DRAWING #:	PK-E-12
SCALE:	N.T.S.
REVISION DATE:	02-201
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

ENCE- BALL CONTROL - STILE BACKSTOP -
SECTION

DRAWING #:	PK-E-13
SCALE:	3/16" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

FENCE - BALL CONTROL - STOLE BACKSTOP -
SECTION WITH BACKBOARD

DRAWING #:	PK-E-14
SCALE:	3/16" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of Bellevue

TITLE:

ENCE - BALL CONTROL - BACKSTOP BACKBOARD - REAR ELEVATION

DRAWING #:	PK-E-1
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

ENCE - BALL CONTROL - BACKSTOP - BACKBOARD
ANGLE IRON CONNECTION - PLAN

DRAWING #:	PK-E-1
SCALE:	$\frac{1}{4}$ " = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue


TITLE:

ENCE - BALL CONTROL - CONCRETE CURB/MOW
STRIP - PLAN

DRAWING #:	PK-E-1
SCALE:	1/2" = 1'
REVISION DATE:	02-201
DEPARTMENT:	PARKS



PLAN




City of Bellevue

TITLE:

ENCE - BALL CONTROL - BOTTOM BOARD CONNECTION

DRAWING #:	PK-E-1
SCALE:	3" = 1'
REVISION DATE:	02-201
DEPARTMENT:	PARKS

BLEACHER SDIE



INFIELD SDIE




City of
Bellevue

TITLE:

FENCE - BALL CONTROL - DUGOUT - SECTION

DRAWING #:	PK-E-20
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



OPTIONAL 3"x12" PRESSURE TREATED BACKBOARDS

4" O.D. SS40 J-STYLE LINE POSTS

1 5/8" O.D. SS40 RAILS

6 GA. CORE CHAIN LINK FABRIC ON ALL FENCING 10' AND LOWER

9 GA. CORE CHAIN LINK FABRIC ON ALL FENCING 10' AND HIGHER

2x6 PRESSURE TREATED BOTTOM BOARD (WITH BOTTOM RAIL BEHIND)




City of
Bellevue

TITLE:

FENCE - BALL CONTROL - STOLE BACKSTOP -
ELEVATION - LARGE 00 BASE PATHS T P

DRAWING #:	PK-E-24
SCALE:	3/32" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

FENCE - BALL CONTROL - STILE BACKSTOP -
ELEVATION - SMALL 60 BASE PATHS T P

DRAWING #:	PK-E-2
SCALE:	3/32" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



- DUGOUT OPENINGS WITH OPTIONAL GATE
- 2x6 PRESSURE TREATED BOTTOM BOARD (WITH BOTTOM RAIL BEHIND)
- 2 7/8" O.D. SS40 POSTS
- 1 5/8" O.D. SS40 HORIZONTAL RAILS
- 6 GA. CORE CHAIN LINK FABRIC




City of
Bellevue

TITLE:

FENCE - BALL CONTROL - WING DUGOUT
ELEVATION - LARGE 0 BASE PATHS T P

DRAWING #:	PK-E-26
SCALE:	3/32" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue


TITLE:

FENCE - BALL CONTROL - WING DUGOUT
ELEVATION - SMALL 60 BASE PATHS T P

DRAWING #:	PK-E-2
SCALE:	3/32" = 1'
REVISION DATE:	02-201
DEPARTMENT:	PARKS



SECTION



ISOMETRIC VIEW - N.T.S.




City of Bellevue


TITLE:

BOLLARD - WOOD - REMOVABLE


DRAWING #:	PK-S-01A
SCALE:	1" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




FRONT VIEW



SIDE VIEW



PLAN VIEW



ISOMETRIC VIEW - N.T.S.

- ① 3/8" THICK GALV. STEEL PLATE
- ② REMOVABLE PIN: 3/4" DIA. GALV. STEEL ROD
- ③ PIN RECEIVER: 1" DIA. x 1/8" THICK GALV. STEEL PIPE WITH 3/8" NOTCH TO RECEIVE PIN
- ④ (6) 5/8" DIA. HOLES
- ⑤ 1/2" DIA. HOLE TO RECIEVE PAD LOCK
- ⑥ INCISE BOLLARD 1/4" TO FIT INSIDE BRACKET




City of
Bellevue


TITLE:

**BOLLARD - WOOD - REMOVABLE - SLIDE THROUGH
BRACKET DETAIL**


DRAWING #:	PK-S-01B
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




SIDE VIEW



FRONT VIEW



ISOMETRIC VIEW - N.T.S.



PLAN VIEW

- ① 3/8" THICK GALV. STEEL PLATE
- ② 1/4"x1 1/4"x1 1/4" GALV. ANGLE IRON
- ③ 1/4"x1" GALV. STEEL BAR
- ④ 2" DIA. SCH 40 GALV. STEEL POST
- ⑤ 1/2" DIA. GALV. STEEL ROD
- ⑥ FINISHED GRADE OF HARDSURFACE PAVEMENT




City of
Bellevue

TITLE:

BOLLARD - WOOD - REMOVABLE - ANCHOR DETAIL

DRAWING #:	PK-S-01
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

WOOD BOLLARD - I ED

DRAWING #:	PK-S-02
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

STEEL BOLLARD - ED

DRAWING #:	PK-S-03
SCALE:	1" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




- NOTES:**
1. CONCRETE SLAB TO BE 3000 PSI MIN. BROOMED FINISH WITH 4" SMOOTH BAND AROUND PERIMETER. INSTALL CUT JOINT EVERY 4'-0" O.C., TYP.
 2. 1 1/2" ABS DRAIN LINES SHALL BE SLIGHTLY SLOPED TOWARD THE CATCH BASIN AND DRY SUMP (OR SEWER) TO PROMOTE POSITIVE DRAINAGE.
 3. WASHED ROCK DRY SUMP SIDES, TOP AND BOTTOM SHALL BE LINED WITH FILTER FABRIC.
 4. PLUMB DRAIN TO SANITARY SEWER IF AVAILABLE IN LIEU OF DRY SUMP.
 5. INSTALL 1" WILKINS 600 SERIES PRESSURE REDUCING VALVE IF WATER PRESSURE EXCEEDS 75 PSI, TYP.




TITLE:
DRINKING FOUNTAIN INSTALLATION

DRAWING #:	PK-S-000
SCALE:	1/2" = 1'-0"
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



TITLE:
DUGOUT COVER - PLAN

DRAWING #:	PK-S-000
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



NOTES:

1. ALL NAIL AND SCREW HARDWARE USED TO SECURE BOARDS, ROOFING, ETC. TO BE STAINLESS STEEL OR GALVANIZED.
2. SCREWS ATTACHING METAL ROOFING SHALL BE SET IN JOISTS, FACIA OR PURLIN. NO SCREWS SHALL BE PROTRUDING ANYWHERE ELSE. OVERLAP ROOFING PANELS AS NECESSARY TO ENSURE UNIFORMITY.
3. THE EXPOSED UNDERSIDE OF PLYWOOD SHEATHING SHALL BE STAINED WITH 2 COATS SIKKENS CETAL SRD "NATURAL OAK" STAIN.




**City of
Bellevue**

TITLE:

DUGOUT COVER - SECTION


DRAWING #:	PK-S-000
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




PLAN VIEW

NOTES:

1. ALL DIMENSIONS TO FACE OF FRAMING, UNLESS OTHERWISE SPECIFIED.
2. THE CONCRETE SLAB AND CURB SHALL BE MONOLITHIC.
3. CONCRETE REINFORCEMENT:
 - (2) #4 REBAR AT BOTTOM OF FOOTING
 - (1) #4 REBAR AT TOP OF CURB
 - WWF 6x6 W2.9xW2.9, CENTERED IN 4" SLAB
 - 1/2"x10" ANCHOR BOLTS AT 6'-0" O.C. MIN. WITH (1) BOLT AT EACH END OF WALL (12" MAX./4" MIN. FROM END OF 2x WALL PLATE) WITH 1/4"x3"x3" PLATE WASHERS AT EACH BOLT
4. DOOR HEADERS TO BE D.F. #2 6x10 WITH (2) BEARING STUDS AND 1 FULL HEIGHT STUD AT EACH END.
5. ROOF FRAMING SHALL BE 2x6 AT 24" O.C. WITH 2x6 COLLAR-TIES AND 1/2" CDX SHEATHING (SEE WALL NOTE FOR NAILING PATTERN).
6. GARAGE DOOR SHALL BE STYROFOAM INSULATED 20 GA. SECTIONAL WITH VINYL BACKING.
7. HARDWARE AND LOCK FOR METAL DOOR SHALL BE STANDARD CITY OF BELLEVUE PARKS SPECS.
8. USE SIMPSON METAL FRAMING CONNECTORS AT ALL RAFTER AND HEADER LOCATIONS.
9. ROOFING TO BE PABCO PREMIER WEATHERED WOOD (OR APPROVED EQUIVALENT) WITH RIDGE CAP AND PRE-FINISHED METAL DRIP FLASHING.
10. ALL EXTERIOR WALLS AND TRIM TO RECEIVE 2 COATS OF PRIMER AND 2 COATS OF PAINT. PRIMER TO BE BENJAMIN MOORE EXTERIOR LATEX SUPER SPEC. PAINT FOR WALLS, BATTENS AND EAVES TO BE BENJAMIN MOORE EXTERIOR BRIARWOOD. PAINT FOR TRIM TO BE BENJAMIN MOORE EXTERIOR WHITE.



FRONT ELEVATION



SIDE ELEVATION




City of
Bellevue

TITLE:

12 16 STORAGE BUILDING

DRAWING #:	PK-S-000
SCALE:	3/16" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



City of
Bellevue


TITLE:

TRASH RECYCLE RECEPTACLE INSTALLATION


DRAWING #:	PK-S-000
SCALE:	3/4" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS

STANDARD SECTION

OVERLAY SECTION



2-4" ASPHALT CONCRETE PAVEMENT PER SPECIFICATIONS
 6" MIN. BASE COURSE MATERIAL COMPACTED TO 95% DENSITY
 EXISTING COMPACTED SUBGRADE



1.5" MIN. ASPHALT CONCRETE PAVEMENT OVERLAY
 OPTIONAL PETRO-MAT LAYER
 SMOOTH EXISTING ACP LAYER
 EXISTING COMPACTED BASE COURSE MATERIAL
 EXISTING COMPACTED SUBGRADE

NOTES:

1. ASPHALT CONCRETE MIX SHALL BE HMA CLASS "B" OR APPROVED EQUAL WITH INSTALLATION TEMPERATURES RANGING BETWEEN 275°-300°F.
2. MINIMUM ASPHALT THICKNESS FOR PEDESTRIAN ONLY PATHWAYS SHALL BE 2". MINIMUM ASPHALT THICKNESS FOR PARKING LOTS, DRIVEWAYS AND PATHWAYS THAT ACCOMMODATE VEHICULAR TRAFFIC SHALL BE 4".
3. BASE COURSE MATERIAL SHALL MEET WSDOT 2-09.3(1)E STANDARDS.
4. ALL SAW CUTS MADE FOR REPAIRS/PATCHING SHALL BE VERTICAL AND IN STRAIGHT LINES. TACK ASPHALT FACES OF SAW CUTS AND SEAL ALL JOINTS WITH PG 64-22 OIL OR APPROVED EQUAL.




City of Bellevue


TITLE:

TYPICAL ASPHALT PAVEMENT SECTIONS


DRAWING #:	PK-HS-□□
SCALE:	1" □ 1□
REVISION DATE:	02-201□
DEPARTMENT:	PARKS




SECTION



FULL DEPTH EXPANSION JOINT



CONTROL JOINT



PLAN

- ① 3000 PSI CEMENT CONCRETE SLAB PER WSDOT 6-02
- ② 5/8" CRUSHED AGGREGATE PER WSDOT 9.03.9(3) COMPACTED TO 95% DENSITY
- ③ UNDISTURBED NATIVE MATERIAL
- ④ 1/2" RADIUS AT ALL PERIMETER EDGES, TYP.
- ⑤ 4" TOOLED EDGE AT ALL PERIMETER EDGES AND BOTH SIDES OF FULL DEPTH EXPANSION JOINTS, TYP.
- ⑥ 6"x6" WELDED WIRE FABRIC
- ⑦ BROOM FINISH
- ⑧ 0.5% MIN. SLOPE FOR POSITIVE DRAINAGE, 2% MAX. SLOPE FOR A.D.A. COMPLIANCE
- ⑨ 2" TOOLED EDGE AT BOTH SIDES OF CONTROL JOINTS, TYP.
- ⑩ 3/8"-1/2" RADIUS AT ALL JOINTS, TYP.
- ⑪ PREMOLDED JOINT FILLER
- ⑫ 3/8" FULL DEPTH EXPANSION JOINT AT 10'-0" O.C.
- ⑬ CONTROL JOINT CENTERED BETWEEN EXPANSION JOINTS
- ⑭ DIRECTION OF BROOM FINISH, TYP.
- ⑮ CAULK ALL FULL DEPTH EXPANSION JOINTS




City of
Bellevue

TITLE:

TYPICAL CONCRETE SLAB ON GRADE

DRAWING #:	PK-HS-□□
SCALE:	N.T.S.□
REVISION DATE:	02-201□
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

TYPICAL CONCRETE STAIRS

DRAWING #:	PK-HS-□□
SCALE:	3/4" = 1'
REVISION DATE:	02-201□
DEPARTMENT:	PARKS



NOTES:

1. ALL WELDED JOINTS TO BE GROUND SMOOTH.
2. RAIL TO BE HOT DIPPED GALVANIZED OR POWDER COATED PER SPECIFICATIONS PRIOR TO INSTALLATION IN THE FIELD.




City of
Bellevue

TITLE:

TYPICAL STEEL HAND RAILING OR CONCRETE STAIRS

DRAWING #:	PK-HS-□□
SCALE:	1/2" = 1'
REVISION DATE:	02-201□
DEPARTMENT:	PARKS



NOTES:

1. ALL MARKING PAINT SHALL BE LOW V.O.C. WATERBORNE PER WSDOT SECTION 9-34, OR APPROVED EQUAL.
2. ALL PAVEMENT MARKINGS TO BE INSTALLED IN CONFORMANCE WITH WSDOT SECTION 8-22.
3. REFERENCED "TE" DRAWINGS CAN BE FOUND AT THE FOLLOWING WEBSITE:
[HTTP://WWW.BELLEVUEWA.GOV/TRANSPORTATION-DESIGN-MANUAL-DRAWINGS.HTM](http://www.bellevuewa.gov/transportation-design-manual-drawings.htm)




**City of
Bellevue**

TITLE:

PARKING LOT - A D A RESERVED STALL

DRAWING #:	PK-HS-□□
SCALE:	3/16" □ 1"
REVISION DATE:	02-201□
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

**TYPICAL POINT OF CONNECTION SCHEMATIC
WITH MASTER VALVE OUTSIDE VAULT**

DRAWING #:	PK-IR-01
SCALE:	N.T.S.
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

TYPICAL POINT OF CONNECTION SCHEMATIC
WITH MASTER VALVE IN VAULT

DRAWING #:	PK-IR-02
SCALE:	NTS
REVISION DATE:	02-201
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

**TYPICAL POINT OF CONNECTION SCHEMATIC WITH
SEPARATE QUICK COUPLER LINE**

DRAWING #:	PK-IR-03
SCALE:	N.T.S.
REVISION DATE:	02-2010
DEPARTMENT:	PARKS





City of Bellevue

TITLE:

DOUBLE CHECK VALVE ASSEMBLY IN VALVE BOX



DRAWING #:	PK-IR-04
SCALE:	1" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



TITLE:



DOUBLE CHECK VALVE ASSEMBLY IN VAULT

DRAWING #:	PK-IR-00
SCALE:	3/4" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




TITLE: DOUBLE CHECK VALVE ASSEMBLY IN VAULT WITH AUTOMATIC CONTROL MASTER VALVE

DRAWING #:	PK-IR-06
SCALE:	3/4" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




TITLE: **DOUBLE CHECK VALVE ASSEMBLY IN VAULT WITH PRESSURE REDUCING VALVE**

DRAWING #:	PK-IR-00
SCALE:	3/4" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



TITLE:
DOUBLE CHECK VALVE ASSEMBLY IN VAULT WITH PRESSURE REDUCING VALVE AND AUTOMATIC CONTROL MASTER VALVE

DRAWING #:	PK-IR-00
SCALE:	3/4" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

PRESSURE REDUCING VALVE ASSEMBLY

DRAWING #:	PK-IR-00
SCALE:	1" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



NOTES:

1. ASSEMBLY SIZE DETERMINED BY VALVE INLET SIZE.
2. ALL THREADED FITTINGS TO RECEIVE TEFLON TAPE (3 WRAPS MIN.).




**City of
Bellevue**

TITLE:

AUTOMATIC CONTROL MASTER VALVE ASSEMBLY

DRAWING #:	PK-IR-10
SCALE:	1" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS





City of Bellevue

TITLE:

LOW SENSOR ASSEMBL

DRAWING #:	PK-IR-11
SCALE:	1" = 1'
REVISION DATE:	02-201
DEPARTMENT:	PARKS




TITLE:

COMBINED AUTOMATIC CONTROL MASTER VALVE

LOW SENSOR ASSEMBLY

DRAWING #:	PK-IR-12
SCALE:	3/4" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



NOTE: USE NO FEMALE OR MALE ADAPTERS.




City of
Bellevue

TITLE:

ISOLATION CURB VALVE ASSEMBLY

DRAWING #:	PK-IR-13
SCALE:	1" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

ISOLATION GATE VALVE ASSEMBLY

DRAWING #:	PK-IR-14
SCALE:	1" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



NOTES:

1. ASSEMBLY SIZE DETERMINED BY VALVE INLET SIZE.
2. ALL THREADED FITTINGS TO RECEIVE TEFLON TAPE (3 WRAPS MIN.).
3. ALL VALVES TO RECEIVE CHRISTY'S 2 1/4" x 2 3/4" YELLOW I.D. TAGS WITH BLACK LETTERS (BOTH SIDES) WITH CONTROLLER STATION NUMBER, OR APPROVED EQUAL.




City of
Bellevue

TITLE:

AUTOMATIC CONTROL VALVE ASSEMBLY

DRAWING #:	PK-IR-10
SCALE:	1" = 1'
REVISION DATE:	03-2010
DEPARTMENT:	PARKS



NOTES:

1. ASSEMBLY SIZE DETERMINED BY VALVE INLET SIZE.
2. ALL THREADED FITTINGS TO RECEIVE TEFLON TAPE (3 WRAPS MIN.).
3. ALL VALVES TO RECEIVE CHRISTY'S 2 1/4"x2 3/4" YELLOW I.D. TAGS WITH BLACK LETTERS (BOTH




City of
Bellevue

TITLE:

AUTOMATIC CONTROL VALVE ASSEMBLY - DRIP

DRAWING #:	PK-IR-16
SCALE:	1" = 1'
REVISION DATE:	03-2010
DEPARTMENT:	PARKS

NOTE: ASSEMBLY SIZE DETERMINED BY VALVE INLET SIZE



A-SECTION VIEW

B-PLAN VIEW



City of
Bellevue


TITLE:

**AUTOMATIC CONTROL VALVE ASSEMBLY IN VAULT
FOR SPORT FIELDS AND PARKS**

DRAWING #:	PK-IR-10
SCALE:	1/2" = 1'
REVISION DATE:	04-2010
DEPARTMENT:	PARKS

NOTES:

1. SWING ARM ASSEMBLY SIZE DETERMINED BY HEAD INLET SIZE.
2. ALL NIPPLES TO BE EXTRUDED WITH MACHINED THREADS.
3. ALL THREADED FITTINGS TO RECEIVE TEFLON TAPE (3 WRAPS MIN.).




City of
Bellevue

TITLE:

**HEAD & SWING ARM ASSEMBLY - ROTARY -
SECTION**

DRAWING #:	PK-IR-18
SCALE:	1/2" = 1'
REVISION DATE:	04-2016
DEPARTMENT:	PARKS



- NOTES:**
1. SWING ARM ASSEMBLY SIZE DETERMINED BY HEAD INLET SIZE.
 2. ALL NIPPLES TO BE EXTRUDED WITH MACHINED THREADS.
 3. ALL THREADED FITTINGS TO RECEIVE TEFLON TAPE (3 WRAPS MIN.).




TITLE:
HEAD & SWING ARM ASSEMBLY - ROTARY - PLAN

DRAWING #:	PK-IR-19
SCALE:	3" = 1'
REVISION DATE:	04-2016
DEPARTMENT:	PARKS

NOTE:

1. ALL NIPPLES TO BE EXTRUDED WITH MACHINED THREADS.
2. ALL THREADED FITTINGS TO RECEIVE TEFLON TAPE (3 WRAPS MIN.)




City of
Bellevue

TITLE:

HEAD & SWING ARM ASSEMBLY - SPRAY - SECTION

DRAWING #:	PK-IR-20
SCALE:	3" = 1'
REVISION DATE:	04-2016
DEPARTMENT:	PARKS




City of Bellevue

TITLE:

HEAD & SWING ARM ASSEMBLY - SPRAY - PLAN

DRAWING #:	PK-IR-21
SCALE:	3" = 1'
REVISION DATE:	04-2016
DEPARTMENT:	PARKS

NOTE: ALL THREADED FITTINGS TO RECEIVE TEFLON TAPE (3 WRAPS MIN.)




City of Bellevue

TITLE:

HEAD SWING ARM ASSEMBLY - SPRINKLER
TUBING ROW ONLY TYPE

DRAWING #:	PK-IR-22
SCALE:	3" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of Bellevue

TITLE:

HEAD SWING ARM ASSEMBLY - SPRAYED AT ACP SUPPORTED CURB - PLANTING BED - SECTION

DRAWING #:	PK-IR-23
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

HEAD □ SWING ARM ASSEMBLY □ - SPRAYED AT ACP
SUPPORTED CURB - PLAN

DRAWING #:	PK-IR-24
SCALE:	1/2" □ 1"
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:


□ □ ICK CO □ PLER VALVE ASSEMBL □

DRAWING #:	PK-IR-2□
SCALE:	1 1/2" □ 1□
REVISION DATE:	02-201□
DEPARTMENT:	PARKS



TITLE:
**QUICK COUPLER VALVE ASSEMBLY - PITCHING
 MOND**

DRAWING #:	PK-IR-26
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



NOTES:

1. TECHLINE RUNS SHALL NOT EXCEED 200' IN LENGTH.
2. FOR SLOPES, INSTALL CHECK VALVES EVERY 54" IN ELEVATION CHANGE.




**City of
Bellevue**

TITLE:

DRIP - TECHLINE CENTER □ EED LA □ O □ T

DRAWING #:	PK-IR-2□
SCALE:	¼" □ 1"
REVISION DATE:	02-201□
DEPARTMENT:	PARKS



NOTES:

1. TECHLINE RUNS SHALL NOT EXCEED 200' IN LENGTH.
2. FOR SLOPES, INSTALL CHECK VALVES EVERY 54" IN ELEVATION CHANGE.




City of
Bellevue

TITLE:

DRIP - TECHLINE END NEED LAOIT

DRAWING #:	PK-IR-20
SCALE:	1/4" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

DRIP - TECHLINE IRREGULAR AREA LAO T

DRAWING #:	PK-IR-2
SCALE:	1/4" = 1'
REVISION DATE:	02-201
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

DRIP - TYPICAL TECHLINE SECTION

DRAWING #:	PK-IR-30
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

DRIP - TECHLINE MANUAL FLUSH VALVE

DRAWING #:	PK-IR-31
SCALE:	3" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

DRIP - OPERATION INDICATOR

DRAWING #:	PK-IR-32
SCALE:	1½" □ 1"
REVISION DATE:	02-201□
DEPARTMENT:	PARKS




City of Bellevue

TITLE:

TYPICAL IRRIGATION TRENCH SECTION

DRAWING #:	PK-IR-33
SCALE:	1 1/2" - 1"
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



NOTES:

1. SLEEVING MATERIAL SHALL BE SCH 40 PVC PIPE AND SHALL BE LARGE ENOUGH TO ALLOW IRRIGATION PIPE AND ASSOCIATED COUPLINGS TO EASILY SLIP THROUGH SLEEVING MATERIAL, TYPICALLY 2x DIAMETER OF IRRIGATION PIPE.
2. ONLY 1 IRRIGATION PIPE PER SLEEVE, TYP.
3. USE DUCTILE IRON WHEN CROSSING UNDER HEAVILY TRAVELED ARTERIAL ROADWAYS.
4. EXTEND SLEEVING MATERIAL 18" BEYOND EDGE OF PAVEMENT.
5. PROVIDE 48" COILED SLACK WHERE CONTROL WIRES ENTER AND EXIT THE SLEEVE.




City of
Bellevue

TITLE:

TYPICAL IRRIGATION TRENCH SECTION UNDER PAVEMENT

DRAWING #:	PK-IR-34
SCALE:	1 1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



- ① STRONG BOX MODEL #SB-24SS 24" WIDE STAINLESS STEEL ENCLOSURE (UL LISTED, NEMA TYPE 3R RATED) WITH PED-24SS 12" STAINLESS STEEL RISER PEDESTAL.
- ② #CH751 RAIN BIRD KEY CORE.
- ③ STRONG BOX MODEL #QP-24 ENCLOSURE MOUNTING PAD WITH SUPPORT BASE.
- ④ FINISHED GRADE TO BE 1", OR SPECIFIED DEPTH OF MULCH PLUS 1", BELOW TOP OF MOUNTING PAD, TYP.
- ⑤ COMPACTED NATIVE SOIL.
- ⑥ 3/8" GRAVEL BACKFILL FOR DRAINS PER WSDOT 9-03.12(4)
- ⑦ CONDUIT AND WIRE FROM POWER SOURCE.
- ⑧ 2" CONDUIT FOR VALVE AND FLOW SENSOR WIRE FEED INTO IRRIGATION CONTROL PANEL.
- ⑨ DIRECT BURIAL VALVE AND FLOW SENSOR WIRES.
- ⑩ IRRIGATION CONTROL PANEL PER SPECIFICATIONS.
- ⑪ LOOP AND ZIP TIED VALVE AND FLOW SENSOR WIRES. PROVIDE A MIN. 48" OF SLACK COILED WITHIN CABINET.




**City of
Bellevue**

TITLE:

SINGLE SIDED IRRIGATION CONTROL PEDESTAL

DRAWING #:	PK-IR-3□
SCALE:	1/2" □ 1□
REVISION DATE:	02-201□
DEPARTMENT:	PARKS



- ① STRONG BOX MODEL #SB-24SS/120V STAINLESS STEEL 2 SIDED METERED ENCLOSURE (UL LISTED, NEMA TYPE 3R RATED).
- ② #CH751 RAIN BIRD KEY CORE ON IRRIGATION CONTROL SIDE.
- ③ 32"x32"x14" POURED IN PLACE CONCRETE BASE WITH 1" CHAMFERED EDGES.
- ④ FINISH GRADE TO BE 1", OR SPECIFIED DEPTH OF MULCH PLUS 1", BELOW TOP OF CONCRETE BASE, TYP.
- ⑤ COMPACTED NATIVE SOIL.
- ⑥ 5/8" MINUS CRUSHED AGGREGATE PER WSDOT 9.03.9(3) COMPACTED TO 95% DENSITY.
- ⑦ CONDUIT AND WIRE FROM POWER SOURCE FOR LINE FEED INTO METER SOCKET.
- ⑧ 2" CONDUIT FOR VALVE AND FLOW SENSOR WIRE FEED INTO IRRIGATION CONTROL PANEL.
- ⑨ DIRECT BURIAL VALVE AND FLOW SENSOR WIRES.
- ⑩ IRRIGATION CONTROL PANEL PER SPECIFICATIONS.
- ⑪ LOOP AND ZIP TIED VALVE AND FLOW SENSOR WIRES. PROVIDE A MIN. 48" OF SLACK COILED WITHIN CABINET.
- ⑫ PAD LOCK TO BE PLACED BY PUGET SOUND ENERGY AFTER METER HAS BEEN INSTALLED AND CHARGED.
- ⑬ CONTRACTOR SHALL PROVIDE ALL CONDUIT, WIRES, POLE MOUNTING BRACKETS, WEATHERHEADS AND ALL OTHER MISC. EQUIPMENT REQUIRED FOR PUGET SOUND ENERGY TO CONNECT CABINET TO POWER SOURCE AND CHARGE METER.




City of
Bellevue

TITLE:


2 SIDED IRRIGATION CONTROL PEDESTAL WITH COMMERCIAL POWER METER SOCKET

DRAWING #:	PK-IR-36
SCALE:	1/2" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



GROUND ROD LAYOUT

- ① PEDESTAL CABINET ENCLOSURE PER SPECIFICATIONS WITH CONTROLLER OR CLUSTER CONTROL UNIT (CCU).
- ② #10 AWG SOLID BARE COPPER WIRE FROM CONTROLLER (OR CCU) TO GROUNDING RODS.
- ③ COVER GROUNDING RODS WITH CARSON SPEC. GRADE 910 6" DIA. ROUND BOX (GREEN).
- ④ 5/8"x8' COPPER CLAD GROUNDING ROD. INSTALL RODS IN SOIL IN A TRIANGULAR PATTERN SPACED A MINIMUM 8'-0" APART. GROUNDING GRID TO HAVE A RESISTANCE OF 10 OHMS OR LESS.
- ⑤ #10 AWG BARE COPPER WIRE BETWEEN GROUNDING RODS.
- ⑥ BRASS WIRE CLAMP. USE SEPERATE CLAMP FOR EACH WIRE.
- ⑦ FINISHED GRADE TO BE 1", OR SPECIFIED DEPTH OF MULCH PLUS 1", BELOW TOP OF VALVE BOX.




GROUND ROD ASSEMBLY (N.T.S.)



City of Bellevue

TITLE:
IRRIGATION CONTROLLER GROUNING ROD
 LA□□T

DRAWING #:	PK-IR-3□
SCALE:	3/4" □ 1□
REVISION DATE:	02-201□
DEPARTMENT:	PARKS



NOTE: ALL COMPONENTS TO BE INSTALLED PER MANUFACTURES SPECIFICATIONS AND PER CITY OF BELLEVUE CODE. CONTROL PANEL TO BE PRE-ASSEMBLED IN A UL CERTIFIED SHOP PRIOR TO FIELD INSTALLATION.

- ① SPECIFIED RAIN BIRD ESP CONTROLLER WITH MAXICOM INTERFACE BOARD.
- ② REMOVABLE PRE-DRILLED BACKBOARD AS SUPPLIED BY THE SPECIFIED ENCLOSURE MANUFACTURER.
- ③ 3/4" DIA. UL LISTED ZINC CONDUIT NIPPLE.
- ④ 2"x4" UL LISTED ALUMINUM JUNCTION BOX WITH COVER.
- ⑤ 1/2" DIA. UL LISTED ZINC OFFSET CONDUIT NIPPLE.
- ⑥ 18"x12"x6" HOFFMAN COVER TYPE 1 ENCLOSURE, CAT. NO. ASE18X12X6NK (SHOWN WITH COVER REMOVED).
- ⑦ WIRE HARNESS(S) FROM CONTROLLER.
- ⑧ ABB ENTRELEC BAM2 0206 351.16 END STOP TERMINAL BLOCKS.
- ⑨ ABB ENTRELEC M 6/8 0115 118.11 FEED THROUGH TERMINAL BLOCKS.
- ⑩ RAIN BIRD PT3002 PULSE TRANSMITTER WITH LCD DISPLAY IN RAIN BIRD NEMACAB-NEMA ENCLOSURE.
- ⑪ (2) ABB ENTRELEC DIN 3 TS/F6 MOUNTING RAILS.
- ⑫ 4"x4" UL LISTED ALUMINUM JUNCTION BOX WITH 2-GANG ALUMINUM COVER.
- ⑬ UL LISTED PIG TAIL POWER SUPPLY CORD FROM JUNCTION BOX.
- ⑭ UL LISTED 20A 125V CLASS A GFCI OUTLET.
- ⑮ UL LISTED TYPE 3 MCOV 150V OULET.
- ⑯ 120V/60 AC POWER SOURCE IN UL LISTED 3/4" DIA. FLEXIBLE METAL CONDUIT.
- ⑰ VALVE AND FLOW SENSOR WIRES.
- ⑱ 2" DIA. UL LISTED ZINC CONDUIT HUB.
- ⑲ PROVIDE LAMINATED LABELING FOR ALL BLOCKS.
- ⑳ CALAMP VANGUARD 3000 MULTICARRIER 3G CELLULAR BROADBAND ROUTER TO BE SUPPLIED BY CONTRACTOR AND INSTALLED BY THE CITY.
- ㉑ ANTENNAPLUS AP85/19-Q-S2 TO BE SUPPLIED BY THE CONTRACTOR AND INSTALLED BY THE CITY. HOLE THROUGH WALL TO BE DRILLED BY THE CITY.




City of
Bellevue

TITLE:

IRRIGATION CONTROL PANEL WITH CELLULAR CONNECTION

DRAWING #:	PK-IR-3□
SCALE:	N.T.S.□
REVISION DATE:	02-201□
DEPARTMENT:	PARKS




NOTE: ALL COMPONENTS TO BE INSTALLED PER MANUFACTURES SPECIFICATIONS AND PER CITY OF BELLEVUE CODE. CONTROL PANEL TO BE PRE-ASSEMBLED IN A UL CERTIFIED SHOP PRIOR TO FIELD INSTALLATION.

- ① SPECIFIED RAIN BIRD ESP CONTROLLER WITH MAXICOM INTERFACE BOARD.
- ② REMOVABLE PRE-DRILLED BACKBOARD AS SUPPLIED BY THE SPECIFIED ENCLOSURE MANUFACTURER.
- ③ 3/4" DIA. UL LISTED ZINC CONDUIT NIPPLE.
- ④ 2"x4" UL LISTED ALUMINUM JUNCTION BOX WITH COVER.
- ⑤ 1/2" DIA. UL LISTED ZINC OFFSET CONDUIT NIPPLE.
- ⑥ 18"x12"x6" HOFFMAN COVER TYPE 1 ENCLOSURE, CAT. NO. ASE18X12X6NK (SHOWN WITH COVER REMOVED).
- ⑦ WIRE HARNESS(S) FROM CONTROLLER.
- ⑧ ABB ENTRELEC BAM2 0206 351.16 END STOP TERMINAL BLOCKS.
- ⑨ ABB ENTRELEC M 6/8 0115 118.11 FEED THROUGH TERMINAL BLOCKS.
- ⑩ RAIN BIRD PT3002 PULSE TRANSMITTER WITH LCD DISPLAY IN RAIN BIRD NEMACAB-NEMA ENCLOSURE.
- ⑪ TELEPHONE LINE CORD TO CONTROLLER.
- ⑫ RJ-11 PHONE JACK.
- ⑬ (2) ABB ENTRELEC DIN 3 TS/F6 MOUNTING RAILS.
- ⑭ 4"x4" UL LISTED ALUMINUM JUNCTION BOX WITH 2-GANG ALUMINUM COVER.
- ⑮ UL LISTED PIG TAIL POWER SUPPLY CORD FROM JUNCTION BOX.
- ⑯ UL LISTED 20A 125V CLASS A GFCI OUTLET.
- ⑰ UL LISTED TYPE 3 MCOV 150V OULET.
- ⑱ 120V/60 AC POWER SOURCE IN UL LISTED 3/4" DIA. FLEXIBLE METAL CONDUIT.
- ⑲ TELEPHONE WIRE FROM LAND LINE SOURCE.
- ⑳ VALVE AND FLOW SENSOR WIRES.
- ㉑ 2" DIA. UL LISTED ZINC CONDUIT HUB.
- ㉒ PROVIDE LAMINATED LABELING FOR ALL BLOCKS.



TITLE:
IRRIGATION CONTROL PANEL WITH LAND LINE CONNECTION

DRAWING #:	PK-IR-3□
SCALE:	N.T.S.□
REVISION DATE:	02-201□
DEPARTMENT:	PARKS



- ① STRONG BOX MODEL #SB-24SSW 24"x36" STAINLESS STEEL WALL MOUNT ENCLOSURE (UL LISTED, NEMA TYPE 3R RATED).
- ② #CH751 RAIN BIRD KEY CORE.
- ③ 2" CONDUIT FOR VALVE AND FLOW SENSOR WIRE FEED INTO IRRIGATION CONTROL PANEL.
- ④ CONDUIT AND WIRE FROM POWER SOURCE.
- ⑤ CONDUIT AND WIRE FROM PHONE COMMUNICATION SOURCE.
- ⑥ CONDUIT STRAPS EVERY 24" O.C., TYP.
- ⑦ HEAVY GAUGE UNISTRUT CHANNEL, CLAMPS AND HARDWARE FOR MOUNTING ENCLOSURE TO WALL, OR APPROVED EQUAL.




City of
Bellevue

TITLE:

WALL MOUNT IRRIGATION CONTROL CABINET - SINGLE DOOR

DRAWING #:	PK-IR-40
SCALE:	3/4" = 1'
REVISION DATE:	08-2015
DEPARTMENT:	PARKS




City of Bellevue


TITLE:

PLANTING - TYPICAL SHRUB

DRAWING #:	PK-IM-01
SCALE:	N.T.S.
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



PROVIDE 2 SPARE LINKS MIN. TO ALLOW FOR TENSION ADJUSTMENT



POSITION TIE WITH 1/2" MIN. CLEARANCE ON ALL SIDES OF TRUNK

STAKING PLAN

NOTES:

1. CONDUCT TREE PIT DRAINAGE TEST IN THE PRESENCE OF CITY INSPECTOR PRIOR TO PLANTING.
2. STAKING IS REQUIRED FOR TREES 5'-0" OR GREATER IN HEIGHT UNLESS OTHERWISE SPECIFIED.
3. ALTERNATIVE STAKING METHODS MAY BE ACCEPTED WITH APPROVAL OF CITY INSPECTOR.
4. 3 STAKES MAY BE REQUIRED FOR TREES WITH 3" CALIPER OR GREATER.
5. STAKES SHALL BE REMOVED NO LATER THAN 1 YEAR AFTER TREE PLANTING UNLESS OTHERWISE SPECIFIED.




City of Bellevue


TITLE:

PLANTING - TYPICAL TREE

DRAWING #:	PK-IM-02
SCALE:	N.T.S.
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



PROVIDE 2 SPARE LINKS MIN. TO ALLOW FOR TENSION ADJUSTMENT



POSITION TIE WITH 1/2" MIN. CLEARANCE ON ALL SIDES OF TRUNK

STAKING PLAN

NOTES:

1. THIS DETAIL APPLIES TO TREE PLANTINGS ON SLOPES EXCEEDING 3:1.
2. CONDUCT TREE PIT DRAINAGE TEST IN THE PRESENCE OF CITY INSPECTOR PRIOR TO PLANTING.
3. STAKING IS REQUIRED FOR TREES 5'-0" OR GREATER IN HEIGHT UNLESS OTHERWISE SPECIFIED.
4. ALTERNATIVE STAKING METHODS MAY BE ACCEPTED WITH APPROVAL OF CITY INSPECTOR.
5. 3 STAKES MAY BE REQUIRED FOR TREES WITH 3" CALIPER OR GREATER.
6. STAKES SHALL BE REMOVED NO LATER THAN 1 YEAR AFTER TREE PLANTING UNLESS OTHERWISE SPECIFIED.




City of Bellevue

TITLE:

PLANTING - TREE ON SLOPE

DRAWING #:	PK-IM-03
SCALE:	N.T.S. □
REVISION DATE:	02-2010 □
DEPARTMENT:	PARKS



NOTES:

1. LOCATE ALL UNDERGROUND UTILITIES PRIOR TO TRENCHING OPERATIONS.
2. ROOT BARRIER PRODUCT: USE PLASTIC INTERLOCKING PANELS, 18" MIN. DEPTH X 24" TYP. WIDTH X .08" MIN. THICKNESS, WITH 90° DEFLECTION RIBBING, OR OWNER APPROVED EQUAL.
3. TREATMENT OF ROOTS EXPOSED DURING CONSTRUCTION: FOR ROOTS OVER 1" IN DIAMETER, MAKE A CLEAN, STRAIGHT CUT TO REMOVE DAMAGED PORTION OF ROOT. ALL EXPOSED ROOTS SHALL BE TEMPORARILY COVERED WITH MOIST BURLAP TO PREVENT DRYING, AND COVERED WITH SOIL AS SOON AS POSSIBLE.
4. ALL PRUNING SHALL BE PERFORMED TO ANSI A300 STANDARDS.
5. CONSULT CERTIFIED ARBORIST REGARDING THINNING OF FOLIAR CANOPY.
6. ROOT PRUNING SHOULD NOT BE PERFORMED WITHIN 5 MONTHS OF LOCAL HIGH-WIND SEASON.



**City of
Bellevue**

TITLE:

PLANTING - ROOT BARRIER INSTALLATION


DRAWING #:	PK-IM-04
SCALE:	N.T.S. □
REVISION DATE:	02-201□
DEPARTMENT:	PARKS

NOTES:

1. TREE PROTECTION DURING CONSTRUCTION:
 A SIX FOOT HIGH TEMPORARY CHAIN LINK FENCE SHALL BE ERECTED AT DRIP LINE OF TREE(S) TO BE SAVED, OR A DISTANCE OF 15 FEET FROM THE TRUNK, WHICHEVER IS GREATER. THE FENCE SHALL COMPLETELY ENCIRCLE THE TREE(S). INSTALL FENCE POSTS USING BLOCKS ONLY. IF INSTALLING POSTS DIRECTLY INTO GROUND IS NECESSARY, AVOID DRIVING INTO MAJOR ROOTS. AT THE DISCRETION OF THE CITY INSPECTOR, FENCING MAY BE EXTENDED BEYOND THE DRIP LINE OR 15 FEET. THE CITY INSPECTOR MAY PERMIT ALTERNATIVE FENCING METHODS IF SITE CONDITIONS PROHIBIT THE INSTALLATION OF PIER BLOCKS (STEEP SLOPES, SOFT SOILS, ETC.).

2. TREATMENT OF ROOTS EXPOSED DURING CONSTRUCTION:
 FOR ROOTS OVER 1 INCH IN DIAMETER DAMAGED DURING CONSTRUCTION, MAKE A CLEAN STRAIGHT CUT TO REMOVE DAMAGED PORTION OF ROOT. ALL EXPOSED ROOTS SHALL BE TEMPORARILY COVERED WITH MOIST BURLAP TO PREVENT DRYING AND COVERED WITH SOIL AS SOON AS POSSIBLE.

3. WORK WITHIN THE PROTECTION FENCE SHALL BE DONE MANUALLY. NO EXCAVATION, MATERIAL STOCKPILING, VEHICULAR TRAFFIC OR STORAGE OF EQUIPMENT/MACHINERY SHALL BE ALLOWED WITHIN THE LIMIT OF THE FENCING.




**City of
Bellevue**

TITLE:

PLANTING - TREE PROTECTION

DRAWING #:	PK-IM-0□
SCALE:	N.T.S.□
REVISION DATE:	02-201□
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

PLANTING - CRITICAL ROOT ONE BENEATH
 HARDSURFACE PATHWAY

DRAWING #:	PK-IM-06
SCALE:	N.T.S.
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



NOTES:

1. PERFORATED DRAIN PIPE TO BE N-12 PLASTIC DUAL WALL WITH SMOOTH INTERIOR AND CORRUGATED EXTERIOR.
2. DEPTH OF TRENCH AND DRAIN PIPE WILL VARY DEPENDING ON SITE TOPOGRAPHY. MAINTAIN NO LESS THAN 1% SLOPE FROM TARGET DRAIN AREA TO COLLECTION LINE(S) AND/OR OUTFALL. OWNER MAY REQUEST FLOW TEST TO ENSURE POSITIVE DRAINAGE PRIOR TO FINAL ACCEPTANCE.
3. USE NO FILTER FABRIC UNLESS OTHERWISE SPECIFIED.




**City of
Bellevue**

TITLE:

TYPICAL TRENCH DRAIN

DRAWING #:	PK-IM-□□
SCALE:	1 1/2" □ 1"
REVISION DATE:	01-2016
DEPARTMENT:	PARKS



NOTES:

1. PERFORATED DRAIN PIPE TO BE N-12 PLASTIC DUAL WALL WITH SMOOTH INTERIOR AND CORRUGATED EXTERIOR. TYPICAL PIPE SPACING TO BE 15'-0" O.C. THROUGHOUT TARGET DRAIN AREA. USE 4" DIA. PLASTIC N-12 DUAL WALL SOLID PIPE FOR COLLECTION LINE(S).
2. DEPTH OF TRENCH AND DRAIN PIPE WILL VARY DEPENDING ON SITE TOPOGRAPHY. MAINTAIN NO LESS THAN 1% SLOPE FROM TARGET DRAIN AREA TO COLLECTION LINE(S) AND/OR OUTFALL. OWNER MAY REQUEST FLOW TEST TO ENSURE POSITIVE DRAINAGE PRIOR TO FINAL ACCEPTANCE.
3. USE NO FILTER FABRIC UNLESS OTHERWISE SPECIFIED.
4. TOPSOIL TO BE 60% SAND, 40% COMPOST MIX FROM OWNER APPROVED VENDOR AND SHALL BE SUFFICIENTLY COMPACTED SO TO MINIMIZE SETTLING. SOIL MAY BE SLIGHTLY BERMED ABOVE FINISHED GRADE TO ACCOUNT FOR SETTLING.
5. FARM GROWN SOD SHALL BE PERENNIAL RYE GROWN LOCALLY IN THE PACIFIC NORTHWEST REGION WITHIN A MEDIUM CONTAINING NO NETTING AND LESS THAN 15% CLAY CONTENT. SOD SHALL BE CUT FROM THE SUPPLIER'S FIELD, DELIVERED TO THE PROJECT SITE AND INSTALLED WITHIN A 48 HOUR WINDOW.
6. GRASS SEED SHALL BE A PERENNIAL RYE MIX CONTAINING NO LESS THAN 98% PURE RYEGRASS SEED AND NO MORE THAN 0.5% WEED SEED.




City of
Bellevue

TITLE:

TYPICAL SUBSURFACE DRAIN SECTION FOR
EXISTING GENERAL TRENCH AREAS

DRAWING #:	PK-IM-00
SCALE:	NTS
REVISION DATE:	10-2010
DEPARTMENT:	PARKS



NOTES:

1. PERFORATED DRAIN PIPE TO BE NDS PLASTIC FLEXIBLE CORRUGATED SINGLE WALL DELIVERED TO THE SITE IN MIN. 250 LF ROLLS. PIPE TO BE SEAMLESS PER TRENCH RUN AND INSTALLED AT 10'-0" O.C. THROUGHOUT TARGET DRAIN AREA. USE 4" DIA. PLASTIC N-12 DUAL WALL (SMOOTH INTERIOR, CORRUGATED EXTERIOR) SOLID PIPE FOR COLLECTION LINE(S).
2. TRENCHING OPERATIONS SHALL BE PERFORMED SO THAT ALL SPOILS ARE ELEVATED BY A MEANS OF CONVEYANCE AND REMOVED FROM SITE WITHOUT TURF CONTACT. ALL TRENCHING SHALL BE AN AUTOMATED ONE STEP OPERATION TO MINIMIZE SITE COMPACTION AND DISTURBANCE.
3. PIPE SHALL BE MECHANICALLY INSTALLED TO ENSURE PRECISE ENVELOP OF FILL MATERIAL AND TO ENSURE THAT PIPE INSTALLATION IS ABOVE TRENCH BOTTOM AND CENTERED BETWEEN TRENCH WALLS. BACKFILL MEDIUM TO BE COMPACTED IN LIFTS/LAYERS TO PREVENT SETTLING. PIPE PLACEMENT TO BE AN AUTOMATED ONE STEP PROCESS TO MINIMIZE SITE COMPACTION AND DISTURBANCE.
4. DEPTH OF TRENCH WILL VARY DEPENDING ON SITE TOPOGRAPHY. MAINTAIN A MIN. 8" COVER OVER ALL DRAIN PIPE. MAINTAIN NO LESS THAN 1% SLOPE FROM TARGET DRAIN AREA TO COLLECTION LINE(S). TRENCHING SHALL EMPLOY AUTOMATED LASER GUIDE TO ENSURE POSITIVE FLOW.
5. ALL INSTALLATION EQUIPMENT SHALL BE TURF RATED SO NOT TO EXCEED GROUND PRESSURE OF 15 PSI, LOADED.
6. USE NO FILTER FABRIC UNLESS OTHERWISE SPECIFIED.
7. SAND MEDIUM BACKFILL MATERIAL SHALL MEET SIEVE ANALYSIS AS ESTABLISHED BY THE UNITED STATES GOLF ASSOCIATION (USGA) STANDARDS.
8. FARM GROWN SOD SHALL BE PERENNIAL RYE GROWN LOCALLY IN THE PACIFIC NORTHWEST/BRITISH COLUMBIA REGION WITHIN A MEDIUM CONTAINING NO LESS THAN 95% SAND AND NO NETTING. SOD SHALL BE CUT FROM THE SUPPLIER'S FIELD, DELIVERED TO THE PROJECT SITE AND INSTALLED WITHIN A 48 HOUR WINDOW.
9. HYDROSEED SHALL BE A PERENNIAL RYE MIX CONTAINING NO LESS THAN 98% PURE RYEGRASS SEED AND NO MORE THAN 0.5% WEED SEED.




**City of
Bellevue**

TITLE:

**TYPICAL SUBSURFACE DRAIN SECTION FOR
EXISTING SPORT FIELD TROUSERS AREAS**

DRAWING #:	PK-IM-00
SCALE:	N.T.S.
REVISION DATE:	10-2010
DEPARTMENT:	PARKS



TYPE 1 PREPARATION SEQUENCE:

STEP	DESCRIPTION
1	SET SUBGRADE 10" BELOW FINISH GRADE.
2	REMOVE ALL DEBRIS INCLUDING STUMPS, STICKS, ROOTS AND ROCKS OVER 1" AND DISPOSE OFF SITE. ENGINEER SHALL REVIEW AND APPROVE SUBGRADE PRIOR TO PROCEEDING WITH WORK.
3	PLACE 3" DEPTH TOPSOIL AND SCARIFY TO A DEPTH OF 6".
4	INSTALL 6" DEPTH COMPACTED TOPSOIL TYPE A. COMPACT TO 85% MAXIMUM DRY DENSITY. ENGINEER SHALL REVIEW AND APPROVE TOPSOIL INSTALLATION PRIOR TO PROCEEDING WITH WORK.
5	INSTALL SEED OR 1½" DEPTH MULCH PER SPECIFICATIONS.




**City of
Bellevue**

TITLE:

TYPE 1 SOIL PREPARATION

DRAWING #:	PK-IM-□□
SCALE:	N.T.S.□
REVISION DATE:	0□-201□
DEPARTMENT:	PARKS



TYPE 2 PREPARATION SEQUENCE:

STEP	DESCRIPTION
1	EXCAVATE EX SOIL TO 18" MIN. DEPTH BELOW FINISH GRADE. AVOID UNDERMINING NEARBY FEATURES.
2	INSTALL 3" DEPTH FINE COMPOST.
3	SCARIFY TOPSOIL TO A 9" DEPTH. ENGINEER SHALL REVIEW & APPROVE SCARIFICATION PRIOR TO PROCEEDING TO STEP 4.
4	INSTALL 15" MIN. DEPTH TOPSOIL TYPE A AND REVIEW FINISH GRADE WITH ENGINEER PRIOR TO PLANTING.
5	INSTALL PLANTS, MATERIALS & IRRIGATION PER SPECIFICATIONS.
6	INSTALL 1½" DEPTH MULCH PER SPECIFICATIONS (NO WOOD CHIPS)

NOTES:

1. ALL DIMENSIONS INDICATE COMPACTED DEPTHS. TOPSOIL TYPE A & MULCH SHALL BE COMPACTED TO 85% DRY DENSITY.
2. INCREASE DEPTH OF EXCAVATION & TOPSOIL TO ACCOMODATE TREE ROOT BALL DEPTHS OF 18"-30".
3. MOUND TOPSOIL IN PLANTER STRIPS AND MEDIANS PER SPECIFICATIONS.




City of
Bellevue

TITLE:

TYPE 2 SOIL PREPARATION

DRAWING #:	PK-IM-00
SCALE:	N.T.S.
REVISION DATE:	00-2010
DEPARTMENT:	PARKS




City of Bellevue

TITLE:

TYPICAL PLANTER STRIP GRADING

DRAWING #:	PK-IM-00
SCALE:	N.T.S.
REVISION DATE:	03-2010
DEPARTMENT:	PARKS



TRAIL DIMENSIONS & MATERIALS BY TYPE:

TRAIL TYPE	TRAIL WIDTH	TOP COURSE MATERIAL & DEPTH	BASE COURSE MATERIAL
LTD. PRPS. TYPE 1	4' -6'	4" DEPTH MEDIUM WOODCHIPS/BARK	NATIVE SOIL*
LTD. PRPS. TYPE 2	4' -6'	2" DEPTH 3/8" MINUS C.R.	5/8" MINUS C.R.*
MULTI-PURPOSE	6' -10'	2" DEPTH 3/8" MINUS C.R. OR CLASS "B" ASPHALT	5/8" MINUS C.R.*
PAVED	6' -10'	2 1/2" -4" DEPTH CLASS "B" ASPHALT OR 3 1/2" -5" DEPTH CONCRETE**	5/8" MINUS C.R.
BICYCLE	10' -12'	2 1/2" -4" DEPTH CLASS "B" ASPHALT**	5/8" MINUS C.R.
EQUESTRIAN	4' -6'	4" DEPTH MEDIUM WOOD CHIPS	NATIVE SOIL

*INDICATES FILTER FABRIC BETWEEN COURSES, **INDICATES AS SPECIFIED BY CITY




City of Bellevue

TITLE:

TRAIL - DIMENSION □ MATERIAL OPTIONS

DRAWING #:	PK-TR-01
SCALE:	N.T.S. □
REVISION DATE:	02-201□
DEPARTMENT:	PARKS



NOTES:

1. ALL PLANS MUST BE APPROVED BY THE CITY PRIOR TO CONSTRUCTION OF TRAIL. TRAIL CENTERLINE TO BE STAKED IN THE FIELD BY THE CONTRACTOR AND APPROVED BY THE APPROPRIATE CITY INSPECTOR.
2. ALL HAZARD TREES AND TREE LIMBS, AS DEFINED BY THE WASHINGTON STATE DEPARTMENT OF NATURAL RESOURCES HAZARD TREE BULLETIN, SHALL BE FELLED AND REMOVED FROM SITE.
3. PROVIDE WOVEN FILTER FABRIC BETWEEN MULCH AND SUB-GRADE AS REQUIRED BY CITY.




City of
Bellevue

TITLE:

TRAIL - MULCH

DRAWING #:	PK-TR-02
SCALE:	N.T.S.
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



NOTES:

1. ALL PLANS MUST BE APPROVED BY THE CITY PRIOR TO CONSTRUCTION OF TRAIL. TRAIL CENTERLINE TO BE STAKED IN THE FIELD BY THE CONTRACTOR AND APPROVED BY THE APPROPRIATE CITY INSPECTOR.
2. ALL HAZARD TREES AND TREE LIMBS, AS DEFINED BY THE WASHINGTON STATE DEPARTMENT OF NATURAL RESOURCES HAZARD TREE BULLETIN, SHALL BE FELLED AND REMOVED FROM SITE.
3. PROVIDE WOVEN FILTER FABRIC BETWEEN BASE COURSE AND SUB-GRADE AS REQUIRED BY CITY.




**City of
Bellevue**

TITLE:

TRAIL - GRAVEL

DRAWING #:	PK-TR-03
SCALE:	N.T.S. □
REVISION DATE:	02-201□
DEPARTMENT:	PARKS



NOTES:

1. ALL PLANS MUST BE APPROVED BY THE CITY PRIOR TO CONSTRUCTION OF TRAIL. TRAIL CENTERLINE TO BE STAKED IN THE FIELD BY THE CONTRACTOR AND APPROVED BY THE APPROPRIATE CITY INSPECTOR.
2. ALL HAZARD TREES AND TREE LIMBS, AS DEFINED BY THE WASHINGTON STATE DEPARTMENT OF NATURAL RESOURCES HAZARD TREE BULLETIN, SHALL BE FELLED AND REMOVED FROM SITE.
3. ONE-WAY BIKE PATH TO BE A MINIMUM OF 8 FEET WIDE.
4. TYPICAL MULTI PURPOSE: 6'-10' PAVED PATH, 6'-10' BIKE PATH, 10'-12' TOTAL WIDTH AS SPECIFIED BY CITY.




**City of
Bellevue**

TITLE:

TRAIL - ASPHALT

DRAWING #:	PK-TR-04
SCALE:	N.T.S. □
REVISION DATE:	02-201□
DEPARTMENT:	PARKS



NOTES:

1. ALL PLANS MUST BE APPROVED BY THE CITY PRIOR TO CONSTRUCTION OF TRAIL. TRAIL CENTERLINE TO BE STAKED IN THE FIELD BY THE CONTRACTOR AND APPROVED BY THE APPROPRIATE CITY INSPECTOR.
2. ALL HAZARD TREES AND TREE LIMBS, AS DEFINED BY THE WASHINGTON STATE DEPARTMENT OF NATURAL RESOURCES HAZARD TREE BULLETIN, SHALL BE FELLED AND REMOVED FROM SITE.
3. MAINTAIN MIN. 2'-0" CLEARANCE FROM ADJACENT TREE TRUNKS AND 7'-0" HEIGHT CLEARANCE FROM BOTTOM TREE BRANCHES TO TOP OF TRAIL SURFACE.



City of
Bellevue


TITLE:

TRAIL - ON SLOPE

DRAWING #:	PK-TR-0□
SCALE:	N.T.S.□
REVISION DATE:	02-201□
DEPARTMENT:	PARKS

NOTES:

1. STAIR TIMBERS TO BE HEM-FIR #2 OR BETTER WITH ROUGH SAWN WALKING SURFACE, WOLMANIZED NATURAL SELECT® WOOD TREATED WITH .21 PCF CA-B OR .15 PCF CA-C, OR APPROVED EQUAL.
2. ALL CUTS MADE IN THE FIELD SHALL BE TREATED WITH COPPER NAPHTHENATE WOOD PRESERVATIVE.



PLAN

SECTION




City of
Bellevue

TITLE:

TRAIL - TIMBER STAIRS


DRAWING #:	PK-TR-06
SCALE:	3/4" = 1'
REVISION DATE:	02-2010
DEPARTMENT:	PARKS



NOTES:

1. LANDING TIMBERS TO BE HEM-FIR #2 OR BETTER WITH ROUGH SAWN WALKING SURFACE, WOLMANIZED NATURAL SELECT® WOOD TREATED WITH .21 PCF CA-B OR .15 PCF CA-C, OR APPROVED EQUAL.
2. ALL CUTS MADE IN THE FIELD SHALL BE TREATED WITH COPPER NAPHTHENATE WOOD PRESERVATIVE.

SECTION



PLAN




City of
Bellevue

TITLE:

TRAIL - TIMBER STAIR LANDING

DRAWING #:	PK-TR-0□
SCALE:	1/2" □ 1"
REVISION DATE:	02-201□
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

TRAILS - BOLLARD - WOOD - FIXED

DRAWING #:	PK-TR-08
SCALE:	1" = 1'
REVISION DATE:	03-2016
DEPARTMENT:	PARKS



City of
Bellevue



TITLE:

TRAILS - BOLLARD - WOOD - REMOVAL

DRAWING #:	PK-TR-09
SCALE:	1" = 1'
REVISION DATE:	03-2016
DEPARTMENT:	PARKS

NOTES:

1. THE DISTANCE FROM HOME PLATE TO 1ST AND 3RD BASE IS TO BE MEASURED FROM THE BACK POINT OF HOME PLATE TO THE BACK EDGE OF THE BASES.
2. THE DISTANCE FROM HOME PLATE TO 2ND BASE IS TO BE MEASURED FROM THE BACK POINT OF HOME PLATE TO THE CENTER OF 2ND BASE. THE DISTANCE FROM 2ND BASE TO 1ST AND 3RD BASE IS TO BE MEASURED FROM THE CENTER OF 2ND BASE TO THE OUTER EDGE OF THE FOUL LINES.
3. THE DISTANCE FROM HOME PLATE TO THE PITCHING RUBBER IS TO BE MEASURED FROM THE BACK POINT OF HOME PLATE TO THE FRONT OF THE RUBBER. THE RUBBER IS TO BE CENTERED IN LINE WITH THE BACK POINT OF HOME PLATE AND THE FRONT CORNER OF 2ND BASE.
4. THE FOUL LINE IS TO BE IN FAIR PLAY AND GO THROUGH 1ST AND 3RD BASE.
5. THE OUTFIELD ARC (GRASS EDGE) IS TO BE MEASURED FROM THE FRONT CENTER OF THE PITCHING RUBBER.



City of
Bellevue



TITLE:

SKINNED BASEBALL - 60" BASE DIMENSIONS

DRAWING #:	PK-SP-01
SCALE:	N.T.S.
REVISION DATE:	02-2010
DEPARTMENT:	PARKS

NOTES:

1. THE DISTANCE FROM HOME PLATE TO 1ST AND 3RD BASE IS TO BE MEASURED FROM THE BACK POINT OF HOME PLATE TO THE BACK EDGE OF THE BASES.
2. THE DISTANCE FROM HOME PLATE TO 2ND BASE IS TO BE MEASURED FROM THE BACK POINT OF HOME PLATE TO THE CENTER OF 2ND BASE. THE DISTANCE FROM 2ND BASE TO 1ST AND 3RD BASE IS TO BE MEASURED FROM THE CENTER OF 2ND BASE TO THE OUTER EDGE OF THE FOUL LINES.
3. THE DISTANCE FROM HOME PLATE TO THE PITCHING RUBBER IS TO BE MEASURED FROM THE BACK POINT OF HOME PLATE TO THE FRONT OF THE RUBBER. THE RUBBER IS TO BE CENTERED IN LINE WITH THE BACK POINT OF HOME PLATE AND THE FRONT CORNER OF 2ND BASE.
4. THE FOUL LINE IS TO BE IN FAIR PLAY AND GO THROUGH 1ST AND 3RD BASE.
5. THE OUTFIELD ARC (GRASS EDGE) IS TO BE MEASURED FROM THE FRONT CENTER OF THE PITCHING RUBBER.



City of
Bellevue



TITLE:

SKINNED BASEBALL - 10" BASE DIMENSIONS

DRAWING #:	PK-SP-02
SCALE:	N.T.S.
REVISION DATE:	02-2010
DEPARTMENT:	PARKS

NOTES:

1. THE DISTANCE FROM HOME PLATE TO 1ST AND 3RD BASE IS TO BE MEASURED FROM THE BACK POINT OF HOME PLATE TO THE BACK EDGE OF THE BASES.
2. THE DISTANCE FROM HOME PLATE TO 2ND BASE IS TO BE MEASURED FROM THE BACK POINT OF HOME PLATE TO THE CENTER OF 2ND BASE. THE DISTANCE FROM 2ND BASE TO 1ST AND 3RD BASE IS TO BE MEASURED FROM THE CENTER OF 2ND BASE TO THE OUTER EDGE OF THE FOUL LINES.
3. THE DISTANCE FROM HOME PLATE TO THE PITCHING RUBBER IS TO BE MEASURED FROM THE BACK POINT OF HOME PLATE TO THE FRONT OF THE RUBBER. THE RUBBER IS TO BE CENTERED IN LINE WITH THE BACK POINT OF HOME PLATE AND THE FRONT CORNER OF 2ND BASE.
4. THE FOUL LINE IS TO BE IN FAIR PLAY AND GO THROUGH 1ST AND 3RD BASE.
5. THE OUTFIELD ARC (GRASS EDGE) IS TO BE MEASURED FROM THE FRONT CENTER OF THE PITCHING RUBBER.




City of
Bellevue

TITLE:

SKINNED SOFTBALL - 60 BASE DIMENSIONS

DRAWING #:	PK-SP-03
SCALE:	N.T.S.
REVISION DATE:	02-2010
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:

STANDARD BASE □ ANCHOR INSTALLATION

DRAWING #:	PK-SP-04
SCALE:	1 1/2" □ 1"
REVISION DATE:	02-201□
DEPARTMENT:	PARKS




City of
Bellevue

TITLE:


SA□ET□ SLIDE BASE □ ANCHOR INSTALLATION

DRAWING #:	PK-SP-0□
SCALE:	1 1/2" □ 1□
REVISION DATE:	02-201□
DEPARTMENT:	PARKS



7/8" x 40" x 50" POROUS RUBBER MATTING WITH BEVELED EDGES
 -USE A TOTAL OF 5 SHEETS FOR BATTERS BOXES AND CATCHERS BOX

ISOMETRIC VIEW - EXCAVATED (N.T.S.)



SECTION (3/4" = 1'-0")




City of
Bellevue

TITLE:

BATTERS □ CATCHERS BO □ □ ORTI □ ICATION

DRAWING #:	PK-SP-06
SCALE:	AS SHOWN
REVISION DATE:	02-201□
DEPARTMENT:	PARKS

 pdfelement

